

Spur Ridge Rise New Build

Project Specification

33 Spur Ridge Rise, Jacks Point, New Zealand
Project Ref: J 292
Date: 30 September 2026

PROJECT SPECIFICATION Works, materials and workmanship for construction in accordance with the accompanying drawings.

Spec Version ID: 382217-462928
Document authenticity may be verified at masterspec.co.nz/verify/382217-462928
Prepared using Masterspec software

© CIL Masterspec Sep 2026

TABLE OF CONTENTS

1220	PROJECT	4
1232	INTERPRETATION & DEFINITIONS	6
1232S1	EXPLANATION OF SCHEDULE SECTIONS	8
1233	REFERENCED DOCUMENTS	9
1234	DOCUMENTATION	10
1237	WARRANTIES	14
1237S1	SCHEDULE OF WARRANTIES	16
1240	ESTABLISHMENT	17
1250	TEMPORARY WORKS & SERVICES	18
1270	CONSTRUCTION	21
2210	PREPARATION & GROUNDWORK	25
3820	CARPENTRY	29
4161T	KINGSPAN THERMAKRAFT UNDERLAYS, FOILS, DPC, DPM, & TAPES	33
4231HL	JAMES HARDIE® LINEA™ WEATHERBOARD CLADDING	39
4239JH	JAMES HARDIE® SOFFITS	44
4241	PROFILED METAL CLADDING	48
4311D	DIMOND PROFILED METAL ROOFING	53
4337E	ECOPLY® ROOFING & DECKING	59
4422A	ARDEX BUTYNOL & BUTYSEAL MEMBRANE ROOFING	62
4521	ALUMINIUM WINDOWS AND DOORS	68
4610	GLAZING RESIDENTIAL	75
5113G	GIB® PLASTERBOARD LININGS	79
5230	INTERIOR DOORS	85
5433E	ECOPLY® FLOORING	88
6700R	RESENE PAINTING GENERAL	91
6711R	RESENE PAINTING EXTERIOR	97
6721R	RESENE PAINTING INTERIOR	98
7120	HOT & COLD WATER SYSTEM	100
7420	SANITARY SYSTEMS	105
7430	DRAINAGE	107
7701	ELECTRICAL BASIC	110

© CIL Masterspec Sep 2026

© CIL Masterspec Sep 2026

1220 PROJECT

1 GENERAL

This general section describes the project including:

- A description of the work
- Site description, features and restrictions
- Design parameters for design by contractor
- Archaeological discovery

1.1 READ ALL SECTIONS TOGETHER

Read all general sections together with all other sections.

Description of the work

1.2 SCOPE OF THE WORK

1.3 RESTRICTED BUILDING WORK

This project includes Restricted Building Work.

Site

1.4 SITE

The site consists of: 512 m sq.
as shown on drawing no. 100

1.5 LEGAL DESCRIPTION

The site of the works, the street address and the legal description are shown on the drawings.

Site environment - Wind

1.6 WIND DESIGN PARAMETERS - NON SPECIFIC DESIGN

The design wind pressures are to NZS 3604, Table 5.4 Determination of wind zone, up to and including Extra High Wind Zone.

Building wind zone High 44 m/s :(refer to NZS 3604, table 5.4)

Site environment - Durability

1.7 EXPOSURE ZONE

The exposure zone is to NZS 3604, Section 4 Durability, 4.2 Exposure zones and NZBC E2/AS1.

The site zone is: B

Site environment - Seismic

1.8 EARTHQUAKE ZONE - NON SPECIFIC DESIGN

The zone is to NZS 3604, Section 5 Bracing design, 5.3 Earthquake bracing demand.

The earthquake zone is: 3

Archaeological discovery

1.9 ANTIQUITIES AND ITEMS OF VALUE

Report the finding of any fossils, antiquities and other items of value, to the Contract Administrator. All to remain undisturbed until approval is given for removal.

© CIL Masterspec Sep 2026

Pre-1900, items or evidence of human activity on the site, come under the Heritage New Zealand Pouhere Taonga Act 2014. If such items or evidence is discovered work must stop immediately and the Contract Administrator must be notified immediately. The site may be classified as an Archaeological Site under the Act, and the Contract Administrator or Owner must contact the Heritage New Zealand for authority to proceed.

Post-1900 items remain the property of the owner, pre-1900 items may remain the property of the owner or the Crown subject to what is found.



© CIL Masterspec Sep 2026

1232 INTERPRETATION & DEFINITIONS

1 GENERAL

This general section relates to definitions and interpretation that are used in this specification.

Definitions

1.1 DEFINITIONS

Required:	Required by the documents, the New Zealand Building Code or by a statutory authority.
Proprietary:	Identifiable by naming the manufacturer, supplier, installer, trade name, brand name, catalogue or reference number.
Provide and fix:	"Provide" or "fix" or "supply" or "fix" if used separately mean provide and fix unless explicitly stated otherwise.
Review:	Review by the contract administrator is for general compliance only. Review does not remove the need for the contractor to comply with the stated requirements, details and specifications of the manufacturers and suppliers of individual components, materials and finishes. Neither can the review be construed as authorising departures from the contract documents.
Working day:	Working day means a calendar day other than any Saturday, Sunday, public holiday or any day falling within the period from 24 December to 5 January, both days inclusive, irrespective of the days on which work is actually carried out.
Workplace:	Workplace means the place where work is being carried out, or is customarily carried out, for a business or undertaking including any place where a worker goes, or is likely to be, while at work (under Health and Safety at Work Act 2015).
Hold point:	A stage of the construction where the Contract administrator requires notice to be given that particular work is to be carried out. Work may not proceed on that particular part until the Contract administrator or other nominated person has advised that work can continue. A notice period of 2 Working Days is required unless stated otherwise.
Notification point:	A stage of the construction where the Contract administrator requires notice to be given that particular work is to be carried out. Work may continue and the Contract administrator may choose whether or not they wish to witness the particular work being carried out. A notice period of 2 Working Days is required unless stated otherwise.

1.2 PERSONNEL

Owner:	The person defined as "owner" in the New Zealand Building Code.
Principal:	The person defined as "principal" in the conditions of contract.
Contractor:	The person contracted by the principal to carry out the contract.
Contract administrator:	The person appointed by the principal to administer the contract on the principal's behalf. Where no person has been appointed by the Principal, it means the Principal or the Principal's representative.

1.3 ABBREVIATIONS

The following abbreviations are used throughout the specification:

AAMA	American Architectural Manufacturers Association
AS	Australian Standard
AS/NZS	Joint Australian/New Zealand Standard
ASTM	American Society for Testing and Materials
AWCINZ	Association of Wall and Ceiling Industries of New Zealand Inc.
BCA	Building Consent Authority
BRANZ	Building Research Association of New Zealand

© CIL Masterspec Sep 2026

BS	British Standard
COP	Code of practice
CSIRO	Commonwealth Scientific and Industrial Research Organisation
HERA	Heavy Engineering Research Association
LBP	Licensed Building Practitioner
MBIE	Ministry of Business, Innovation and Employment
MPNZA	Master Painters New Zealand Association Inc
NZBC	New Zealand Building Code
NZS	New Zealand Standard
NZS/AS	Joint New Zealand/Australian Standard
NZTA	New Zealand Transport Agency
NUO	Network Utility Operator
PCBU	Person Conducting a Business or Undertaking (under Health and Safety at Work Act 2015)
OSH	Occupational Safety and Health
TA	Territorial Authority
TNZ	Transit New Zealand (Transit New Zealand is now New Zealand Transport Agency NZTA - some specifications are still prefixed TNZ)
RBW	Restricted Building Work
SARNZ	Scaffolding and Rigging New Zealand Inc
SED	Specific Engineering Design

1.4 DEFINED WORDS

Words defined in the conditions of contract, New Zealand Standards, or other reference documents, to have the same interpretation and meaning when used in their lower case, title case or upper case form in the specification text.

1.5 WORDS IMPORTING PLURAL AND SINGULAR

Where the context requires, words importing singular only, also include plural and vice versa.

© CIL Masterspec Sep 2026

1232S1 EXPLANATION OF SCHEDULE SECTIONS

1 GENERAL

This General section provides an explanation of Schedule sections and their relationship to General sections and Work sections. Specific Schedule sections contained within this specification are also identified.

1.1 EXPLANATION OF SCHEDULE SECTIONS

A schedule section identifies Work sections that contain common requirements, as identified in the title of the Schedule section. For example 1235S1 SCHEDULE OF SHOP DRAWINGS identifies Work sections that have requirements for shop drawings. Details of the requirements are contained in the identified Work sections with additional requirements contained in the General section 1235 SHOP DRAWINGS.

A Schedule section is identified by the 4 digit CBI (Co-ordinated Building Information) number of the General section that it relates to, followed by the letter "S" followed by a numeral (1-9). The numeral allows for multiple schedule sections to be associated with the same General section.

1.2 SCHEDULE SECTIONS

The following Schedule sections are contained within the specification:

1237S1 Schedule of Warranties

© CIL Masterspec Sep 2026

1233 REFERENCED DOCUMENTS

1 GENERAL

1.1 REFERENCED DOCUMENTS

Throughout this specification, reference is made to various New Zealand Building Code Compliance Documents (NZBC __), acceptable solutions (__ AS_) and verification methods (__ VM_) for criteria and/or methods used to establish compliance with the New Zealand Building Code.

Reference is also made to various standards produced by Standards New Zealand (NZS, AS/NZS, NZS/AS), overseas standards and to listed Acts, Regulations and various industry codes of practice and practice guides. The latest edition (including amendments and provisional editions) at the date of this specification applies unless stated otherwise.

It is the responsibility of the contractor to be familiar with the materials and expert in the techniques quoted in these publications.

Documents cited both directly and within other cited publications are deemed to form part of this specification. However, this specification takes precedence in the event of it being at variance with the cited documents.

1.2 DOCUMENTS

Documents referred to in the GENERAL sections are:

NZBC F4/AS1	Safety from falling
NZBC F5/AS1	Construction and demolition hazards
AS/NZS 1170.2	Structural design actions - Wind loads
AS/NZS 3012	Electrical installations - Construction and demolition sites
NZS 1170.5	Structural design actions - Earthquake actions - New Zealand
NZS 3109	Concrete construction
NZS 3114	Specification for concrete surface finishes
NZS 3404:1997	Steel structures standard
NZS 3602	Timber and wood-based products for use in building
NZS 3604	Timber-framed buildings
NZS 4210	Masonry construction: Materials and workmanship
NZS 6803	Acoustics - Construction Noise

Building Act 2004
Building Regulations 1992
Health and Safety at Work Act 2015
Health and Safety at Work (General Risk and Workplace Management) Regulations 2016
Health and Safety at Work (Hazardous Substances) Regulations 2017
Health and Safety in Employment Regulations 1995 (reprint 4 April 2016)
New Zealand Building Code
Heritage New Zealand Pouhere Taonga Act 2014
Resource Management Act 1991
Smoke-free Environments Act 1990

WorkSafe NZ	Guidelines for the provision of facilities and general safety in the construction industry
WorkSafe NZ	Good Practice Guidelines - Excavation Safety
WorkSafe NZ	Scaffolding in New Zealand - Good Practice Guidelines
SARNZ	Best practice guideline for scaffolding in New Zealand

© CIL Masterspec Sep 2026

1234 DOCUMENTATION

1 GENERAL

This general section relates to documentation required by the Territorial Authority / Building Consent Authority for compliance with the New Zealand Building Code. It also includes documentation relating to:

- Substitutions
- Manufacturers' documents
- Branded work sections
- Care of construction documents
- Confidentiality of documents
- Receipt of construction documents

Building Consent Authority documentation

1.1 BUILDING CONSENT

Obtain the original building consent forms and documents from the owner and keep them on site, preserve the condition of consent forms and documents. Liaise with the building consent authority for all notices to be given and all inspections required during construction to ensure compliance. Return the consent form and documents to the owner on completion.

1.2 BUILDING CONSENT COMPLIANCE

It is an offence under the Building Act 2004

- to carry out any work not in accordance with the building consent.
- to carry out Restricted Building Work by anyone other than a Licensed Building Practitioner licensed for that type of work.

The resolution of matters concerning building code compliance to be referred to the contract administrator for a direction and then if required to the BCA for consent.

Where any alteration is requested by the territorial authority or any other authority, do not undertake such alteration until the matter has been referred to the contract administrator for direction.

1.3 PROJECT PERSONNEL

Provide names and contact details of the contractor's key personnel and tradespersons who are involved with the project. Review the list once a month and reissue it if changes have been made.

Licensed Building Practitioner documentation

1.4 LICENSED BUILDING PRACTITIONERS

Provide LBP details. Provide names, LBP numbers, areas of practice and contact information. Provide this information to the BCA before commencing work on the Restricted Building Work in the form required by the BCA. Advise the BCA of any change to an LPB previously advised.

Include the following as applicable

- Site LBP
- Carpenter
- Foundations 1 Concrete foundation walls and concrete slab-on-ground constructor
- Bricklaying and block laying 1 Brick / masonry veneer
- Roofing 2 Profiled metal roofer and/or wall cladding installer

Also provide names and contact details of the following

- Registered drainlayer
- Registered plumber
- Registered electrician

1.5 PRODUCER STATEMENTS

When producer statements verifying construction are required, provide copies to both the Building Consent Authority and the Contract Administrator. Provide producer statements in the form required by the BCA.

© CIL Masterspec Sep 2026

1.6 RECORD OF WORK

Where Restricted Building Work is carried out by a LBP, on completion provide a Record of Work. Provide copies to both the BCA and the Contract Administrator.

Compliance information

1.7 DOCUMENTATION REQUIRED FOR CODE COMPLIANCE

Information may be required either as a condition of the contract documents or as a condition of the building consent. It may include the following:

- Applicators approval certificate from the manufacturer / supplier
- Manufacturer's / supplier's warranty
- Installer / applicator's warranty
- Producer Statement - Construction from the applicator / installer
- Producer Statement - Construction review from an acceptable suitably qualified person

Refer to the general sections for the requirements for compliance information to be provided by the contractor.

Refer to the building consent for the requirements for compliance information to be provided by the contractor.

Obtain required documents from the relevant parties for delivery to the contract administrator after the final inspection has been carried out by the BCA.

1.8 DOCUMENTATION REQUIRED ON COMPLETION

As soon as practicable after completion of the building work, provide in writing the following information and documentation to the client and the relevant territorial authority.

Information and documentation relating to:

- The identity of the building contractor and the subcontractors who carried out the work.
- Maintenance requirements for any products incorporated in the building.

If applicable also provide any guarantee or insurance obtained by the building contractor in relation to the building work.

Substitutions

1.9 ACCEPTABLE PRODUCT/MATERIAL SUPPLIERS

Where a product or material supplier is named in SELECTIONS, the product/material must be provided by the named supplier. Where more than one named supplier, any one of the named suppliers will be acceptable.

1.10 NO SUBSTITUTIONS

Where specifically stated in a section, substitutions are not permitted to any of the specified systems, components and associated products listed in that section.

1.11 PROPOSED SUBSTITUTIONS

A substitution may be proposed where specified products are not reasonably available. A substitution may also be proposed by the contractor where the contractor considers a proposed substitution to be an alternative to the specified product. Except where a specified product is not available, the contract administrator is not bound to accept any substitutions. Where branded work sections are included in this specification, substitution of those products or systems will not be allowed.

1.12 NOTIFICATION OF SUBSTITUTIONS

Notify proposed substitution of specified products. Notification to include but not be limited to:

- Product identification
- Manufacturer's name, address, telephone number, website and email address
- Detailed comparison between the properties and characteristics of the specified product and the proposed substitution
- Statement of NZBC compliance including durability
- Details of manufacturer warranties

© CIL Masterspec Sep 2026

Plus an assessment of:

- Any changes required to the programme including any extension of time required
- Any consequential effects of the proposed substitution
- Any effect the substitution may have on Health & Safety requirements
- Allowance for time and cost for re-design and documentation (if applicable)
- Allowance for time and cost for obtaining an amendment to the Building Consent (if applicable)
- Any change in cost associated with the proposed substitution

and if requested:

- All current manufacturer's literature on the product
- Accreditations and appraisals available
- Reference standards
- Product limitations
- Samples
- List of existing installations in the vicinity of the project

1.13 ACCEPTANCE OF SUBSTITUTIONS

The Contract administrator must advise of acceptance of substitutions in writing.

Variations to issued Building Consent

1.14 CONTRACTOR VARIATION TO BUILDING CONSENT

Where the contractor has sought acceptance of a substitution or a variation which is for the contractor's own convenience and the substitution or variation requires an amendment to the Building Consent, the contractor must apply for and obtain the required amendment.

The contractor must:

- Obtain approval for substitutions from the contract administrator.
- Prepare and provide to the BCA all documentation required for the variation.
- Pay all fees and other costs associated with this amendment.
- Where the amendment affects other approved plans, also amend those plans.

1.15 PRINCIPALS VARIATION TO BUILDING CONSENT

Where the principal is proposing a substitution or a variation which requires an amendment to the Building Consent, the contractor must provide to the principal information that the contractor has that is required for the amendment.

The principal will:

- Prepare and provide to the BCA all documentation required for the amendment.
- Pay all fees and other costs associated with this amendment.
- Where the amendment affects other approved plans, also amend those plans.

Manufacturer's documents

1.16 MANUFACTURER’S AND SUPPLIER’S INSTALLATION REQUIREMENTS

Manufacturers and supplier’s requirements, instructions, specifications or details means those issued by them for their particular material, product or component and are the latest edition.

1.17 CONTRACTOR TO OBTAIN CURRENT DOCUMENTATION

Where manufacturer’s installation, application and execution requirements are referred to in this specification, the Contractor must ensure they are fully aware of this documentation. Whenever necessary obtain and keep on site the relevant latest version of such documentation and make it available to workers carrying out that part of the work.

1.18 DOCUMENTATION PROVIDED FOR BUILDING CONSENT

Documentation including manufacturer’s installation instructions, specification data sheets, producer statements, BRANZ and similar appraisals may be included in the issued Building Consent. These documents have been provided only to demonstrate compliance with the NZBC.

© CIL Masterspec Sep 2026

Branded work sections

1.19 BRANDED WORK SECTIONS

Branded sections may be included in this specification relating to specific products and systems to be installed as part of the contract works. Where branded sections are included, substitutions to the branded products and systems will not be allowed.

1.20 CROSS REFERENCED WORK SECTIONS

If any related work is cross referenced to a generic work section, but only the equivalent branded section is included in the specification, use that branded section. Confirm with the contract administrator if there is any doubt.



© CIL Masterspec Sep 2026

1237 WARRANTIES

1 GENERAL

This general section refers to the requirements for warranties/guarantees, referred to within this specification and referred to within separate specifications/documents relating to this project. It includes:

- Warranties for parts of the work required by the principal in a required form
- Installer/applicator warranties for parts of the work in the installer's/applicator's standard form
- Manufacturer/supplier warranties provided with products, appliances and the like in the manufacturer's/supplier's standard form
- Guarantees provided by contractor in the contractor's standard form

These guarantees/warranties are in addition to any warranties, implied warranties, or guarantees that are required by the Building Act, the Building Regulations, or the building consent.

1.1 SCHEDULE SECTION

Refer to 1237S1 SCHEDULE OF WARRANTIES for work sections contained in this specification that have requirements for warranties.

Warranties

1.2 PROVIDE WARRANTIES

Provide executed warranties in favour of the principal in respect of, but not limited to, materials, components, service, application, installation and finishing called for in that specified section of work. The terms and conditions of the warranty in no case negate the minimum remedies available under common law as if no warranty had been offered. Failure to provide the warranty does not reduce liability under the terms of the warranty called for in that specified section of work.

- Conform to the WARRANTY AGREEMENT form included in the specification/conditions of contract.
- Commence warranties from the date of practical completion of the contract works (unless otherwise stated).
- Maintain their effectiveness for the times stated.
- Provide executed warranties prior to practical completion.

1.3 WARRANTIES - INSTALLER/APPLICATOR

Where installer/applicator warranties are offered covering execution and materials of proprietary products or complete installations, provide such warranties to the contract administrator. These warranties may be provided in lieu of the warranties that are otherwise required provided that these warranties are subject to similar conditions and periods.

Provide warranties in favour of the principal. The terms and conditions of such warranties in no case negate the minimum remedies available under common law as if no warranty had been offered. Failure to provide the warranty does not reduce liability for execution and materials for that part of the work.

1.4 WARRANTIES - MANUFACTURER/SUPPLIER

Where warranties are offered covering materials, equipment, appliances or proprietary products, provide all such warranties to the contract administrator.

Provide warranties in favour of the principal. The terms and conditions of such warranties in no case negate the minimum remedies available under common law as if no warranty had been offered. Failure to provide the warranty does not reduce liability for execution and materials for that part of the work.

© CIL Masterspec Sep 2026

Submission

1.5 REVIEW BY CONTRACTOR

Obtain the warranties from the installers, applicators, manufacturers and suppliers at the earliest possible date and review to ensure that they are correctly filled out and executed. Where warranties are executed as a deed, ensure that a duplicate copy is provided for execution by the owner/principal. Keep safe and secure until required for submission.

1.6 WARRANTIES - REQUIRED BY BUILDING CONSENT AUTHORITY

Obtain copies of warranties required as a condition of the building consent in the form required for submission to the BCA. Keep safe and secure until required at the time of the BCA final inspection and Code Compliance Certificate.

1.7 WARRANTIES - REQUIRED BY CONTRACT

Obtain copies of warranties listed in the contract documents. Provide all warranties at the same time. If the project has an operations and maintenance documentation provision, present the warranties with the operations and maintenance information. If no operations and maintenance documentation provision exists, present the warranties to the contract administrator in a loose-leaf binder with a contents index suitably labelled and including the project name and details. Provide a title on the binder edge "Warranties for (project name)"

1.8 WARRANTIES - SUBMISSION NZS3910:2013 CONTRACT

Refer to NZS 3910 Conditions of Contract for building and civil engineering construction, clauses 11.5 and 11.6 for requirements relating to the time for submission of warranties and guarantees. Submit all warranties/guarantees to the engineer no later than the date that the contractor notifies that it believes the contract works qualify for practical completion.

2 SELECTIONS

Project warranties / guarantees

Weathertightness and watertightness warranty

2.1 WEATHERTIGHTNESS AND WATERTIGHTNESS WARRANTY

A warranty is required from the contractor for a minimum period of 2 years, covering the weathertightness of the complete building envelope and the watertightness of all liquid supply and disposal systems and fittings. This general warranty is in addition to any specific warranties required.

Provide this warranty in favour of the principal. The terms and conditions of this warranty in no case negate the minimum remedies available under common law as if no warranty had been offered. Failure to provide the warranty does not reduce liability for execution and materials for that part of the work.

- Conform to the standard form WARRANTY AGREEMENT included in the contract documents.
- Commence the warranty from the date of Practical Completion.
- Maintain its effectiveness for the time stated.

© CIL Masterspec Sep 2026

1237S1 SCHEDULE OF WARRANTIES

1 GENERAL

This schedule section identifies work sections in the specification that have requirements for warranties.

1.1 ASSOCIATED SECTIONS

Read in conjunction with:

- 1232S1 EXPLANATION OF SCHEDULE SECTIONS
- 1237 WARRANTIES
- Identified Work Sections

Warranties

1.2 WARRANTIES

Refer to the following sections:

4161T	Kingspan Thermakraft Underlays, Foils, DPC, DPM, & Tapes
4231HL	James Hardie® Linea™ Weatherboard Cladding
4239JH	James Hardie® Soffits
4241	Profiled Metal Cladding
4311D	Dimond Profiled Metal Roofing
4422A	Ardex Butynol & Butyseal Membrane Roofing
4521	Aluminium Windows & Doors
4610	Glazing Residential
6700R	Resene Painting General
7120	Hot & Cold Water System
7701	Electrical Basic

1.3 PROJECT WARRANTIES

Refer to section 1237 WARRANTIES for project warranties.

1.4 WARRANTIES - ADDITIONAL ITEMS

Refer to separate documentation for warranties not contained within this specification.

© CIL Masterspec Sep 2026

1240 ESTABLISHMENT

1 GENERAL

This general section relates to site establishment including:

- Notices and approvals
- Inspections
- Site preparation
- Signage
- Temporary construction

Notices and approvals

1.1 STATUTORY OBLIGATIONS

Comply with all statutory obligations and regulations of regulatory bodies controlling the execution of the works.

1.2 BUILDING CONSENT AUTHORITY AND NETWORK UTILITY APPROVALS

Attend on Building Consent Authority officers, statutory and network utility inspectors, as necessary to obtain approvals (in addition to building consent approval) for and the satisfactory completion of, the works.

1.3 NOTIFY NETWORK UTILITY OPERATORS

Notify all network utility operators of proposed works before commencing site operations. Ascertain location of services or confirm that none exist in the vicinity of the works. Take all necessary precautions to avoid damage to existing services.

Site preparation

1.4 SITE AND SOIL SURVEYS

Carry out all investigations necessary and peruse all information available to determine ground conditions and likely ground performance both on the site and adjacent to it. Also refer to the territorial authority project information memorandum (PIM).

1.5 GROUND CONDITIONS

Refer to the soils investigation report included with this specification.

Signage

1.6 SITE SIGN

Obtain approval for, provide and erect a timber framed sign board ~mm x ~mm fully painted and displaying:

- Title of contract
- Principal's name
- Contractor's name
- Consultants as listed in general section 1222 PROJECT PERSONNEL
- If the contractor wishes, names of contractor and subcontractors.

© CIL Masterspec Sep 2026

1250 TEMPORARY WORKS & SERVICES

1 GENERAL

This general section relates to temporary works and services required for the construction of the contract works. It includes

- Temporary works and services including temporary fencing and hoardings
- Scaffolding and shoring
- General care and protection

Temporary works

1.1 COMPLY WITH NEW ZEALAND BUILDING CODE

Refer to New Zealand Building Code clauses and approved document paragraphs for the criteria and/or methods that must be used in this section to establish compliance with the code.

1.2 COSTS RELATING TO TEMPORARY WORKS

Pay all rates/fees in respect of temporary works.

1.3 MAINTENANCE OF TEMPORARY WORKS

Maintain alter, adapt and move temporary works and services as necessary. Clear away when no longer required and make good.

1.4 SAFEGUARD THE SITE, THE WORKS AND MATERIALS

Take all precautions to prevent unauthorised access, including access outside working hours, to the site, the works and adjoining property. Safeguard the site, the works, materials and plant from damage and theft.

1.5 SITE FENCING

Provide and maintain a site fence, 2 metres high from ground level on the side accessible to the public. Construct to comply with NZBC F5/AS1 Construction and demolition hazards. Construct as required for public areas and as shown on the drawings.

Construct the fence with:

- galvanized chain link netting with a 50mm x 50mm maximum grid size
- posts at 2.5 metre centres maximum
- gap at the bottom of the fence no greater than 100mm

1.6 SITE FENCING - NON-PUBLIC AREAS

Provide and maintain a 1 metre high site fence to non-public areas. Construct using:

- warratah stakes at 1.5 metre centres fitted with safety caps
- plastic safety mesh

1.7 PROVIDE SEDIMENT AND SILT RUN OFF PROTECTION

Provide appropriate measures to prevent or minimise sediment generation and silt run off. Comply with territorial and other authority requirements relating to carrying out earthworks.

Prevent silt run off by:

- exposing only as much ground as required at any time
- providing run off channels, contour drains or earth bunds to divert clean water away from the site on to stable sealed or grassed ground
- capture silt by the use of silt fences, vegetation buffer strips, sediment ponds or earth bunds.

Provide sediment control by:

- earth bunds constructed across the slope to control and detain run off
- silt fences constructed using filter fabric stretched between posts at a maximum of 1 metre spacing.

Pump water from trenches and other areas of the site using methods to prevent sediment entering any drain or watercourse. Filter dirty water before discharging into drainage system.

© CIL Masterspec Sep 2026

1.8 PROVIDE CONCRETE WASHWATER RUN OFF PROTECTION

Provide appropriate measures to prevent cement/concrete washwater or slurry run off to; drains or waterways, landscaped areas new or remaining and adjoining public or private properties. Comply with territorial and other authority requirements relating to cement/concrete washwater.

Control run off from:

- Cement/concrete based material production, placing and finishing.
- Hosing down and cleaning of, tools and equipment, fresh material, and spilt or surplus material, pumps and mixers etc.
- Wet cutting or grinding.
- Slab watering etc.
- Water cleaning of new concrete elements, fresh used formwork etc.

Spilt or surplus material:

- if possible allow to set and either use or dispose of as hardfill.
- pre-made concrete items, either use or dispose of as hardfill.

Pump washwater away from drains, waterways and adjoining property.

Temporary services

1.9 WATER

Provide clean, fresh water for the works and make arrangements for distributing about the site.

1.10 ELECTRICITY

To AS/NZS 3012.

Nominate the person to install and be responsible for the complete temporary electrical installation. The name and designation of the person responsible is to be displayed prominently and close to the main switch or circuit breaker.

Inspect and overhaul the installation at such intervals as are prescribed by the network utility operator but not exceeding three monthly intervals.

Scaffolding and shoring

1.11 GENERAL SCAFFOLDING

Provide as necessary general scaffolding for the efficient execution of the works. Placement, erection and structure to be by certified suppliers/erectors and approved by the WorkSafe NZ inspectors before being used.

Comply with:

- Health and Safety at Work Act 2015
- Health and Safety in Employment Regulations 1995 (reprint 4 April 2016)
- SARNZ - Best practice guideline for scaffolding in New Zealand
- WorkSafe - Scaffolding in New Zealand - Good Practice Guidelines

Care and protection

1.12 PROTECT EXISTING BUILDINGS

Protect existing buildings and other designated features which are to remain in position during the execution of the works.

1.13 MAKE GOOD EXISTING SERVICES

Make good all damage to existing roads, footpaths, grounds, sewers or other services, caused in carrying out the contract works.

1.14 CONSTRUCTION KEYING AND SECURITY

Provide locksets with temporary keying, or install with the cylinders removed.

© CIL Masterspec Sep 2026

1.15 TEMPORARY STORAGE

Provide temporary storage areas and protective covers and screens. Fillet stack and protect all framing and structural members from moisture and contamination. Completely protect finishing materials from the weather and damage and store in accordance with the manufacturer's requirements. Protect fabricated elements from the weather and damage, and store in accordance with suppliers' requirements.

1.16 PERIODIC SITE CLEANING

Carry out periodic site cleaning during the contract period. Place waste material in appropriate storage pending removal from the site.

1.17 PERIODIC RUBBISH REMOVAL

Maintain on site appropriate means for the storage and removal of construction waste material. Where required or appropriate provide for the separate storage of recyclable waste and other materials requiring special disposal. Keep food waste separate from construction waste.



© CIL Masterspec Sep 2026

1270 CONSTRUCTION

1 GENERAL

This GENERAL section relates to common requirements for construction issues including: -

- Quality assurance
- Noise and nuisance
- Set out
- Common execution requirements
- Common materials requirements
- Supply of spare materials
- Common requirements for samples and tests
- Final presentation and cleaning
- Commissioning

Quality control and assurance

1.1 QUALITY ASSURANCE

Carry out and record regular checks of material quality and accuracy, including:

- Concrete quality and finish.
- Dimensional accuracy of structural column locations (following completion of foundations).
- All perimeter columns and frames for plumb.
- Levels of all floors relative to the site datum.
- Framing timber moisture content.

Where any material, quality or dimension falls outside specified or required tolerances, obtain written direction from the contract administrator. Where building consent approval is affected, confirm remedial action with the Building Consent Authority.

Provide all materials, plant, attendances, supervision, inspections and programming to ensure the required quality standards are met by all project personnel.

Noise and nuisance

1.2 LIMIT CONSTRUCTION NOISE

Minimise the effects of noise generation by including in the planning of the work such factors as placing of plant, programming the sequence of operations and other management functions. Limit construction noise to comply with the requirements of NZS 6803, the requirements of the Resource Management Act sections 326, 327 and 328 and the Health and Safety in Employment Regulations clause 11.

1.3 ACCEPTABLE NOISE LEVELS

Refer to NZS 6803 Tables 2 and NZS 6803, tables 3 for the upper limits of construction work noise in residential and industrial areas over the various time periods, particularly 0730 to 1800 hours. Note also the allowed adjustments and exemptions in NZS 6803, 6. Do not exceed these limits.

1.4 PROVIDE INFORMATION TO NEIGHBOURS

Provide information to neighbours of any noise generation from the site liable to constitute a problem. Explain to them the means being used to minimise excessive noise and establish with them the timings most suitable for the noise generating work to be carried on.

Discuss with any complainant the measures being used to minimise noise. Where possible modify these measures to accommodate particular circumstances. Finally, determine the sound level at the location under discussion using methods and observation reporting as laid down in NZS 6803. If the noise level is above the upper limits of NZS 6803, tables 2 and NZS 6803, tables 3, cease the noise generating operation and remedy the problem.

1.5 DIRT AND DROPPINGS

Remove dirt and droppings deposited on public or private thoroughfares from vehicles servicing the site to the satisfaction of the appropriate authorities and the contract administrator.

© CIL Masterspec Sep 2026

1.6 DAMAGE AND NUISANCE

Take all precautions to prevent damage and nuisance from water, fire, smoke, dust, rubbish and all other causes resulting from the construction works.

Set-out and tolerances

1.7 SURVEY INFORMATION

Locate and verify survey marks and datum points required to set out the works. Record and maintain their position. Re-establish and replace disturbed or obliterated marks.

1.8 SET-OUT AND DATUM

Set out the work to conform with the drawings. Establish a permanent site datum to confirm the proposed building ground floor level and its relationship to all other existing and new building levels.

1.9 CONFIRM HEIGHT IN RELATION TO BOUNDARY

Provide a certificate prepared by a licensed cadastral surveyor that the building has been constructed within the allowed height in relation to boundary. Provide the certificate to the local authority. Provide a copy of the certificate to the contract administrator

1.10 USE OF SET-OUT INSTRUMENTS

Permit without charge, the use of instruments already on site for checking, setting out and levels.

1.11 CHECK DIMENSIONS

Check all dimensions both on drawings and site, particularly the correlation between components and work in place. Take all dimensions on drawings to be between structural elements before linings or finishes, unless clearly stated otherwise.

1.12 TOLERANCES

All work to be level, plumb, and true to line and face. Unless otherwise specified in specific work sections of this specification, tolerances for structural work shall comply with the following:

Concrete construction:	To NZS 3109 Concrete construction Clause 3.9 Tolerances for reinforcement Table 5.1 Tolerance for precast components Table 5.2 Tolerance for in situ construction To NZS 3114 Concrete surface finishes
Masonry construction:	To NZS 4210 Masonry construction: Materials and workmanship Clause 2.6.5 Tolerances Table 2.2 Maximum tolerances
Structural steelwork:	To NZS 3404:1997 Steel structures standard Section 14.4 Tolerances (after fabrication) Section 15.3 Tolerances (erection)
Timber framing:	To NZS 3604 Timber-framed buildings Clause 2.2 Tolerances Table 2.1 Timber framing tolerances

Refer to work sections for tolerance requirements for finishes.

Execution

1.13 EXAMINE PREVIOUS WORK

Before commencing any part of the work carefully examine the previous work on which it may depend. Report in writing to the contract administrator defects that may affect the quality of the proposed work and obtain instructions. Commencing work on any part means that previous work is accepted as being satisfactory for work of the required standard.

1.14 WORKER QUALIFICATIONS

All work to be level, plumb, and true to line and face. Employ only experienced workers familiar with the materials and techniques specified.

1.15 MINIMISE DELAYS DUE TO WEATHER

Use appropriate techniques and methods to prevent damage and minimise delays due to weather.

© CIL Masterspec Sep 2026

Materials

1.16 NEW PRODUCTS AND MATERIALS

Materials and products to be new unless stated otherwise, of the specified standard, and complying with all cited documents.

1.17 COMPATIBILITY OF MATERIALS AND FINISHES

Ensure all parts of a construction or finish are compatible and their individual use approved by the manufacturers and suppliers of other parts of the system. Source all parts of a system from a single manufacturer or supplier.

1.18 STORING PRODUCTS AND MATERIALS

Take delivery of and store products, materials and components in accordance with codes of practice and the product manufacturer's or supplier's stated requirements. Maintain the proper condition of any protective packaging, wrappings or supports during delivery, unloading and storage.

1.19 HANDLING PRODUCTS AND MATERIALS

Handle products, materials and components in accordance with codes of practice and the manufacturer's or supplier's stated guidelines. Avoid distortion and any contact with potentially damaging surfaces or conditions.

1.20 SUBSTRATE CONDITIONS

Ensure substrate conditions are within the manufacturer's or supplier's stated guidelines both before and during the installation of any material, product or system. Obtain written instructions on the necessary action to rectify unsatisfactory conditions.

1.21 INSTALLING PRODUCTS AND MATERIALS

Install in accordance with the manufacturer's or supplier's technical literature. Ensure that all installers are familiar with the required substrate conditions and the manufacturer's or supplier's specified preparation, fixing and finishing techniques.

1.22 COMPLY WITH STANDARDS

Comply with the relevant and/or cited Standard for any material or component. Obtain certificates of compliance when requested by the contract administrator.

1.23 CONDITION OF MATERIALS AND COMPONENTS

To be in perfect condition when incorporated into the work.

1.24 INCOMPATIBLE MATERIALS AND METALS

Separate incompatible materials and metals with separation layers, sleeves or gaskets of plastic film, bituminous felt or mastic or paint coatings, installed so that none are visible on exposed surfaces.

1.25 CONTROL STANDARD

Obtain the contract administrator's confirmation of material, component and work samples which then become the quality control standard. Remove from the site any rejected samples. Retain confirmed samples with care on site for comparison throughout the contract. Remove from the site when no longer required.

Final presentation and cleaning

1.26 REMOVE TEMPORARY PROTECTION

Remove all temporary markings, coverings, labels and protective wrappings unless instructed otherwise.

1.27 REPLACE DAMAGED MATERIALS

Replace all materials or component damaged during the works to the standard of and integral with the original.

1.28 COMPLETE ALL SERVICES

Ensure all services are complete and operational, with all temporary labelling removed, required labelling fixed and service instructions provided.

© CIL Masterspec Sep 2026

1.29 CLEANING BY CONTRACTOR

Clear the contract works of all construction materials, waste, dirt and debris. Clean the contract works including:

- Wipe all surfaces to remove construction dust
- Clean out service ducts and accessible concealed spaces
- Clean out all gutters and rainwater heads
- Wipe dust from both sides of glass. Take particular care when removing paint or cementitious materials to not damage the glass.
- Remove adhesive residue left by labels and other temporary protection/markings
- Clean out the interior of all cabinetry
- Wash down external concrete including driveways and concrete masonry. Take care when waterblasting to not cause damage to the surface or allow water to enter the building.
- Remove rubbish and building material from the area immediately adjacent to the contract works

Commissioning

1.30 MOVING PARTS

Adjust, ease and lubricate all doors, windows, drawers, hardware, appliances, controls and all moving parts to give easy and efficient operation.

1.31 SECURITY AT COMPLETION

Remove any temporary lock cylinders and complete final keying prior to handing over keys to the principal on completion of the works. Leave the works secure with all accesses locked. Account for all keys/cards/codes and hand to the principal along with an itemised schedule, retaining a duplicate schedule signed by the principal as a receipt.

© CIL Masterspec Sep 2026

2210 PREPARATION & GROUNDWORK

1 GENERAL

This section relates to the clearance, excavation and backfilling of the site area in preparation for:

- footings and floor slabs

Documents

1.1 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZS 3604	Timber-framed buildings
WorkSafe NZ	Good Practice Guidelines - Excavation Safety

1.2 SITE SAFETY

Provide adequate support for all excavations. Cover holes and fence off open trenches and banks.

1.3 ARCHAEOLOGICAL DISCOVERY

If fossils, antiquities and other items of value are found refer to the general section 1220 PROJECT for actions to be taken with archaeological discovery.

© CIL Masterspec Sep 2026

2 PRODUCTS

2.1 EXCAVATED CLEAN FILL

Clean, free of contamination, mineral soil from other formations in the excavation which may be selected and approved as suitable for filling by having grading and moisture content properties that will allow recompaction to 95% of maximum density.

2.2 VOLCANIC TUFF FILL

Scoriaceous tuff of variable grading excluding excessive silt or clay material, capable of being placed and compacted as specified.

2.3 ROCK FILL

Hard material comprising rock, broken stone, hard brick, concrete, run of pit scoria, or other comparable inert material capable of being placed and compacted as specified.

2.4 SAND FILL

Clean sand of such grading in particle size to achieve mechanical compaction to 90% maximum density.

2.5 HARD FILL

Scoria or crushed rock to GAP (General All Passing) 40 grading.

2.6 GRANULAR FILL

Approved screened crushed gravel or scoria, graded in size from 20mm to 7mm, clean. When tested with a standard sieve of 4.75 opening no material is to pass.

2.7 DRESSING COURSE

Scoria to GAP 20 grading, or "dirty footpath scoria", or equivalent "all in" graded crushed metal aggregate.

2.8 FREE-DRAINING AGGREGATE

Scoria or crushed gravel graded 50 to 14 clean.

© CIL Masterspec Sep 2026

3 EXECUTION

3.1 WASHOUT BAY FOR TRUCK

Provide a designated area for trucks to be washed down to avoid mud and dirt being carried off site.

3.2 EXCAVATION GENERALLY

Carry out excavation, using plant suitable for the purpose, to the guidelines set by the WorkSafe NZ, Good Practice Guidelines - Excavation Safety.

3.3 BURNING OF MATERIALS

Burning of materials is not permitted on site.

3.4 PROTECT EXISTING WORK

Protect from damage existing buildings, structures, roads, paving and services nominated on the drawings as being retained.

3.5 PROTECT EXISTING TREES, PLANTING, OR LANDSCAPE FEATURES

Protect from damage trees, shrubs, natural site features and existing landscaped areas nominated on the drawings as being retained. Ensure existing levels are undisturbed beneath the dripline of retained trees.

3.6 EROSION CONTROL

Ensure measures are in place to contain silt dislodged as a result of water infiltration and to prevent it being carried off site with stormwater.

3.7 SURFACE PREPARATION

Comply with NZS 3604, section 3.5, **Site preparation**. Remove all turf, vegetation, trees, topsoil, stumps, uncontrolled fill and rubbish from the area to be built on.

3.8 STOCKPILE TOPSOIL

Stockpile excavated topsoil on site where directed. Keep separate from other excavated materials. Spread and level where directed before completion of the works.

3.9 GENERAL EXCAVATION

Trim ground to required profiles, batters, falls and levels. Remove loose material. Protect cut faces from collapse. Keep excavations free from water.

3.10 ROCK EXCAVATION

If rock is found at any level above the underside of the structural foundations, or above required base levels for site service trenches, immediately notify the owner. Obtain written instructions from the owner on the proposed approach to rock excavation, or consequent alterations to subgrade construction. Confirm any changes with the territorial authority.

3.11 FOUNDATION EXCAVATION

Take foundation excavations to depths shown. Keep trenches plumb and straight, bottoms level and free of soft spots, stepped as detailed and clean and free of water.

3.12 INADEQUATE BEARING

If bearing is not to NZS 3604, 3.1.2 **Foundations** and 3.1.3 **Determination of good ground**, then excavate further and backfill with material as follows. Confirm any changes with the territorial authority.

Below slabs on grade: Hardfill compacted in 150mm layers
Below footings: 10 MPa concrete
Service trenches: Hardfill compacted in 150mm layers

If excavation exceeds the required depths, backfill and compact to the correct level with material as listed.

3.13 STANDARD OF COMPACTION

Place fill in layers of not more than 150mm and compact to achieve 95% of maximum dry density. For granular fill material, the fill shall be compacted to 80% of saturated dry density.

© CIL Masterspec Sep 2026

3.14 GENERAL BACKFILLING

Obtain written confirmation from the owner before using any excavated material. Compact approved backfilling in 150mm layers with the last 200mm in clean topsoil, lightly compacted and neatly finished off.

3.15 SURPLUS MATERIAL

Remove surplus and excavated material from the site.



© CIL Masterspec Sep 2026

3820 CARPENTRY

1 GENERAL

This section relates to the supply and erection of timber framing, as a framed structure, or as partitioning. It includes prefabricated timber and engineered wood.

1.1 RELATED WORK

Refer to 4161 UNDERLAYS, FOIL AND DPC for underlays, foils and DPC.

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC B2/AS1	Durability
AS/NZS 1328.1	Glued laminated structural timber - Performance requirements and minimum production requirements
AS/NZS 1604.4	Specification for preservative treatment - Laminated veneer lumber (LVL)
AS/NZS 1604.5	Specification for preservative treatment - Glue laminated timber products
NZS 3602	Timber and wood-based products for use in building
NZS 3603	Timber structures standard
NZS 3604	Timber-framed buildings
NZS 3622	Verification of timber properties
NZS 3640	Chemical preservation of round and sawn timber
AS/NZS 4357.0	Structural laminated veneer lumber - Specification
FTMA CoP	Frame and Truss Manufacturers Association Code of Practice

***A copy of** NZS 3604 **Timber-framed buildings, must be held on site.**

1.3 QUALIFICATIONS

Workers to be experienced, competent trades people familiar with the materials and techniques specified.

1.4 DIMENSIONS

All timber sizes except for battens are actual minimum dried sizes.

2 PRODUCTS

2.1 TIMBER FRAMING, TREATED

Species, grade and in service moisture content to NZS 3602, NZBC B2/AS1 and treatment to NZS 3640, NZBC B2/AS1. Structural grade (SG) to NZS 3604, NZS 3622 with properties to NZS 3603.

2.2 EXTERIOR CAVITY WALL BATTENS - TIMBER - NON-STRUCTURAL

H3.1 or H3.2 Radiata pine battens, minimum 20mm thickness, width and height to match timber framing studs. Temporary fix battens before being fixed into the framing with the cladding fixings. To NZS 3602, table 1, reference 1D.10, Requirements for wood-based building components to achieve a 50-year durability performance.

Components

2.3 NAILS

Type to NZS 3604, section 4, **Durability**, and of the size and number for each particular types of joint as laid down in the nailing schedules of NZS 3604, sections 6-10.

2.4 BOLTS AND SCREWS

Bolts and screws of engineering and/or coach type complete with washers, to the requirements of NZS 3604, section 4, **Durability**, and of the number and form required for each particular junction to NZS 3604, sections 6-10.

© CIL Masterspec Sep 2026

2.5 NAIL PLATES

Comply with the requirements of NZS 3604, section 4, **Durability**, and of the number and form required for each particular junction to NZS 3604, sections 6-10. Plates to the plate manufacturer's design for the particular locations as shown on the drawings.

2.6 CONNECTORS

Comply with the requirements of NZS 3604, section 4, **Durability**, and of the number and form required for each particular junction to NZS 3604, sections 6-10. Connectors and structural brackets to the connector manufacturer's design for particular locations shown on drawings.

2.7 CORROSION RISKS

For interior timber, treated with copper-based timber preservatives (H3.2 or higher), use a minimum of hot-dipped galvanized steel fixings and fasteners.

For exterior timber, timber in damp areas and timber subject to occasional wetting, use only stainless steel (or equivalent) fixings and connectors, when the timber is treated with; Copper Azole (CuAz, Preservative code 58), Alkaline Copper Quaternary (ACQ, Preservative code 90), Micronise Copper Azole (code 88) or Micronised Copper Quaternary (code 89).

2.8 DPC

Refer to 4161 UNDERLAYS, FOIL AND DPC section

© CIL Masterspec Sep 2026

3 EXECUTION

3.1 EXECUTION GENERALLY

To NZS 3604 except as varied in this specification. Execution to include those methods, practices and processes contained in the unit standards for the National Certificate in Carpentry and the National Certificate in Joinery (cabinetry, exterior joinery, stairs).

3.2 SEPARATION

Separate all timber framing timbers from concrete, masonry and brick by: -

- a full length bituminous damp-proof membrane overlapping timber by at least 6mm; or
- a 12mm minimum free draining air space

3.3 ATTENDANCE

Provide and fix blocks, nogs, openings and other items as required by other trades.

3.4 MOISTURE CONTENT

Maximum allowable equilibrium moisture content (EMC) for non air-conditioned or centrally heated buildings for framing to which linings are attached.

Framing at erection:	24% maximum
Framing at enclosure:	20% maximum
Framing at lining:	16% maximum

3.5 SET-OUT

Set out framing in accordance with the requirements of NZS 3604 and as required to support sheet linings and claddings.

3.6 FRAMING FLOORS

Framed and fastened to NZS 3604, section 7, **Floors**.

3.7 FRAMING WALLS

Frame to required loading and bracing complete with lintels, sills and nogs, all fabricated and fastened to NZS 3604, section 8, **Walls**.

3.8 FRAMING ROOFS

Frame to required loading and bracing complete with valley boards, ridge boards and purlins. Design and fit roof trusses complete with anchorage. All fabricated and fastened to NZS 3604, section 9, **Posts** and 10, **Roof framing**.

3.9 FRAMING CEILINGS

Frame to required loading and bracing complete with runners and battens set out to support ceiling lining. All fabricated and fastened to NZS 3604, section 13, **Ceilings**. Trim for openings in ceilings and hatches to NZS 3604 section 13.3, **Openings in ceilings**. Provide blocking for water tanks located in the ceiling space to NZS 3604, section 13.4, **Water tanks in roof space**.

3.10 INSTALLING WALL UNDERLAYS

Refer to 4161 UNDERLAYS, FOIL AND DPC section

3.11 FIT CAVITY BATTENS

Fit and fix 20mm cavity battens over wall underlay or rigid air barrier, fully nail to timber studs to the requirements of the manufacturer or to NZS 3604. Fit and fix related flashings. Fit and fix cavity closers to base of walls, open horizontal (or raking) junctions and over openings (windows, meters etc.).

3.12 DPC TO LOSP TREATED TIMBER

Refer to 4161 UNDERLAYS, FOIL AND DPC section.

3.13 DPC TO TIMBER

Refer to 4161 UNDERLAYS, FOIL AND DPC section.

© CIL Masterspec Sep 2026

4 SELECTIONS

4.1 FLOOR FRAMING - RADIATA PINE

Member	Species	Grade	Treatment
Mid floor joists:	Radiata pine	SG8	H1.2
Boundary joists:	Radiata pine	SG8	H1.2

4.2 EXTERIOR WALL FRAMING - RADIATA PINE

Member	Species	Grade	Treatment
	Radiata pine	Merch	H1.2

4.3 CAVITY BATTENS

Cavity battens	Species	Grade	Treatment
Timber - Non Structural:	Radiata pine	Merchantable	H3.1
Proprietary - non structural:	Manufacturer TBS		
Cavity closer:	Manufacturer TBS		

4.4 ROOF FRAMING - RADIATA PINE

Member	Species	Grade	Treatment
Rafters:	Radiata pine	SG8	H1.2
Trusses:	Radiata pine	SG8	H1.2
Purlins:	Radiata pine	SG8	H1.2
Ceiling joists and battens:	Radiata pine	SG8	H1.2
Valley boards:	Radiata pine	Merchantable	H1.2
Sarking:	Radiata pine	Merchantable	H1.2
Skillion roof framing:	Radiata pine	SG8	H1.2
Enclosed flat roof framing:	Radiata pine	SG8	H1.2

4.5 INTERIOR FRAMING - RADIATA PINE

Member	Species	Grade	Treatment
Non structural walls:	Radiata pine	SG8	H1.2
Structural and braced walls:	Radiata pine	SG8	H1.2

© CIL Masterspec Sep 2026

4161T KINGSPAN THERMAKRAFT UNDERLAYS, FOILS, DPC, DPM, & TAPES

1 GENERAL

This section relates to the supply and installation of Kingspan's Thermakraft product range including DPC, DPM, Wall & Roof Underlays, Foils, Flashing Tapes, and accessories.

1.1 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

DPC	Damp proof course
DPM	Damp proof membrane
EPDM	Ethylene propylene diene monomer

The following definitions apply specifically to this section:

Wall underlay	The same meaning as defined in NZBC E2/AS1, covering kraft based and synthetic wall underlays, sometimes called wall wraps, building wraps or building papers.

Documents

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10 m in height
AS 1530.2	Methods for fire tests on building materials, components and structures - Test for flammability of materials
AS/NZS 2904	Damp-proof courses and flashings
NZS 3604	Timber-framed buildings
NZS 4229	Concrete masonry buildings not requiring specific engineering design
AS/NZS 4347	Damp-proof courses and flashings - Methods of test
AS/NZS 4389	Roof safety mesh
AS/NZS 4534	Zinc and zinc/aluminium-alloy coatings on steel wire
CodeMark CMNZ10002 ver5	Watergate Plus Wall Underlay
CodeMark CMNZ30028 verK	Thermakraft Covertek 407 Roof and Wall Underlay
CodeMark CMNZ30030 verJ	Thermakraft Covertek 405 Roof and Wall Underlay
CodeMark CMNZ30069 verI	Thermakraft Covertek 403 Roof and Wall Underlay

1.3 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer and supplier documents relating to this part of the work:

Thermakraft's Product Data Sheets
Thermakraft's Installation Guides
BRANZ Appraisal 329 (2022) - Supercourse 500 Damp-Proof Course and Concealed Flashing - Amendment 29 August 2023
BRANZ Appraisal 651 (2024) - Thermakraft Covertek 407 Roof and Wall Underlay - Amended 13 July 2026
BRANZ Appraisal 695 (2023) - Watergate Plus Wall Underlay - Amended 01 July 2025
BRANZ Appraisal 878 (2025) - Thermakraft Aluband Window Flashing Tape
BRANZ Appraisal 917(2025) - Thermakraft Covertek 403 Roof and Wall Underlay
BRANZ Appraisal 942 (2022) - OneSeal Multi-fit Pipe and Cable Penetration Seals - Amended 28 July 2026

© CIL Masterspec Sep 2026

Manufacturer/supplier contact details
Company: Kingspan Insulation NZ Ltd
Web: www.thermakraft.co.nz
Email: technical@kingspaninsulation.co.nz
Telephone: 0800 806 595

Warranties

1.4 WARRANTY - MANUFACTURER/SUPPLIER

Provide a material manufacturer/supplier warranty:

15 years For Kingspan Thermakraft product range.

- Provide this warranty on the manufacturer/supplier standard form (if not available then use the standard form in the general section 1237WA WARRANTY AGREEMENT)
- Commence the warranty from the date of practical completion of the contract works.

Refer to the general section 1237 WARRANTIES for additional requirements.

Requirements

1.5 QUALIFICATIONS GENERALLY

Refer to 1270 CONSTRUCTION for requirements relating to qualifications.

1.6 NO SUBSTITUTIONS

Substitutions are not permitted to any of the specified systems, components and associated products listed in this section.

Compliance information - CodeMark certified

1.7 CODEMARK CERTIFICATE - THERMAKRAFT WATERGATE PLUS

Thermakraft Watergate Plus wall underlay meets the requirements of the NZBC when used within the conditions and limitations of its CodeMark Certificate of Conformity CMNZ10002.

1.8 CODEMARK CERTIFICATE - THERMAKRAFT COVERTEK 407

Thermakraft Covertek 407 roof and wall underlay and Covertek 407 Early Close Wall Application meet the requirements of the NZBC when used within the conditions and limitations of its CodeMark Certificate of Conformity CMNZ30028.

Compliance information - BRANZ appraised

1.9 BRANZ APPRAISED - THERMAKRAFT COVERTEK 407

Thermakraft Covertek 407 roof and wall underlay has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 651

1.10 BRANZ APPRAISED - THERMAKRAFT WATERGATE PLUS

Thermakraft Watergate Plus wall underlay has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 695

1.11 BRANZ APPRAISED - THERMAKRAFT ALUBAND

Thermakraft Aluband flashing tape has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 878

1.12 BRANZ APPRAISED - THERMAKRAFT ONESEAL

Thermakraft OneSeal multi-fit pipe and cable penetration seal has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 942

© CIL Masterspec Sep 2026

2 PRODUCTS

DPC

2.1 THERMAKRAFT PERIMETER

Sand coated black paper DPC composed of cardboard, bitumen and fine sand. Tested to AS/NZS 4347 in accordance with AS/NZS 2904. Available in various width. Refer to SELECTIONS.

DPM

2.2 THERMAKRAFT THERMATHENE BLACK

0.25mm x 4000mm wide black DPM composed of recycled alloyed polythene. Membrane has a vapour flow resistance of at least 90MNs/g to NZS 3604 and NZS 4229, Damp-Proof Membranes. Refer to SELECTIONS.

Synthetic underlays - fire retardant

2.3 THERMAKRAFT WATERGATE PLUS

CodeMark certified and BRANZ appraised synthetic wall underlay, white with blue logo print, composed of a water resistant vapour permeable film laminated to a non-woven polyolefin sheet. Fire retardant, tested to AS 1530.2 and assigned a Flammability Index of ≤5. Available in 685mm, 1370mm and 2740mm width. Refer to SELECTIONS.

2.4 THERMAKRAFT COVERTEK 407

CodeMark certified and BRANZ appraised self-supporting synthetic roof and wall underlay, white with red logo print, composed of a water resistant vapour permeable film laminated to two layers of non-woven, spun bonded polyolefin sheet. Fire retardant, tested to AS 1530.2 and assigned a Flammability Index of ≤5. Available in 1250mm, 2550mm and 2740mm width. Suitable for use as an Early Close Wall Application providing up to 120 days temporary weather protection. Suitable for use as temporary weather protection for up to 30 days on roofs. Refer to SELECTIONS.

Components - sealing

2.5 THERMAKRAFT WHITE GENERAL PURPOSE TAPE

60mm wide, white polypropylene general purpose tape with acrylic adhesive. Refer to SELECTIONS.

2.6 THERMAKRAFT ONESEAL

BRANZ appraised black multi-fit pipe and cable penetration seal composed of adhesive coated, 1.2mm thick flexible synthetic rubber material (EPDM) with pre-notched ring markings. Refer to SELECTIONS.

2.7 THERMAKRAFT CORNER MOULDS

Orange, flexible inert polythene moulded window corner flashing. Refer to SELECTIONS.

2.8 THERMAKRAFT ALUBAND

BRANZ appraised, black, self-adhering polymeric faced bituminous flashing tape. Available in 75mm, 150mm and 200mm width. Refer to SELECTIONS.

Fixings

2.9 FIXINGS - TO TIMBER

Little grippers, staples, clouts or screws to suit application. Refer to SELECTIONS.

3 EXECUTION

Conditions

3.1 DELIVERY, STORAGE & HANDLING OF PRODUCTS

Refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.

© CIL Masterspec Sep 2026

3.2 ROUTINE MATTERS

Refer to 1250 TEMPORARY WORKS & SERVICES for protection requirements.

Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.3 PRE-INSTALLATION REQUIREMENTS

Check work previously carried out and confirm it is of the required standard for this part of the work.

Installation/application - generally

3.4 STANDARDS AND TOLERANCES

Refer to the general section 1270 CONSTRUCTION for general requirements.

Installation - DPC

3.5 INSTALL DPC

Ensure substrate's surface is smooth, flat and free from sharp ridges/projections that may puncture membrane. Install as a single layer with minimum 50mm overlap at joints to the Installation Guide.

Installation - DPM

3.6 INSTALL DPM - CONCRETE FLOOR

Install DPM over sand blinding below concrete floors, install in a neat fashion with a smooth surface as a single layer with minimum 150mm overlap at joints to the Installation Guide.

3.7 APPLY TAPE TO LAPPED DPM JOINTS

Ensure DPM is free of dust and contaminates, where required clean with a dry cloth. Apply tape to the Installation Guide centred over joint laps by firmly pressing down without stretching or pulling tape.

Installation - wall underlay

3.8 INSTALL WALL UNDERLAY

Install wall underlay to the Installation Guide horizontally and in true alignment over exterior face of wall framing including openings. Start by placing first sheet draw taut and fix at maximum 300mm centres to wall framing members. Install additional sheets in rows repeating the process for the first sheet with sheet end laps to be of at least 150mm and occurring over wall framing and overlapping higher over lower sheets by at least 150mm.

3.9 INSTALL WALL PENETRATION SEALS

Ensure wall underlay is free of dust and contaminates, where required clean with a dry cloth. Install penetration seal to the Installation Guide over pipe/conduit with a tight fit. Slide seal over pipe/conduit and place on underlay in a diamond shape. Remove backing release film and push firmly down to fix in place.

Installation - roof underlay

3.10 INSTALL ROOF UNDERLAY - HORIZONTAL

Install underlay to the Installation Guide horizontally and in true alignment over exterior face of roof framing. Place first sheet overlapping guttering (max. 20mm) or if eaves flashing is used terminate on the upper side of the flashing, draw sheet taut and fix at maximum 300mm centres to roof framing members. Install additional sheets in row repeating the process for the first sheet with sheet end laps to be of at least 150mm. Install sheets up to and over the ridge repeating the installation process for the first row and overlapping higher over lower sheets by at least 150mm.

3.11 INSTALL ROOF UNDERLAY - VERTICAL

Install underlay to the Installation Guide vertically and in true alignment over exterior face of roof framing. Place first sheet up the slope to the ridge overlapping guttering (max. 20mm) or if eaves flashing is used terminate on the upper side of the flashing, draw sheet taut and fix at maximum 300mm centres to roof framing members. Install additional sheets repeating the process for the first sheet lapping joints by at least 150mm.



© CIL Masterspec Sep 2026

Preparation of wall underlay for window/door placement

3.12 FORM OPENINGS

Form openings in wall underlay to the Installation Guide. Cut underlay diagonally from corner to corner across the opening and tightly fold underlay flaps into opening over the full depth. Secure underlay to the back face of opening framing with staples. Trim excess underlay off at internal face. Remove dust and contaminates from underlay with a dry cloth.

3.13 INSTALL CORNER MOULDS

Install corner moulds with tight fit to sill/jamb corners to the Installation Guide.

3.14 FLASHING TAPE APPLICATION - GENERALLY

Install flashing tape to the Installation Guide. Fold tape back onto exterior wall surface by at least 50mm, cover opening depth in full and finish by lining up with inside edge of opening framing. Fix tape by applying even pressure by hand or a roller leaving no air bubbles beneath the tape.

3.15 APPLY FLASHING TAPE TO SILL

Use 150mm wide tape for up to 100mm deep opening framing and 200mm wide tape for deeper framing. Cut tape to sill length plus 400mm. Remove release film from tape, align back edge of tape with interior sill edge allowing for at least 200mm tape upstand at jambs, apply tape to sill and jamb. Cut tape overhang at external sill/jamb corners, fold back onto and apply to exterior wall face.

3.16 APPLY FLASHING TAPE TO HEADER

Use 150mm wide tape for up to 100mm deep opening framing and 200mm wide tape for deeper framing. Cut tape to 400mm length. Remove release film from tape, align back edge of tape with interior opening framing edge and apply 200mm along head and 200mm down jambs. Cut tape overhang at external head/jamb corners, fold back onto and apply to exterior wall face.

3.17 APPLY FLASHING TAPE ACROSS HEAD/JAMB CORNERS

Cut 75mm wide tape to 100mm length. Apply to exterior wall surface across head/jamb corners at 45°, overlap corners by 3mm to create a seal at corner junctions.

Completion

3.18 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

For further details on selections go to www.thermakraft.co.nz.
Substitutions are not permitted to the following, unless stated otherwise.

DPC

4.1 DPC - THERMAKRAFT PERIMETER

Location:	Bottom Plate to concrete
Manufacturer:	Thermakraft
Brand:	Perimeter
Type:	Damp proof course
Width:	90mm

DPM

4.2 DPM - THERMAKRAFT THERMATHENE BLACK

Location:	Refer enginer foundation design
Manufacturer:	Thermakraft
Brand:	Thermathene Black
Type:	Damp proof membrane
Width:	4000mm
Joint tape:	White General Purpose Tape

© CIL Masterspec Sep 2026

Synthetic underlays - fire retardant

4.3 WALL UNDERLAY - THERMAKRAFT WATERGATE PLUS

Location:	External Walls
Manufacturer:	Thermakraft
Brand:	Watergate Plus
Type:	Synthetic wall underlay
Width:	1370mm,
Fixings:	Galvanized 6mm-8mm staples
Maximum UV exposure:	90 days

4.4 ROOF & WALL UNDERLAY - THERMAKRAFT COVERTEK 407

Location:	Roof
Manufacturer:	Thermakraft
Brand:	Covertek 407
Type:	Synthetic roof and wall underlay
Width:	1250mm
Fixings:	Galvanized 6mm-8mm staples
Maximum UV exposure:	Roofs - 30 days

Components for sealing wall underlay penetrations

4.5 PENETRATION SEAL - THERMAKRAFT ONESEAL

Location:	as required
Manufacturer:	Thermakraft
Brand:	OneSeal
Type:	Pipe and service penetration seal
Size:	as required
Maximum UV exposure:	120 days

4.6 WINDOW CORNER FLASHING - THERMAKRAFT CORNER MOULDS

Location:	Windows and External Doors
Manufacturer:	Thermakraft
Brand:	Corner Moulds
Type:	Window corner flashing
Fixings:	Staples

4.7 150MM FLASHING TAPE - THERMAKRAFT ALUBAND

Location:	Windows and External Doors
Manufacturer:	Thermakraft
Brand:	Aluband
Type:	Flashing tape
Width:	150mm
Maximum UV exposure:	42 days

© CIL Masterspec Sep 2026

4231HL JAMES HARDIE® LINEA™ WEATHERBOARD CLADDING

1 GENERAL

This section relates to the supply and fixing of James Hardie® Linea™ Weatherboard cladding.

1.1 RELATED WORK

Refer to painting section/s for the protective coating required to meet the NZBC durability requirements.

1.2 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions
used throughout the specification.

The following abbreviations apply specifically to this section:

PVC	Polyvinyl chloride

Documents

1.3 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10 m in height
AS/NZS 1170.2:2011	Structural design actions - Wind actions
AS/NZS 2908.2	Cellulose-cement products - Flat sheet
NZS 3604	Timber-framed buildings
CodeMark™ CMNZ30018 - Rev P	Linea™ Weatherboard by James Hardie® Direct Fixed and Cavity Cladding systems

1.4 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer and supplier documents relating to this part of the work:

James Hardie® Linea™ Weatherboard Direct Fix Technical Specification (August 2025)
James Hardie® Linea™ Weatherboard Cavity Fix Technical Specification (August 2025)
James Hardie® Technical Supplement - Linea™ Weatherboard Fixing to Brick Veneer Framing
James Hardie® Technical Supplement - Hardie® Fibre Cement Claddings Installation to Steel Frame
James Hardie® Linea™ Weatherboard Installation Checklist
BRANZ Appraisal 447 (2020) - Linea™ Weatherboard Cavity Cladding
BRANZ Appraisal 1285 (2025) - James Hardie Fire and Acoustic Systems - Amended 16 June 2026

Manufacturer/supplier contact details

Company:	James Hardie New Zealand Limited
Web:	www.jameshardie.co.nz
Email:	info@jameshardie.co.nz
Telephone:	Ask James Hardie on 0800 808 868

Warranties

1.5 WARRANTY - MANUFACTURER/SUPPLIER

Provide a material manufacturer/supplier warranty:

25 years	For James Hardie® Linea™ Weatherboards
15 years	For accessories supplied by James Hardie®

- Provide this warranty on the manufacturer/supplier standard form (if not available then use the standard form in the general section 1237WA WARRANTY AGREEMENT)
- Commence the warranty from the date of purchase

© CIL Masterspec Sep 2026

Refer to the general section 1237 WARRANTIES for additional requirements.

1.6 WARRANTY - INSTALLER/APPLICATOR

Provide an installer/applicator warranty:

2 years For installation

- Provide this warranty on the installer/applicator standard form (if not available then use the standard form in the general section 1237WA WARRANTY AGREEMENT)
- Commence the warranty from the date of practical completion of the contract works

Refer to the general section 1237 WARRANTIES for additional requirements.

Requirements

1.7 QUALIFICATIONS GENERALLY

Refer to 1270 CONSTRUCTION for requirements relating to qualifications.

1.8 NO SUBSTITUTIONS

Substitutions are not permitted to any of the specified systems, components and associated products listed in this section.

1.9 INFORMATION FOR OPERATION AND MAINTENANCE

Refer to the general section 1239 OPERATION & MAINTENANCE for provision of the following general operation and maintenance information as electronic PDF format documents:

James Hardie® Linea™ Weatherboard Care and Maintenance guide

Provide this information prior to practical completion.

Compliance information

1.10 COMPLIANCE - CODEMARK CERTIFICATE

James Hardie® Linea™ Weatherboard meets the requirements of the NZBC when used within the Conditions and Limitations of its Certificate of conformity CMNZ30018

1.11 COMPLIANCE - BRANZ APPRAISAL 447 - OVER DRAINED CAVITY

James Hardie® Linea™ Weatherboard has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 447.

2 PRODUCTS

Materials

2.1 LINEA™ WEATHERBOARDS

Pre-primed lightweight cellulose cement composite bevel back weatherboards manufactured to AS/NZS 2908.2. 16mm thick, 4200mm long. Tongue and groove ends. Available in 150mm or 180mm widths. Refer to SELECTIONS.

2.2 WALL UNDERLAY

For flexible wall underlays and rigid wall underlays, refer to the appropriate separate section(s).

2.3 TIMBER CAVITY BATTENS

Radiata pine battens, minimum 45mm wide x 18mm thick, H3.1 treated, height to match timber framing studs.

Components

2.4 LINEA™ EXTERNAL SLIMLINE BOX CORNER MOULD

Etched primed aluminium extrusion with box section. Available in 2700mm and 4000mm lengths. Refer to SELECTIONS.

2.5 LINEA™ INTERNAL CORNER "W" MOULD 90

Etched primed aluminium extrusion. Available in 2700mm and 4000mm lengths. Refer to SELECTIONS.

© CIL Masterspec Sep 2026

2.6 LINEA™ INTERNAL CORNER "W" MOULD 135
Etched primed aluminium extrusion, 2700mm length.

2.7 LINEA™ CAVITY CLOSER
35mm wide perforated PVC vented cavity closer with built in cant strip, 70mm upstand, 3000mm length. Suitable vermin proofing to NZBC E2/AS1.

2.8 FASTENER TYPE
Refer to SELECTIONS.

Accessories

2.9 TIMBER TRIMS
H3.1 treated timber scriber, sill and eave mould as detailed.

2.10 ADOS CRC BUILDERS FILL
Two part polyester composite exterior grade fill.

2.11 PRIMER
Refer to SELECTIONS.

2.12 SEALANT
Refer to SELECTIONS.

2.13 PAINT
Refer to painting section/s.

3 EXECUTION

Conditions

3.1 DELIVERY, STORAGE & HANDLING OF PRODUCTS
Refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.

3.2 ROUTINE MATTERS
Refer to 1250 TEMPORARY WORKS & SERVICES for protection requirements.
Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.3 PRE-INSTALLATION REQUIREMENTS
Check work previously carried out and confirm it is of the required standard for this part of the work.

Installation/application

3.4 STANDARDS AND TOLERANCES
Refer to the general section 1270 CONSTRUCTION for general requirements.

3.5 INSTALLATION GENERALLY
To James Hardie® Linea™ Weatherboard technical specifications.

3.6 INSTALL CAVITY CLOSURE
Install cavity closure at base of walls, on horizontal/raking open junctions and over openings (windows, meter boards, etc).

3.7 INSTALL CAVITY BATTENS
Fix cavity battens vertically over wall underlay/rigid air barrier to wall framing studs. Tack in place with 40 x 2.8mm galvanized nails. Seal the top of the cavity with flexible sealant. Do not use horizontal cavity battens. Use cavity spacers where fixing is required between cavity battens.

3.8 PENETRATIONS AND FLASHINGS
Confirm that exterior wall openings have been prepared ready for the installation of all window and door frames and other penetrations through the cladding. Required preparatory work includes the following:

© CIL Masterspec Sep 2026

- Wall underlay appropriately incorporated with penetration and junction flashings.
- Materials lapped in a way that water tracks down to the exterior face of the wall underlay.
- Wall underlay to openings finished and dressed off ready for the installation of window and door frames and other penetrations.
- Required holes in cladding accurately formed and cut to James Hardie® requirements, ensure (if required) services penetration grommets/sleeves/seals/tapes are in place prior to cladding installation.
- Claddings neatly finished off to all sides of openings
- Installation of flashings (those required to be installed prior to installation of penetrating elements).

3.9 INSTALL CORNER MOULDS

Nail fix corner moulds.

3.10 CUT LINEA™ WEATHERBOARDS

Cut weatherboards to required lengths. Prime site cut ends prior to installation.

3.11 JOINTING LINEA™ WEATHERBOARDS

Apply a continuous bead of flexible sealant to tongue edge of weatherboard fitting joints off-stud to groove ends.

3.12 FIX LINEA™ WEATHERBOARDS - CONCEALED NAILING

Fit weatherboard horizontally. Fix at 20mm from top of weatherboard into framing. Finish nails flush to surface. Fit subsequent weatherboard row with 30mm overlap to previous weatherboard concealing the nail fixing under the horizontal lap.

3.13 FIX LINEA™ WEATHERBOARDS - FACE NAILING

Install weatherboards horizontally with 30mm overlap. Pre-drill hole. Fix via hand-driven nails at 15mm from bottom of upper weatherboard through horizontal lap (i.e. through 2 rows of weatherboards) into framing. Punch nails 2mm below the surface and fill nails heads with builders fill.

3.14 FIXING LINEA™ WEATHERBOARD ENDS - CONCEALED NAILING

Fix minimum 25mm from weatherboard end for hand driven nails or minimum 50mm from weatherboard ends for gun driven nails.

Completion & Commissioning

3.15 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

For further details on selections go to www.jameshardie.co.nz.
Substitutions are not permitted to the following, unless stated otherwise.

4.1 JAMES HARDIE® LINEA™ WEATHERBOARDS - CAVITY FIXED

Location:	Refer Plans
Manufacturer:	James Hardie® New Zealand Ltd
Brand:	Linea™ Weatherboard
Thickness:	16mm
Width:	150mm
Construction type:	Cavity fixed
Fixing method:	Concealed nailing
Fastener type:	Galvanized, 60 x 2.87mm D head gun nail

© CIL Masterspec Sep 2026

Components

4.2 LINEA™ SLIMLINE BOXED CORNER

Location:	Refer Details
Manufacturer:	James Hardie® New Zealand Ltd
Brand/type:	Linea™ External Slimline Box Corner
Material:	Aluminium
Length:	2700mm

4.3 LINEA™ INTERNAL CORNER "W" MOULD 90

Location:	Refer Details
Manufacturer:	James Hardie® New Zealand Ltd
Brand/type:	Linea™ 90° internal 'W' mould
Material:	Aluminium
Length:	2700mm

Accessories

4.4 PRIMER

Brand/type: Resene Quick Dry

4.5 ADHESIVE SEALANT

Brand/type: Bostik Seal N Flex-1

4.6 FLEXIBLE SEALANT

Brand/type: Bostik Seal N Flex-1



© CIL Masterspec Sep 2026

4239JH JAMES HARDIE® SOFFITS

1 GENERAL

This section relates to the supply and fixing of James Hardie® soffit and eave linings.
It includes:

- James Hardie® Hardie™ Flex Eaves Lining

Documents

1.1 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10 m in height
AS/NZS 1170.2:2011	Structural design actions - Wind actions
AS/NZS 2908.2	Cellulose-cement products - Flat sheet
NZS 3604	Timber-framed buildings

1.3 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer and supplier documents relating to this part of the work:

Eaves and Soffits Installation Manual by James Hardie® (Feb 2025)
Fire and Acoustic Design Manual by James Hardie, May 2025
James Hardie® Eaves and Soffit Care and Maintenance
BRANZ Appraisal 1285 (2025) - James Hardie Fire And Acoustic Wall Systems - Amended 16 June 2026

Manufacturer/supplier contact details

Company:	James Hardie New Zealand Limited
Web:	www.jameshardie.co.nz
Email:	info@jameshardie.co.nz
Telephone:	0800 808 868

Warranties

1.4 WARRANTY - MANUFACTURER/SUPPLIER

Provide a material manufacturer/supplier warranty:

15 years:	For lining product and accessories

- Provide this warranty on the manufacturer/supplier standard form (if not available then use the standard form in the general section 1237WA WARRANTY AGREEMENT)
- Commence the warranty from the date of purchase

Refer to the general section 1237 WARRANTIES for additional requirements.

Requirements

1.5 QUALIFICATIONS GENERALLY

Refer to 1270 CONSTRUCTION for requirements relating to qualifications.

1.6 NO SUBSTITUTIONS

Substitutions are not permitted to any of the specified systems, components and associated products listed in this section.

© CIL Masterspec Sep 2026

1.7 INFORMATION FOR OPERATION AND MAINTENANCE

Refer to the general section 1239 OPERATION & MAINTENANCE for provision of the following general operation and maintenance information as electronic PDF format documents:

James Hardie® Eaves and Soffit Care and Maintenance

Performance

1.8 PERFORMANCE - UP TO AND INCLUDING VERY HIGH WIND ZONE

The design wind speeds/zones are to NZS 3604, up to and including Very High Wind Zone. Eaves and Soffits Installation Manual by James Hardie® requirements are suitable for these conditions.

2 PRODUCTS

Materials

2.1 HARDIE™ FLEX EAVES LINING

James Hardie® Hardie™ Flex Eaves Lining 4.5mm and 6mm thick cellulose fibre reinforced cement sheet. Manufactured to AS/NZS 2908.2 from Portland cement, ground sand, cellulose fibre and water.

Components

2.2 FASTENER TYPE

Fasteners to minimum durability requirements of the NZBC. Refer to NZBC E2/AS1, Table C.1.1.1A: Material selection, for fixing material, and NZBC E2/AS1, Table C.1.1.1B: Compatibility of materials in contact, for selection of suitable fixing materials and their compatibility with other materials.

Exposure	Fixing	Fixing Material	Zone
Sheltered	Nail	Hot-dip galvanized steel	B
Sheltered	Nail	Stainless steel	B, C, D, E
Sheltered	Screw	Stainless steel	B, C, D, E

Check against SED (specific engineering design) requirements for microclimate conditions. Refer to SELECTIONS for fastener type.

Components - Hardie™ Flex Eaves Lining

2.3 SOFFIT JOINTERS AND MOULDS

Extruded uPVC jointer, capping and scotia mould.

2.4 HARDIE™ FLEX NAILS

Hardie™ Flex Nail, 40 x 2.8mm stainless steel or galvanized nail, Refer to SELECTIONS.

2.5 INSEAL TAPE

Inseal® 3259, 1.5mm thick x 48mm wide black compressible medium density closed cell foam tape.

2.6 POLYPROPYLENE TAPE

Polypropylene tape, 30mm minimum width.

Components - General

2.7 FLEXIBLE JOINT SEALANT

Refer to SELECTIONS.

3 EXECUTION

Conditions

3.1 DELIVERY, STORAGE & HANDLING OF PRODUCTS

Refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.



© CIL Masterspec Sep 2026

3.2 ROUTINE MATTERS

Refer to 1250 TEMPORARY WORKS & SERVICES for protection requirements.

Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.3 PRE-INSTALLATION REQUIREMENTS

Check work previously carried out and confirm it is of the required standard for this part of the work.

Moisture content timber framing: 18% maximum

3.4 STANDARDS AND TOLERANCES

Refer to the general section 1270 CONSTRUCTION for general requirements.

Application - general

3.5 SHEET LAYOUT

All sheet edges must be fully supported by framing or rebates in fascia and barge boards.

3.6 CUTTING SOFFIT CLADDING

Cut sheets dry using score and snap method, hand guillotine method or fibreshear heavy duty method. If these methods are not feasible, use an alternative manufacturer approved method.

3.7 CIRCULAR HOLE FORMING

Mark the centre of the hole on the sheet, pre-drill a pilot hole. Use the pilot hole as a guide for a hole saw fitted to a heavy duty electric drill.

3.8 IRREGULAR HOLE FORMING

Drill a series of small holes around the perimeter of the proposed hole, tap out the waste piece from the sheet face.

3.9 INSTALL HARDIE™ FLEX EAVES LINING

Install in accordance with James Hardie® installation manual requirements. Refer to SELECTIONS for fixing and jointing methods.

3.10 BUTT JOINT

Paint sheet edges prior to installation.

3.11 CONTROL JOINT

Install control joint to James Hardie® installation manual requirements.

3.12 FASTENER - SIZE AND LAYOUT

Fix sheets to framing using fasteners as nominated in SELECTIONS. Fix to James Hardie® installation manual requirements.

3.13 SEALANTS

Application and use of sealants to manufacturer's instructions. Check with sealant manufacturer prior to coating over sealants.

3.14 PAINTING

Refer to painting section/s for protective coating system.

Completion

3.15 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

For further details on selections go to www.jameshardie.co.nz
Substitutions are not permitted to the following, unless stated otherwise.

© CIL Masterspec Sep 2026

Materials

4.1 HARDIE™ FLEX EAVES LINING

Location:	Eaves
Brand/type:	James Hardie® Hardie™ Flex Eaves Lining
Thickness:	4.5mm
Width:	450mm, 600mm
Fixing Method:	Hardie™ Flex nails
Fixing type:	Galvanized Hardie™ Flex Nail, 40 x 2.8mm
Joint detail:	Soffit 4.5mm PVC 2-way Jointer (for negative detail) for 4.5mm thick sheet.

© CIL Masterspec Sep 2026

4241 PROFILED METAL CLADDING

1 GENERAL

This section relates to the supply and fixing of proprietary overlap rigid sheet profiled metal wall cladding complete with accessories.

1.1 RELATED WORK

Refer to 4161 UNDERLAYS, FOIL AND DPC for underlays, foils and DPC.

1.2 ABBREVIATIONS

The following abbreviations are used throughout this part of the specification:

BMT	Base metal thickness
NZMRM	New Zealand Metal Roofing Manufacturers Inc

Documents

1.3 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC C/AS1	Protection from fire for buildings with sleeping (residential) and outbuildings (risk group SH)
NZBC C/AS2	Protection from fire for buildings other than risk group SH
NZBC C/VM2	Framework for fire safety design
NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10 m in height
AS/NZS 1170.2:2011	Structural design actions - Wind actions
AS 1397	Continuous hot-dip metallic coated steel sheet and strip - Coatings of zinc and zinc alloyed with aluminium and magnesium
AS 3566	Self-drilling screws for the building and construction industries
NZS 3602	Timber and wood-based products for use in building
NZS 3604	Timber-framed buildings
NZMRM CoP	NZ Metal Roof and Wall Cladding Code of Practice

1.4 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer's and supplier's documents relating to this part of the work:

Manufacturer/supplier contact details

Company:	Armorsteel®
Web:	https://www.armorsteel.co.nz/
Email:	Sales@armoursteel.co.nz
Telephone:	0800 27 6677

Warranties

1.5 WARRANTY - MANUFACTURER/SUPPLIER

Warrant this work under normal environmental and use conditions against materials failure.

15 years:	For failure of coating adhesion
15 years:	For weatherproofing by material penetration
Form:	Cladding manufacturers standard form

Requirements

1.6 WARRANTY - INSTALLER/APPLICATOR

Warrant this work under normal environmental and use conditions against weatherproofing failure.

5 years:	From the date of completion of the roof
Form:	Metal wall cladding installer's standard form

© CIL Masterspec Sep 2026

Include a copy of the cladding manufacturers' maintenance requirements with the warranty. Refer to the general section 1237 WARRANTIES - INSTALLER/APPLICATOR for additional requirements.

1.7 QUALIFICATIONS

Carry out the cladding work with experienced, competent installers familiar with the products being used and preferably with appropriate qualifications such as the National Certificate in Metal Roofing and Cladding. And for Restricted Building Work shall also be, a LBP or supervised by a LBP.

Performance

1.8 PERFORMANCE

Install cladding materials and associated flashings and accessories to form a weathertight and durable system for the completed cladding system, including all penetrations through the walls and junctions with roofs and parapets.

1.9 SPREAD OF FIRE

To NZBC C/AS1, 5.3 External cladding systems, NZBC C/AS2, 5.5 External cladding systems, or NZBC C/VM2.

Performance - Wind (design by contractor)

1.10 DESIGN PARAMETERS - NON SPECIFIC DESIGN

Design the installation to the wind zone parameters of NZS 3604, table 5.4.

Refer to general section 1220 PROJECT for details.

2 PRODUCTS

Materials

2.1 EXTERIOR CAVITY WALL BATTENS

Radiata pine battens, minimum 20mm thickness, width and height to match timber framing studs. To NZS 3602, table 1, reference 1D.10, Requirements for wood-based building components to achieve a 50-year durability performance.

2.2 EXTERIOR CAVITY CLOSER/VERMIN-PROOFING

Perforated uPVC or aluminium trays with upstands. Upstand one side 10mm and the other 75mm. Length and width to suit cavity.

2.3 PRE-FINISHED ALUMINIUM/ZINC ALLOY COATED STEEL

Formability G550 steel sheet coated to AS 1397.

Coating class: AZ 150

2.4 FASTENERS GENERALLY

Minimum Class 4 and durability not less than the roofing material being fixed. Screw fasteners to be head stamped identifying the manufacturer and class.

2.5 FIXING CLIPS

Galvanized steel (powder coated for aluminium) to suit the material and profile of the rigid sheet and location as required by the cladding manufacturer. Fix to steel with 16mm x 10 gauge galvanized wafer head self-drilling screws and to timber with 50mm long x 4.5mm galvanized spiral rolled flat head nails.

2.6 FIXING SCREWS

To AS 3566. To comply with AS 3566. Screws appropriate to the cladding material and the supporting structure, as required by the cladding manufacturer and with a durability no less than the material fixed. Screws into timber to penetrate by minimum 30mm.

2.7 RIVETS

Sealed aluminium, minimum diameter 4mm for use with zinc coated, zinc/aluminium coated or aluminium cladding.

© CIL Masterspec Sep 2026

Components

2.8 FLASHINGS GENERALLY

Material, grade and colour as detailed and scheduled. Ensure that materials used for flashings are compatible with the window frame materials and fixings and cladding materials and fixings.

2.9 FLASHINGS

To NZBC E2/AS1, 4.0 Flashings. Formable grade 0.55mm BMT for galvanized, aluminium/zinc-coated and pre-painted steel, and 0.9mm for aluminium (or 0.7mm for small aluminium flashings) to the same standards as the profiled sheets, notched where across profile or provided with a soft edge.

2.10 WALL AND PARAPET FLASHINGS

To NZBC E2/AS1, 4.0 Flashings. Supplied by the cladding manufacturer to match or to suit the cladding.

Accessories

2.11 SEALANT

Neutral curing MS silicone or MS polymer sealant as required by the cladding manufacturerand used as directed.

2.12 CLOSURE STRIPS

Non-bituminous compressible, profiled foam strips to fit the sheet profile.

2.13 LAP SEALING TAPE

Closed cell self adhesive nitrile tape.

3 EXECUTION

Conditions

3.1 INSPECTION

Inspect the wall framing and supporting structure to ensure that it is complete and fully braced ready for cladding.

3.2 FRAMING TIMBER MOISTURE

When continuous metal cladding etc. Runs along a long continuous timber member and is directly fixed to it, the timbers equilibrium moisture content (EMC) to be 18% or less. For flashings in this situation (sometimes called transverse flashings) the framing EMC to be maximum 16%, and preferably as low as 12%. Transverse flashings can be temporarily tacked in place and final fixing done when moisture content is acceptable.

3.3 STORAGE

Take delivery of and accept packs of cladding undamaged on delivery. Reject all damaged material. Store on a level firm base with packs well ventilated and completely protected from weather and damage. Do not allow moisture to build up between sheets. If sheet packs become wet, fillet or cross stack to allow air movement between sheets.

3.4 HANDLING

Avoid distortion and contact with damaging substances, including cement. Do not drag sheets across each other and other materials. Protect edges and surface finishes from damage.

3.5 SEPARATION

Isolate dissimilar materials in close proximity as necessary by painting the surfaces or fitting separator strips of compatible materials. Place isolators between metals and treated timber and cement based materials. Do not use unpainted lead sheet or copper in contact with or allow water run-off onto galvanized and aluminium/zinc-coated metals.

© CIL Masterspec Sep 2026

Application

3.6 SET-OUT

Set cladding to vertical plumb lines and maintain verticality. Set all exposed fixings with horizontal string lines. Carefully set out sheets with side laps away from the main line of sight, and with the widths of end sheets the same. Check during fixing to eliminate creep or spread and to keep fastenings in line.

3.7 AVOID END LAPS

End laps are not permitted, except where specifically detailed.

3.8 MOVEMENT JOINTS

Fixing and jointing to conform with the cladding manufacturer's requirements for thermal movement.

Over timber framing, transverse flashings (those running along continuous framing members) to have expansion joints at maximum 12m centres.

3.9 FIXING GENERALLY

Install and fix in accordance with the NZMRM CoP, and to the cladding manufacturer's required fixing patterns and details for each area of the building cladding. Use only screws as required by the cladding manufacturer. Paint colour matched fixings and accessories before installation.

3.10 INSTALL DRAINED CAVITY

20mm nominal thickness drained cavity to NZBC E2/AS1, 9.0 Wall claddings, where required. Fix vertical cavity battens to wall framing studs and provide a separation strip of metal cladding underlay over batten. The battens are fixed by the cladding fixings which will penetrate the wall framing studs over the wall underlay. Install cavity closer/vermin-proofing at base of wall, open horizontal (or raking) junctions and over openings (windows, meters etc).

3.11 PENETRATIONS

Confirm that exterior wall openings have been prepared ready for the installation of all window and door frames and other penetrations through the cladding. Required preparatory work includes the following:

- wall/cladding underlay to openings finished and dressed off ready for the installation of window and door frames and other penetrations
- claddings neatly finished off to all sides of openings
- installation of flashings (those required to be installed prior to installation of penetrating elements).

3.12 MARKING AND CUTTING

Cut only by shearing tools. Do not use black lead pencils for marking aluminium/zinc coated products.

3.13 FIX SHEETS

Fix sheets in place using the fastening system required by the manufacturer of the specified profiled metal cladding, making due allowance for dynamic local wind pressures on the building and thermal movement in the sheet.

3.14 INSTALL FLASHINGS

Flash to penetrations, cap corners and edges, using sealant and rivets to detail, to the cladding manufacturer's requirements and to NZBC E2/AS1.

3.15 COMPLETE

Ensure the work is complete with all flashings, finishing and trim properly installed so the cladding system is completely weathertight.

3.16 SEPARATION

Separate metal sheeting from CCA treated timber with wall underlay or other suitable isolation material.

Completion

3.17 REPLACE

Replace all damaged or marked elements.

© CIL Masterspec Sep 2026

3.18 LEAVE

Leave this work complete with all necessary flashings and capping all properly installed as the work proceeds so the finished cladding is completely weathertight.

3.19 REMOVE

Remove debris, unused materials and elements from the site.

4 SELECTIONS

4.1 TIMBER CAVITY BATTENS

Timber species:	Radiata pine
Timber grade:	Merchantable
Treatment:	H3.1

4.2 CAVITY CLOSER

Brand/type:	To Be selected
Material:	To be selected

4.3 PRE-FINISHED ALUMINIUM/ZINC ALLOY COATED STEEL - PROFILED METAL CLADDING

Armoursteel Linear 8000, BMT.55mm

4.4 NAILS, SCREWS AND FASTENINGS

Sheathing material:	
Fixing/fastening:	Pre-finished self drilling/tapping screw with neoprene seal washer
Centres:	1200mm

4.5 FLASHINGS

Location:	Refer Details
Material/thickness:	Alum/Zinc coated steel: 0.55mm
Finish:	to be selected

© CIL Masterspec Sep 2026

4311D DIMOND PROFILED METAL ROOFING

1 GENERAL

This section relates to the supply and fixing of Dimond Roofing profiled metal roofing complete with associated accessories and components.

1.1 RELATED WORK

Refer to 4161T Kingspan Thermskraft UNDERLAYS, FOIL AND DPC for underlays, foils and DPC.

1.2 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

BMT	Base metal thickness
LBP	Licenced Building Practitioner
NZMRM	New Zealand Metal Roofing Manufacturers Inc
MS	Modified silicone

Documents

1.3 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

BPS	Building Product Specifications
NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10 m in height
NZBC G12/AS1	Water Supplies
AS/NZS 2728	Prefinished / prepainted sheet metal products for interior / exterior building applications
NZS 3604	Timber-framed buidings
AS 1397	Continuous hot-dip metallic coated steel sheet and strip - Coatings of zinc and zinc alloyed with aluminium and magnesium
AS 3566	Self-drilling screws for the building and construction industries
ISO 5660.1	Reaction to fire tests - heat release, smoke production and mass loss rate. Part 1 Heat release rate (cone calorimeter method)
ISO 5660.2	Reaction to fire tests - heat release, smoke production and mass loss rate. Part 2 Smoke production rate (dynamic measurement)
NZMRM CoP	NZ Metal Roof and Wall Cladding Code of Practice

1.4 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer and supplier documents relating to this part of the work:

Dimond Roofing and Cladding Systems Manual (January 2021)
Dimond Roofing Profile BPIR
Dimond Roofing UniCote® LUX Brochure
UniCote® LUX Data Sheet
AWTA Product Testing Reports for UniCote® Lux

Manufacturer/supplier contact details:

Company:	Fletcher Steel Ltd
Trading as:	Dimond Roofing
Web:	www.dimond.co.nz
Email:	roofspec@dimond.co.nz
Telephone:	0800 346 663 (0800 DIMOND)

© CIL Masterspec Sep 2026

Warranties

1.5 WARRANTY - MANUFACTURER/SUPPLIER

Provide a material manufacturer/supplier warranty:.

18 years - paint	for failure of coating adhesion
50 years - perforationyears: years:	for weatherproofing by material penetration

- Provide this warranty on the manufacturer/supplier standard form (if not available then use the standard form in the general section 1237WA WARRANTY AGREEMENT)
- Commence the warranty from the date of practical completion of the contract works

Refer to the general section 1237 WARRANTIES for additional requirements.

1.6 WARRANTY - INSTALLER/APPLICATOR

Provide an installer/applicator warranty:

5 years	for installation

- Provide this warranty on the installer/applicator standard form (if not available then use the standard form in the general section 1237WA WARRANTY AGREEMENT)
- Commence the warranty from the date of practical completion of the contract works.

Refer to the general section 1237 WARRANTIES for additional requirements.

Requirements

1.7 QUALIFICATIONS GENERALLY

Refer to 1270 CONSTRUCTION for requirements relating to qualifications.

1.8 NO SUBSTITUTIONS

Substitutions are not permitted to any specified system, components and associated products listed in this section.

1.9 INFORMATION FOR OPERATION AND MAINTENANCE

Refer to the general section 1239 OPERATION & MAINTENANCE for provision of the following maintenance information contained in the Dimond Roofing & Cladding Systems Manual - Routine Maintenance, as electronic PDF format.

Provide this information prior to practical completion.

Compliance information

1.10 COMPLIANCE - PROPOSED ALTERNATIVE SOLUTION

Dimond various metal roofing profiles, are presented as an alternative solution for:

Clause:	E2-External moisture
Performance:	E2.3.1 Roofs must shed precipitated moisture. In location subject to snow, roofs must also shed melted snow. E2.3.2 Roofs and exterior walls must prevent the penetration of water that could cause undue dampness, damage to building elements, or both.

Profiles:

Trapezoidal profile:	Dimond DP955, Solar Rib, Steelspan 900 & Topspan
Clip fixed, trough:	Dimondek 630

Proposed alternative solution is supported by:

- In-service history
- NZMRM CoP
- Dimond standard details and installation guidelines

© CIL Masterspec Sep 2026

2 PRODUCTS

Materials

2.1 STEEL - TYPE AM COATING (ALUMINIUM/ZINC/MAGNESIUM ALLOY), PREPAINTED

Formability steel sheet, G550 for roll forming or G300 for flashings, coated to AS 1397. Prefinished /prepainted to AS/NZS 2728.

Fixings

2.2 FASTENERS GENERALLY

Fixings and fasteners are to be compatible with all materials, the environment and meeting the requirements of the NZ Building Code. Installation is to be in accordance with NZBC E2/AS1 and/or the NZMRM CoP and Dimond Roofing requirements.

For fixing patterns refer to Dimond Roofing Fixing Charts for the selected profile.

2.3 FIXING SCREWS

To AS 3566. Screws appropriate to the roofing material and the supporting structure, as required by Dimond Roofing and with a minimum Class 4 or 5 durability and not less than the material being fixed.

Screw into timber to penetrate by minimum 30mm and into steel to penetrate by minimum 3 threads. Screw fasteners to be head stamped identifying the manufacturer and class. Refer to SELECTIONS

2.4 RIVETS - ALUMINIUM

Sealed aluminium, minimum diameter 4mm, for use with zinc coated, zinc/aluminium coated or aluminium roofing.

Components

2.5 FLASHINGS GENERALLY

To NZBC E2/AS1, 4.0 Flashings.

Formable grade 0.55 BMT for galvanized, Type AZ or AM - coated and pre-painted steel, 0.5mm BMT for Copper 0.7mm and 0.90 for aluminium (or 0.7mm for small aluminium flashings) to the same standards as the profiled sheets, notched where across profile or provided with a soft edge.

2.6 BOOT FLASHINGS

Generally to NZBC E2/AS1, 8.4.12 Roof penetrations

EPDM proprietary pipe flashing laid on 45° bias to roofing, with over-flashing (soaker flashing) if required.
A boot flashing should be positioned so that it dams a roofing pan no more than 50%, if this cannot be avoided use an over-flashing back to the ridge and fix the boot flashing to that.

Accessories

2.7 WIRE NETTING AND SAFETY MESH

Refer to 4161 UNDERLAYS, FOIL AND DPC.

2.8 UNDERLAY AND REFLECTIVE FOIL

Refer to 4161T UNDERLAYS, FOIL AND DPC

2.9 SEALANT

Neutral curing MS sealant or polymer sealant as required by the roofing manufacturer and used as directed.

2.10 CLOSURE STRIPS

Non-bituminous compressible, profiled foam strips to fit the sheet profile.

2.11 LAP SEALING TAPE

Closed cell self adhesive nitrile tape.

© CIL Masterspec Sep 2026

3 EXECUTION

Conditions

3.1 DELIVERY, STORAGE & HANDLING OF PRODUCTS

Refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.

3.2 ROUTINE MATTERS

Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.3 PRE-INSTALLATION REQUIREMENTS

Check work previously carried out and confirm it is of the required standard for this part of the work.

Inspect the roof framing and supporting structure to ensure that it is complete and fully braced ready for roofing and free from any misalignments or protrusions that could damage the roofing. Provide a fall for roof drainage minimum as required by selected profile.

Ensure moisture content is:

Timber framing: 18% maximum (16% or preferably less for under transverse flashings)

Transverse flashings can be temporarily tacked in place and final fixing done when moisture content is acceptable.

3.4 SEPARATION

Isolate dissimilar materials in close proximity as necessary by painting the surfaces or fitting separator strips of compatible or inert materials. Place isolators such as flashing tapes or drainage mat between metals and CCA treated timber, cement based materials, and mixing aluminium sheet and steel mesh.

3.5 INSTALLATION DAMAGE

Take care to avoid damaging pre-finished roofing both during and after fixing. Wear only soft-soled shoes on the finished surface.

Installation/application

3.6 STANDARDS AND TOLERANCES

Refer to the general section 1270 CONSTRUCTION for general requirements.

3.7 INSTALLATION GENERALLY

Install Dimond profile metal roofing in accordance with Dimond Roofing requirements and NZMRM CoP and to form a complete water tight roofing system, including all flashings, cappings and penetrations.

3.8 SET-OUT

Carefully set out with consideration of the position of side laps to take account of the prevailing wind and line of sight. Ensure all sheets are square and oversailing the gutter true to line. Check during fixing to eliminate creep or spread and string lines along purlin centres to keep fastenings in line.

3.9 END LAPS

End laps should be avoided, except where specifically detailed. Where end laps are necessary, seal both ends of the lap with lap sealing tape or sealant and 4mm sealed pop rivets at maximum 50mm centres, to detail in NZMRM CoP.

3.10 SEAL CUT EDGES

In very severe marine environments seal cut edges of pre-coated steel sheet with edge protection lacquer before fixing to the cladding manufacturer's requirements.

3.11 THERMAL MOVEMENT

For sheet lengths more than 18 metres, make provision for thermal expansion where required

© CIL Masterspec Sep 2026

3.12 FIXING GENERALLY

Install and fix in accordance with NZBC E2/AS1, the NZMRM CoP and the Dimond Roofing required fixing patterns and details to suit project wind loadings stated in the general section 1220 PROJECT or in accordance with specific design in accordance with project engineer's requirement.

Use only screws and clips as required by Dimond Roofing. Paint colour matched fixings and accessories before installation.

When a load spreading washer is required, pre-drill a 10mm oversized hole to accommodate the EPDM washer.

3.13 MARKING AND CUTTING

Use chalk line, Chinagraph pencils or coloured pencil for marking roof sheets prior to cutting. Do not use lead pencil for marking Zincalume®, Colorsteel® and Colorcote®. Cut by shear only, using nibblers or hand snips. Remove all cutting and drilling debris from the roof.

3.14 STOP ENDS AND DOWNTURNS

Form stop-ends at the upper end of sheets. Form downturns at the gutter line where the roof pitch is less than 8 degrees. Form using the required tools.

Application - Flashings

3.15 FLASHINGS

Flash roof to parapets, walls and penetrations to detail. Flashings to be installed on timber framing with moisture content of less than 18%. Where no detail is provided flash to NZMRM CoP recommendations and Dimond requirements. Cut accurately and fix using sealant and rivets to detail and to Dimond requirements to form a weatherproof cover. For highly visible flashings, plan joints/junction to take account of the aesthetic requirements.

3.16 USE OF SEALANTS

Select and use sealants only as recommended by Dimond. Remove any swarf and clean down, apply sealant in two narrow beads transversely across flashing intersections, close to the two edges. Avoid exposing sealant on outside surfaces. Do not use sealant on Copper material, these materials are required to be soldered to complete any joint.

3.17 FLASHING PENETRATIONS

Flash all penetrations through the roof. Fit pipe flashings with a proprietary collar flashing, with other penetrations flashed as detailed and to provide a weathertight installation. Ensure that flashings are set to avoid any ponding of water.

Completion & Commissioning

3.18 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

For further details on selections go to www.dimond.co.nz.
Substitutions are not permitted to the following, unless stated otherwise.

© CIL Masterspec Sep 2026

Roofing

4.1 DIMOND ROOFING - VEEDEK ROOFING

Location:	Roofing
Profile:	Veedek
BMT/material:	0.4mm Steel
Coating system:	Galvanized, Zincalume®, COLORSTEEL® Maxam™
Colour:	Grey Friars
Protective film:	None
Effective cover:	755mm
Profile height:	28mm
Purlin material:	Timber
Fixing:	Timbertite, 12gx65, 304 Stainless steel
Fixing pattern:	Refer to Dimond Roofing Veedek literature for details

Accessories

4.2 FLASHINGS - GENERALLY

Profile:	As Required
BMT/material:	0.55mm
Coating system:	To match roofing
Paint colour:	To match roofing

© CIL Masterspec Sep 2026

4337E ECOPLY® ROOFING & DECKING

1 GENERAL

This section relates to the supply and installation of Carter Holt Harvey Plywood Ltd Ecoply® plywood sheets as roofing and decking substrates.

1.1 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

CCA	Copper chrome arsenate
PF	Phenol formaldehyde

Documents

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10m in height
AS/NZS 1604.3:2012	Preservative-treated wood-based products - Plywood
AS/NZS 2269.0	Plywood - Structural - Specifications

1.3 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer and supplier documents relating to this part of the work:

Ecoply® Specification and Installation Guide (September 2025)
Ecoply® Structural Plywood used in Roofs Product Technical Statement and Building Product Information Sheet

Manufacturer/supplier contact details

Company:	Carter Holt Harvey Plywood Limited
Web:	www.chhply.co.nz
Email:	info@ecoply.co.nz
Telephone:	0800 326 759

Requirements

1.4 QUALIFICATIONS GENERALLY

Refer to 1270 CONSTRUCTION for requirements relating to qualifications.

1.5 NO SUBSTITUTIONS

Substitutions are not permitted to any of the specified systems, components and associated products listed in this section.

2 PRODUCTS

Materials

2.1 ECOPLY® STRUCTURAL SQUARE EDGE PLYWOOD

Square edge, synthetic phenolic (PF) resin Type A bonded timber veneer plywood sheets manufactured to AS/NZS 2269.0, H3.2 CCA treated to AS/NZS 1604.3:2012. Stress grade F8/F5. Available in appearance grades CD and DD. Sheets 1200mm wide, 2400mm and 2700mm long, and available in range of thicknesses. Refer to SELECTIONS.

Components

2.2 SCREWS

Hot dipped galvanized or stainless steel countersunk screws. Refer to SELECTIONS.

© CIL Masterspec Sep 2026

2.3 ADHESIVE

Refer to SELECTIONS.

2.4 TIMBER PRESERVATIVE TREATMENT

Soudal Metalex Concentrated Timber Preservative treatment, in clear or green colour. Refer to SELECTIONS.

3 EXECUTION

Conditions

3.1 DELIVERY, STORAGE & HANDLING OF PRODUCTS

Refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.

3.2 ROUTINE MATTERS

Refer to 1250 TEMPORARY WORKS & SERVICES for protection requirements.

Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.3 PRE-INSTALLATION REQUIREMENTS

Check work previously carried out and confirm it is of the required standard for this part of the work.

Timber substrate: 18% maximum moisture content

Installation/application

3.4 STANDARDS AND TOLERANCES

Refer to the general section 1270 CONSTRUCTION for general requirements.

3.5 INSTALLATION GENERALLY

Install in accordance with Ecoply® Specification and Installation Guide.

3.6 TREAT CUT EDGES

Brush timber preservative onto cut edges and penetration cut outs.

3.7 APPLY ADHESIVE

Apply a bead or daubs of adhesive to framing. When fastening sheets over adhesive, work from the middle of the sheet outwards to develop glueline pressure.

3.8 LAY PLYWOOD SHEETS - SQUARE EDGE

Lay sheets continuous over at least two spans in a staggered layout with face-grain of sheet at right-angles to support and with sheets in square, true alignment and plane. Provide 3mm expansion gap between all sheet edges. Fully support all sheet edges.

3.9 FIX PLYWOOD SHEETS

Fix sheets to framing to the Ecoply fixing pattern. Maintain clearances to sheet edges to Ecoply requirements. Finish fastener heads flush with the panel surface.

3.10 UNDER MEMBRANE ROOFING

To NZBC E2/AS1, 8.5 Membrane roofs and decks. Fix plywood sheet oriented with C grade face up, and falls as shown on the drawings. Provide a 5mm radius chamfer to external edges where the membrane is to be wrapped over. Screw and adhesive fix sheets with stainless steel screws working from the middle of the sheet outwards to develop glueline pressure. Fix internal corner fillets.

Completion

3.11 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

For further details on selections go to www.chhply.co.nz

© CIL Masterspec Sep 2026

Substitutions are not permitted to the following, unless stated otherwise.

4.1 ECOPLY® STRUCTURAL SQUARE EDGE PLYWOOD - MEMBRANE ROOF

Location:	Deck
Manufacturer/supplier:	Carter Holt Harvey Plywood Ltd.
Brand:	Ecoply® Structural Square Edge plywood
Stress grade:	F8/F5
Appearance grade:	CD
Sheet thickness/ID code:	19mm/19-30-7
Size size:	1200mm wide x 2700mm long
Timber treatment:	H3.2 CCA
Timber certification:	

4.2 SCREWS - MEMBRANE ROOF

Type:	10Gx50mm countersunk self-tapping screw
Finish:	Stainless steel

4.3 ADHESIVE

Brand/type:	Soudal Gorilla Grip (polyurethane-based adhesive)

4.4 TIMBER PRESERVATIVE TREATMENT

Brand/type:	Soudal Metalex Concentrated Timber Preservative
Colour:	Green Supplementary preservative treatment for cut edges and penetration holes in plywood



© CIL Masterspec Sep 2026

4422A ARDEX BUTYNOL & BUTYSEAL MEMBRANE ROOFING

1 GENERAL

This section relates to **ARDEX** Butynol® and Butyseal as single-layer external waterproof coverings, with associated components and accessories, bonded to:

- structural plywood
- Contact ARDEX for other substrates.

1.1 RELATED WORK

Refer to 4337 PLYWOOD ROOFING & DECKING SUBSTRATE for plywood sarking.

1.2 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

PIR	Polyisocyanurate (Polyiso)

Documents

1.3 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10 m in height
AS/NZS 1604.1	Preservative-treated wood-based products - Part 1: Products and treatment
AS/NZS 2269.0	Plywood - Structural - Specifications

Documents listed above and cited in the clauses that follow are part of this specification. However, this specification takes precedence in the event of it being at variance with the cited document.

1.4 MANUFACTURER DOCUMENTS

Manufacturer and supplier documents relating to work in this section are:

ARDEX Waterproofing Manual
ARDEX Butynol® and Butyseal Product Datasheets
BRANZ Appraisal 436 - Butynol® and Butyseal Roofing Membrane Systems
BRANZ Appraisal 946 - Strandsarking for low slope membrane roofs

Copies of the above literature are available from **ARDEX New Zealand Ltd**

Web:	www.ardex.co.nz
Email:	info@ardexnz.com
Telephone:	0800 2 ARDEX (27339)

Requirements

1.5 NO SUBSTITUTIONS

Substitutions are not permitted to any specified ARDEX materials, or associated products, components or accessories.

1.6 QUALIFICATIONS

Installation of the membrane to be carried out by an ARDEX approved installer with experience in installation of Butynol roofing. Application to be strictly in accordance with current ARDEX Technical Literature and BRANZ Appraisal 436 - Butynol® and Butyseal Roofing Membrane Systems.

NOTE: An LBP is required to carry out RBW. An LBP must carry out or supervise this work. They must work within the scope of their licence class.

© CIL Masterspec Sep 2026

1.7 SYSTEM ARDEX PROJECT

Contact ARDEX with any relevant key dates and for a list of approved applicators. The contractor is to contact ARDEX prior to starting the project.

Web:	www.ardex.co.nz
Email:	info@ardexnz.com
Telephone:	0800 2 ARDEX (27339)

Warranties

1.8 WARRANTY - MANUFACTURER/SUPPLIER

Provide a material manufacturer/supplier warranty:

20 years	For Butynol

- Provide this warranty on the ARDEX manufacturer/supplier standard form
- Commence the warranty from the date of practical completion of the contract works.

Refer to the general section 1237 WARRANTIES for additional requirements.

1.9 WARRANTY - INSTALLER/APPLICATOR

Provide an installer/applicator warranty:

5 years	For Butynol installation by ARDEX approved applicator
5 years	For Butyseal installation by ARDEX approved applicator

- Provide this warranty on the ARDEX installer/applicator standard form
- Commence the warranty from the date of practical completion of the contract works.

Refer to the general section 1237 WARRANTIES for additional requirements.

Performance

1.10 TEST

Where required a suitable time lapse or water test to be carried out.

1.11 PERFORMANCE

Accept responsibility for the weather-tight performance of the completed roofing system, including all penetrations through the roof and junctions with walls and parapets. All penetrations to comply with NZBC E2/AS1 and ARDEX recommendations.

Compliance information

1.12 INFORMATION REQUIRED FOR CODE COMPLIANCE

Provide the following compliance documentation:

- Applicator approval certificate from the manufacturer / importer / distributor
- Manufacturer / suppliers warranty
- Installer / applicator warranty
- Producer Statement - Construction from the applicator / installer
- Producer Statement - Construction Review from an acceptable suitably qualified person
- Other information required by the BCA in the Building Consent Approval documents.

2 PRODUCTS

Materials

2.1 BUTYNOL® MEMBRANE

Single ply membrane compounded from butyl rubber.

Rolls 1.4m x 17.86m = 25m² coverage and thickness 1.0mm, 1.2mm ,1.5mm (2.25mm for special applications, coverage 12m²).

© CIL Masterspec Sep 2026

Components

2.2 SEAM TAPE

ARDEX uncured butyl cold gum seam tape for general lap bonding, 50mm x 30.5m

2.3 SEAM PRIMER

ARDEX WPM 299 is a solvent-based water resistant primer for general lap bonding, specially formulated for use prior to Seam Tape application.

2.4 SEALANT

ARDEX CA 20 P Silane Modified Polymer (SMP) construction adhesive and neutral curing sealant. Available in 310mL cartridge.

2.5 FLASHING TAPE

ARDEX uncured underflashing tape, 100mm x 5m. Not to be left exposed to UV. Applied using WA 98 adhesive. A cover strip of Butynol or detail tape must be applied over flashing tape to finish.

2.6 DETAIL TAPE

ARDEX self-adhesive butyl detail/finishing tape, 0.8mm thick. Available in 150mm x 30.4 m roll.

ARDEX fully-cured silicone backed detail/finishing tape. Available in 150mm x 10 m roll.

2.7 OVERLAY/COVER TAPE

ARDEX cured silicone backed self-adhesive tape to join Butyseal end laps. Available in 150mm x 30.4 m roll.

2.8 ADHESIVES AND SOLVENTS

ARDEX WA 98 Butynol contact adhesive for substrate bonding and for laps not subject to periodic ponding (pitch ≥5°), supplied in 20L pails.

2.9 EDGE TRIM

Metal or timber to ARDEX details to suit the specific location.

2.10 RELEASE TAPE

ARDEX release tape is a 25mm wide pressure sensitive tape between two silicone release backings. For all joints in plywood and Strandsarking, and junctions of plywood and Strandsarking with other materials.

Accessories

2.11 ROOFING ACCESSORIES

ARDEX substrate ventilators, roof outlets, overflows, scuppers and rainwater heads.

2.12 SCUPPER OUTLETS

Moulded scupper outlets, 105mm x 65mm or 210mm x 80mm.

3 EXECUTION

Conditions

3.1 GENERALLY

All work and materials to the ARDEX Waterproofing Manual, the current ARDEX technical literature, BRANZ Appraisal 436 and NZBC E2/AS1, 8.5 Membrane roofs and decks.

3.2 DELIVERY, STORAGE & HANDLING OF PRODUCTS

Take delivery of ARDEX Butynol® and Butyseal branded rolls, refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.

3.3 ROUTINE MATTERS

Refer to 1250 TEMPORARY WORKS & SERVICES for protection requirements.

Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.4 PRE-INSTALLATION REQUIREMENTS

Check work previously carried out and confirm it is of the required standard for this part of the work.

© CIL Masterspec Sep 2026

Moisture content:

Substructure	20% maximum
Concrete	75% RH maximum
Plywood	18% maximum

3.5 WEATHER

Apply coverings in a dry atmospheric condition and only when the air temperature is 6°C and above.

Application - preparation

3.6 PRELIMINARY WORK

Ensure that preliminary work, including formation of falls, flashing rebates, grooves, ducts, provision of battens and fillets and fixing of vents and outlets to levels, is complete and properly constructed to enable the system to work as intended. This work and the substrate to be smooth, clean and dry.

3.7 ACCEPTANCE OF SUBSTRATE

Ensure that the substrate, including fillets, outlets and projections, meets design specification and ARDEX conditions.

Ensure whichever is the greater falls are provided:

- as shown in the drawings
- to the membrane manufacturer requirements
- minimum to NZBC E2/AS1, paragraph 8.5.1.2, - 1:30 for roofs, 1:40 for decks and 1:100 for gutters.

Falls must be built into the substrate and slope to an outlet.

3.8 PLYWOOD SUBSTRATE

Ensure plywood is:

- a minimum of 17mm thick and complying with AS/NZS 2269.0
- minimum CD structural grade with the sanded C side upwards
- hazard Class H3.2 with waterborne CCA treatment to AS/NZS 1604.1, and kiln dried after treatment
- laid with staggered joints (brick bond) with all edges of the sheets fully supported or with tongue and groove jointing
- laid with the face grain at right angles to the supports
- provide with 20mm H3.2 CCA treated triangular timber fillets at the base of all upstands and chamfer all external edges a minimum of 5mm
- fixed with 10 gauge x 50mm stainless steel countersunk head screws
- fixed at 150mm centres on edges and 200mm in the body of the sheets.
- **Note: LOSP treated plywood not to be used.**

Plywood must be dry and the timber substructure to have a maximum moisture content of 18% when the membrane is adhered. Consult with plywood manufacturer for correct testing technique.

Application - laying Butynol and Butyseal

3.9 STANDARDS AND TOLERANCES

Refer to the general section 1270 CONSTRUCTION for general requirements.

3.10 CONDITIONS

Do not lay membrane in wet or misty conditions or below 6ºC. Check that the substrate is dry at time of laying. Concrete substrate maximum moisture content 75% RH (relative humidity); timber substructure maximum moisture content 20%.

3.11 GENERAL

Tape backing substrate sheet joints using 25mm ARDEX Release tape. Run out sheets and allow to relax for at least 20 minutes before laying. Do not stretch sheets or tapes in laying.

Substrate does not generally require priming. In cases of extreme absorbency a priming coat of 50/50 solution of ARDEX WA 98 adhesive/solvent may be required, consult with ARDEX to confirm.

© CIL Masterspec Sep 2026

3.12 APPLY ADHESIVE

Apply ARDEX WA98 adhesive to the substrate and the Butyl rubber sheeting by brush, spray, or roller at a spreading rate of not less than 2.5 square metres per litre. Leave to tack dry before bonding the two surfaces together.

3.13 LAY SHEETS

Lay sheets across the roof slope and lap long edges to the full width of selvage, 50mm minimum. Smooth down and roll to remove entrapped air. Adhesive bond and seal to ARDEX requirements and roll or rub down as the work proceeds.

3.14 BONDING LAPS

Bond all laps to ARDEX requirements using ARDEX Seam Tape and Seam Primer.

3.15 MINOR MOVEMENT JOINTS

Lay sheets across joint but leave unbonded on both sides.

Unbonded width: 25mm minimum

All joints and junctions with other materials to be taped using ARDEX release tape. One release backing is removed to allow the tape to be applied over all sheet substrate joints. The other release backing is left in place to provide an unbonded area under the membrane which allows for substrate movement.

3.16 INSPECT

Inspect and test joints on completion.

3.17 PENETRATIONS

Form and finish upstands, downturns, penetrations, sumps and vents to conform with ARDEX details and NZBC E2/AS1.

3.18 PENETRATIONS AND JUNCTIONS

Check that adjoining walls and parapets are prepared ready for the installation of the roofing. Confirm that the openings have been prepared ready for the installation of skylights and other penetrations through the roof. Required work includes the following:

- roofing installation neatly finished to all sides of openings and to all wall and parapet junctions
- installation of flashings (those required to be installed prior to installation of penetrating elements and/or wall linings).

Protection

3.19 ACCEPTANCE

Sign off on completed areas. The main contractor to protect and maintain roofing until completion of the contract works.

Completion & Commissioning

3.20 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

For further details on selections go to www.ardex.co.nz.
Substitutions are not permitted to the following.

4.1 ARDEX BUTYNOL MEMBRANE

Location:	Deck
Substrate:	plywood
Brand/type:	ARDEX Butynol®
Thickness:	1.5mm
Colour:	1.5mm Black

© CIL Masterspec Sep 2026

Components and Accessories

4.2 ARDEX SCUPPER OUTLETS

Location: Deck
Brand/type: ARDEX SS Clamped Leaf Guard

© CIL Masterspec Sep 2026

4521 ALUMINIUM WINDOWS AND DOORS

1 GENERAL

This section relates to the manufacture, supply, and installation of:

- aluminium windows
- aluminium doors and frames
- hardware and furniture
- overhead glazing
- flashings

1.1 RELATED WORK

Refer to glazing sections for glass types

1.2 ABBREVIATIONS AND TERMS

SLS	Serviceability limit state
ULS	Ultimate limit state
WANZ	Windows Association of New Zealand
PQAS	Powder Coating Quality Assurance System

Documents

1.3 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC E2/AS1	External moisture
NZBC F4/AS1	Safety from falling
NZBC H1/VM1	Energy efficiency
NZBC H1/AS1	Energy efficiency
AS/NZS 1580.108.1	Methods of test for paints and related materials - Determination of dry film thickness on metallic substrates - Non destructive methods
AS/NZS 1170.2	Structural design actions - Wind loads
NZS 1170.5	Structural design actions - Earthquake actions - New Zealand
AS/NZS 1734	Aluminium and aluminium alloys - flat sheets, coiled sheet and plate
AS/NZS 1866	Aluminium and aluminium alloys - Extruded rod, bar, solid and hollow shapes
NZS 3604	Timber-framed buildings
AS 3715	Metal finishing - Thermoset powder coatings for architectural applications
BS 3900	Methods of tests for paints, Part C5: Determination of film thickness
NZS 4211	Specification for performance of windows
NZS 4223.3	Glazing in buildings - Human impact safety requirements
AS/NZS 4680	Hot-dip galvanized (zinc) coatings on fabricated ferrous articles
WANZ Installation Guide:	The WANZ Guide to Window Installation as described in E2/AS1 Amendment 6.
WANZ PQAS	Powder Coating Quality Assurance System
WANZ SFA 3503-03	Anodic Oxide coatings on wrought aluminium for external architectural application (2005).
BRANZ BU 337	Protecting Window Glass from Surface Damage
AAMA 2604	Voluntary specification, performance requirements and test procedures for high performance organic coatings on aluminium extrusions and panels.
AAMA 2605	Voluntary specification, performance requirements and test procedures for superior performing organic coatings on aluminium extrusions and panels.

© CIL Masterspec Sep 2026

US Federal Specification

TT-S-001543A	Sealing compound, silicone rubber base (for caulking, sealing and glazing in buildings and other structures)
TT-S-00230C	Sealing compound, elastomeric type, single component (for caulking, sealing and glazing in buildings and other structures)

Warranties

1.4 WARRANTY - MANUFACTURER/SUPPLIER

Provide a material manufacturer/supplier warranty:

5 years: For fabrication

Refer to the general section for the required form of 1237WA WARRANTY AGREEMENT and details of when completed warranty must be submitted.

1.5 WARRANTY - INSTALLER/APPLICATOR

Provide an installer/applicator warranty:

2 years: For installation

- Provide this warranty in the installer/applicator standard form.

Refer to the general section 1237 WARRANTIES for additional requirements.

Requirements

1.6 QUALIFICATIONS

Work to be carried out by trades people experienced, competent and familiar with the materials and techniques specified.

1.7 COMPLIANCE

Windows and doors to be manufactured and installed to NZBC E2/AS1.

1.8 CERTIFICATION

Provide evidence of a certificate by a laboratory accredited by International Accreditation of New Zealand that the windows and doors offered comply with the requirements of NZS 4211.

Performance

1.9 PERFORMANCE - WINDOWS AND DOORS

To NZS 4211, including:

- deflection, opening sashes, air infiltration, water penetration, ultimate strength, torsional strength of sashes, marking.

Refer to SELECTIONS.

1.10 PERFORMANCE - STRUCTURAL/WEATHER-TIGHTNESS

The structural and weather-tight performance of the completed joinery, the glazing and infill panels is the responsibility of the window manufacturer.

Performance - Wind (design by contractor)

1.11 WIND - NON SPECIFIC DESIGN

Design the installation to the wind zone parameters of NZS 3604, table 5.4.

Refer to SELECTIONS for wind zone.

Finishes

1.12 CERTIFY COATINGS - POWDER COATING

Certify on request, compliance with this specification and support with control and sampling records. Test for film thickness to BS 3900, part C5, method No. 4, using method (b) or to AS/NZ 1580.108.1 for certifying thickness and method (a) where any dispute arises as to the thickness provided.

The coating should be applied by an applicator who can certify that the coating has been applied in accordance with the specification.

© CIL Masterspec Sep 2026

2 PRODUCTS

Materials

2.1 WINDOWS

Refer to SELECTIONS for type and finish.

2.2 DOORS

Refer to SELECTIONS for type and finish.

2.3 ALUMINIUM EXTRUSIONS

Alloy designation to comply with AS/NZS 1866. Branded and extruded for anodising or powder coating.

2.4 ALUMINIUM SHEET AND STRIP

Complying with AS/NZS 1734 of suitable thickness. Rolled for anodising or powder coating.

Alloy designation: 5251 - H16 or 5005 - H16

2.5 STAINLESS STEEL SHEET AND STRIP

Type: 316 austenitic steel
Finish grade: 2B (satin lustre)

2.6 GLASS

Refer to the glazing section for glass types and installation.

2.7 REVEALS - TIMBER PAINTED

Timber reveals for paint finish with all sides primed grooved for wall linings or flush finished for architraves.

2.8 FLASHINGS GENERALLY

To NZBC E2/AS1, 9.1.10 **Windows and Doors**. Material, grade and colour of head flashings to match the window frames. Ensure that materials used for head, jamb and sill flashings are compatible with the window frame materials and fixings and cladding materials.

Components - for cavity systems

2.9 STANDARD CAVITY CLOSER

A perforated device constructed from either aluminium or PVC to close the cavity above the window or door unit, between the cladding and head flashing, to provide ventilation in accordance with NZBC E2/AS1 to the spaces above the window or door.

2.10 WANZ SUPPORT BAR

Extruded aluminium support bar with built in drainage and ventilation to NZBC E2/AS1, to provide continuous support to the window unit. Size to suit cladding type.

Components

2.11 GLAZING GASKETS

Thermoplastic rubber. Do not stretch glazing gaskets during installation. Measure and cut gaskets 5-10% over length before installation.

2.12 HARDWARE AND FURNITURE

Hinges, stays, catches, fasteners, latches, locks and furniture as offered by the window and door manufacturer. Refer to SELECTIONS for type and finish. Key alike all lockable window hardware able to be keyed alike.

2.13 SAFETY STAYS

Stainless steel non releasable restrictors to limit window opening to NZBC F4/AS1, Table 2, Acceptable opening sizes for barriers.

© CIL Masterspec Sep 2026

Sealants

2.14 STRUCTURAL SEALANT

Silicone chemically curing sealant specifically formulated and tested or approved equivalent with not less than a ± 40% movement factor complying with US Federal Specification TT S 001543A.

2.15 WEATHERING/INSTALLATION SEALANT

Building sealant used in accordance with manufacturer's instructions for weather sealing aluminium frames to the cladding, complying with US Federal Specification TT S 0011534A, or a one-part polyurethane moisture curing, elastic joint sealant of medium modulus (± 25% movement) to US Federal Specification TT S 00230C.

2.16 FOAM TAPE

Foam tape to NZBC E2/AS1, 9.1.10.7 **Closed cell foam tape**.

Finishes

2.17 POWDER COATED ALUMINIUM - EXTRA DURABLE

Polyester powder organic coating in accordance with WANZ PQAS and AS 3715.

2.18 POWDER COATED ALUMINIUM - HIGH DUTY

Polyester powder coating in accordance with WANZ PQAS and AAMA 2604.

2.19 POWDER COATED ALUMINIUM - SUPER DUTY

PVF² fluoropolymer powder coating in accordance with AAMA 2605 and WANZ PQAS.

3 EXECUTION

Conditions - generally

3.1 DO NOT DELIVER

Do not deliver to site any elements which cannot be unloaded immediately into suitable conditions of storage.

3.2 UNLOAD WINDOW JOINERY

Unload, handle and store elements in accordance with the window manufacturer's requirements.

3.3 AVOID DISTORTION

Avoid distortion of elements during transit, storage and handling.

3.4 PREVENT DAMAGE

Prevent prefinished surfaces rubbing together, and contact with mud, plaster and cement. Keep paper and cardboard wrappings dry.

3.5 PROPRIETARY ELEMENTS

Fix in accordance with the window manufacturer's requirements.

3.6 PROTECTIVE COVERINGS

Retain protective coverings and coatings to BRANZ BU 337 and keep in place during the fixing process. Provide protective coverings and coatings where required to prevent marking of surfaces visible in the completed work and to protect aluminium joinery from following trades. Remove protection on completion.

3.7 ADDITIONAL PROTECTION

Supply and fix additional protection as necessary to prevent marking of surfaces which will be visible on completed work.

© CIL Masterspec Sep 2026

Conditions - fixings and fastenings

3.8 SUPPLY OF FIXINGS

Use only fixings and fastenings recommended by the manufacturer of the component being fixed and to comply with the ULS wind pressure stated in SELECTIONS. Ensure fixings and fastenings exposed to the weather are of aluminium, or Type 316 stainless steel or if not exposed to the weather may they be hot-dip galvanized steel with a coating weight of 610 g/m² complying with AS/NZS 4680.

3.9 INSTALLATION FIXING

To NZBC E2/AS1, 9.1.10.8, **Attachments for windows and doors**. Fix windows/doors through reveal to frame with a pair of 75 x 3.15mm minimum galvanised jolt head nails or a pair of 8 gauge x 65mm minimum stainless steel screws. Fix at a maximum of 450 centres along all reveals and a maximum of 150mm from reveal ends. Ensure fixings do not penetrate metal flashings.

Install packers between reveals and framing at fixing points, except at the head.

Assembly

3.10 FABRICATION

Fabricate frames as detailed on shop drawings. Install glazing, hinges, stays and running gear as scheduled. Provide temporary bracing and protection. Temporarily secure all opening elements for transportation.

3.11 TIMBER REVEALS

Before fixing to aluminium frames, ensure that timber reveals which are being painted have been primed on all surfaces.

3.12 HARDWARE GENERALLY

Factory fit all required and scheduled hardware. Account for all keys and deliver separately to the site manager.

3.13 SAFETY STAYS

Factory fit safety stays to all windows scheduled for safety stays and to all windows where safety stays are required to comply with NZBC F4/AS1 4.0, Opening windows.

Installation - windows and doors

3.14 CORROSION PROTECTION

Before fixing, apply suitable barriers of bituminous coatings, stops or underlays between dissimilar metals in contact, or between aluminium in contact with concrete.

3.15 CONFIRM PREPARATION OF EXTERIOR WALL OPENINGS

Confirm that exterior wall openings have been prepared ready for the installation of all window and door frames. Do not proceed with the window and door installation until required preparatory work has been completed.

Required preparatory work includes the following:

- wall underlay/building wrap to openings finished and dressed off ready for the installation of window and door frames to NZBC E2/AS1:9.1.5 **Wall underlays to wall openings**.
- Full height 20mm jamb battens to NZBC E2/AS1 figure 72A (direct fix only)
- claddings neatly finished off to all sides of openings
- installation of flashings (those which are required to be installed prior to frames).

3.16 INSTALLATION

Fix to comply with the reviewed shop drawings and installation details including flashings and bedding compounds, pointing sealants and weathering sealants.

3.17 INSTALLATION CAVITY CONSTRUCTION

Install to WANZ Installation Guide details and drawings including WANZ sill support bars.

For thresholds with support bars fixed through membranes, pre-fill support bar screw holes with silicone sealant to NZBC E2/AS1, figure 62(d).

© CIL Masterspec Sep 2026

3.18 INSTALL FLASHINGS

Install flashings to heads, jambs and sills of frames as supplied and required by the window manufacturer and as detailed on the drawings. Finish head flashings to match window finish.

Place all flashings so that the head flashing weathers the jamb flashings, which in turn weathers over the upstand of the sill flashing. Ensure that sill flashings drain to the outside air.

Except where window/door frames are recessed, ensure that head flashings over-sail unit by 20mm minimum plus any jamb scriber width at each end.

3.19 COMPLETE AIR SEAL

To NZBC E2/AS1:9.1.6 Air seals. Form an air-tight seal by means of a proprietary expanding foam or sealants used with backing rods, applied between the window / door reveal and structural framing to a depth of 10 - 20mm, to provide a continuous air tight seal to the perimeter of the window or door.

3.20 FIX HARDWARE

Fix all sash and door hardware and furniture as scheduled.

Application - jointing and sealing

3.21 SEAL FRAMES ON SITE

Seal frames to each other and to adjoining structure and finishes, all as required by the window manufacturer and to make the installation weathertight. In very high and extra high or greater wind zones, seal between the window head and the head flashing. Do not seal the junction between the sill member and the cladding or sill flashing which must remain open.

3.22 PREPARE JOINTS

Ensure joints are dry. Remove loose material, dust and grease. Prepare joints in accordance with the sealant manufacturer's requirements, using required solvents and primers where necessary. Mask adjoining surfaces which would be difficult to clean if smeared with sealant.

3.23 BACK UP

When using back-up materials do not reduce depth of joint for sealant to less than the minimum required by the manufacturer of the sealant. Insert polyethylene rod or tape back-up behind joints being pointed with sealant.

3.24 SEALANT FINISH

Tool sealant to form a smooth fillet with a profile and dimensions required by the sealant manufacturer. Remove excess sealant from adjoining surfaces, using the cleaning materials nominated by the sealant manufacturer and leave clean.

Completion - cleaning

3.25 REMOVE TRADE DEBRIS

Remove trade debris by appropriate means on a floor by floor basis as each floor is completed and again before any work is covered up by others. Arrange for general removal.

3.26 TRADE CLEAN

Trade clean window frames, operable windows and doors, glass and other related surfaces inside and out at the time of installation to remove marks, dust and dirt, to enable a visual inspection of all surfaces.

Completion

3.27 PROTECTIVE COVERINGS

Retain protective coverings and coatings and keep in place during the fixing process. Provide protective coverings and coatings where required to prevent marking of surfaces visible in the completed work and to protect aluminium joinery from following trades.

© CIL Masterspec Sep 2026

3.28 SAFETY

Indicate the presence of transparent glasses for the remainder of the contract period, with whiting, tape or signs compatible with the glass type. Indicators other than whiting must not be applied to the glass surface. Masking tape must not be used for this purpose.

3.29 IN SITU TOUCH-UP TO POWDER COATED ALUMINIUM

In situ touch-up of polyester or fluoropolymer coated aluminium is only permitted only to minor surface scratching. Otherwise replace all damaged material.

3.30 REMOVE

At the appropriate stage of the project, remove safety indicators and protective coverings and wipe down all joinery thoroughly.

3.31 REPLACE

Replace damaged, cracked or marked elements.

4 SELECTIONS

Performance

4.1 THERMAL PERFORMANCE

R-value:	R 0.26 (as determined from NZBC H1/VM1 or H1/AS1)

Performance - Wind (design by contractor)

4.2 WIND - NON SPECIFIC DESIGN

Building wind zone	High (refer to NZS 3604, table 5.4)

Window and door system

4.3 ALUMINIUM WINDOWS

Manufacturer:	To be selected
Type/location:	To be selected

4.4 ALUMINIUM DOORS

Manufacturer:	to be selected
Type/location:	to be selected

4.5 TIMBER REVEALS

Timber species:	Radiata pine
Grade/treatment:	H3.1
Thickness:	19mm
Reveals:	flush finish for architraves
Finish:	Preprimed ready for paint

Finishes

4.6 ORGANIC POWDER COATING FINISH

Type:	Polyester organic powder coating
System integrity:	Minimum 10 years film integrity, 7 years colour integrity
Thickness:	Average of 80 microns with a minimum of 50 microns
Colour:	To be selected

4.7 FLASHINGS

Material/type:	Aluminium
Pattern:	Formed to suit details provided

4.8 WEATHERING SEALANT

Brand/type:	MS Sealant 1-part polyurethane moisture curing, elastic joint sealant
Colour:	to be selected

© CIL Masterspec Sep 2026

4610 GLAZING RESIDENTIAL

1 GENERAL

This section relates to the supply and fixing of glass products for external and internal joinery in residential type buildings and includes:

- windows and doors
- frameless shower and bath screens
- splashbacks, wall linings
- balustrade systems, pool fences
- mirrors and mirror frames

1.1 RELATED WORK

Refer to 4521 ALUMINIUM WINDOWS AND DOORS for aluminium joinery.

1.2 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

PVB	Polyvinyl Butyral
CIP	Cast in place

Documents

1.3 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC F4/AS1	Safety from falling
NZBC F9/AS1	Means of restricting access to residential pools
NZBC H1/AS1	Energy Efficiency
AS/NZS 1170.2	Structural design actions - Wind loads
NZS 3604	Timber-framed buildings
NZS 4211	Specification for performance of windows
NZS 4218	Thermal insulation - Housing and Small Buildings
NZS 4223.1	Glazing in buildings - Glass selection and glazing
NZS 4223.Supp1	Glazing in buildings - Supplement 1 to NZS 4223.1:2008 and NZS 4223.4:2008
NZS 4223.2	Glazing in buildings - Insulating glass units
NZS 4223.3	Glazing in buildings - Human impact safety requirements
NZS 4223.4	Glazing in buildings - Wind, dead, snow and live action
AS/NZS 2208	Safety glazing materials in buildings
AS/NZS 4666	Insulating glass units
BRANZ BU 337	Protecting window glass from damage

Warranties

1.4 WARRANTY - MANUFACTURER/SUPPLIER

Warrant glass under normal environmental and use conditions against failure of materials.

10 years:	for insulating glass units
10 years:	for laminated glass
10 years:	for toughened glass

Refer to the general section for the required form of 1237WA WARRANTY AGREEMENT and details of when completed warranty must be submitted.

© CIL Masterspec Sep 2026

Performance

1.5 ENERGY EFFICIENCY

Provide glazing to meet the energy requirements of NZS 4218 and NZBC H1/AS1 for housing small buildings.

Refer to SELECTIONS and schedules for location and type of glazing.

2 PRODUCTS

Materials

2.1 CLEAR FLOAT GLASS

Clear ordinary annealed transparent float glass for general window glazing. Thickness to NZS 4223.1 and NZS 4223. Supp 1.

2.2 TEXTURED, PATTERNED OR OBSCURE GLASS

Translucent, annealed, rolled glass with a decorative pattern on one surface.

2.3 TOUGHENED GLASS

Grade A Safety Glass to AS/NZS 2208.

Heat soaked toughened glass to NZS 4223.1, Appendix E required for critical areas.
Refer to SELECTIONS.

2.4 INSULATING GLASS UNITS (IGU'S)

To AS/NZS 4666, NZS 4223.2 and the IGU Manufacturers Association (IGUMA) requirements.

Marking to NZS 4223.2 as modified by NZBC B2/AS1, 3.5.

Components, aluminium and uPVC glazing

2.5 GLAZING TAPE AND GASKETS

Single/double sided pressure sensitive self-adhesive low/medium/high density foam tapes/butyl tapes selected to suit the glazing detail to window manufacturers' requirements.

2.6 SETTING BLOCKS

Santoprene/Neoprene, 80-90 Shore A hardness, set at quarter points or to detail, to support the weight of glass panes.

3 EXECUTION

Conditions

3.1 GENERAL REQUIREMENTS

To NZS 4223.1, NZS 4223.3, NZS 4223.4. All external glazing to be wind and watertight on completion.

3.2 DELIVERY

Keep glass dry and clean during delivery and bring on to site when ready to glaze directly into place. Comply also with the storage requirements set out in BRANZ BU 337.

3.3 GLASS CONDITION

All glass to have undamaged edges and surfaces.

3.4 GLASS THICKNESS

If not specifically stated in the glazing schedule determine the minimum thickness of glass for each sheet as required by NZS 4223.1, NZS 4223.3, NZS 4223.4 and NZS 4223. Supp 1. For windows tested to NZS 4211, ensure glass meets the requirements of the window testing.

Determine the final glass thickness based on whether wind loading or human impact considerations govern.

3.5 REBATE DIMENSIONS

Provide rebates for glazing to the widths and depths necessary for each situation including minimum glass edge cover to NZS 4223.1, Section 4 Glazing.

© CIL Masterspec Sep 2026

3.6 JOINTING, PUTTY AND SEALING MATERIAL COMPATIBILITY

Ensure jointing, putty and sealing materials are compatible with glass substrates. Confirm compatibility with laminated glass, IGUs and coatings.

Conditions - human impact safety requirements

3.7 SAFETY GLAZING, GENERAL REQUIREMENTS

Glazing of doors, side panels, low level and window seat glazing, bathrooms, stairwell landings and similar locations, to NZS 4223.3 for thickness and maximum areas of safety glass.

3.8 SAFETY GLAZING MATERIAL

Use only safety glazing materials defined in NZS 4223.3, that also comply with the relevant requirements of AS/NZS 2208. Ensure material is permanently marked and if cut by the distributor or installer mark each piece to NZS 4223.3, 2.8 Identification.

3.9 CONTAINMENT

Edge cover to comply with NZS 4223.1, Section 4 Glazing, table 5. Otherwise to NZS 4223.3, 2.3 Edge cover.

Assembly

3.10 WORKING OF GLASS

All working of glass as required in NZS 4223.1.

3.11 EDGE WORK AND BEVELLING

Edgework other than a clean cut. Refer to SELECTIONS/drawings for type.

3.12 SURFACE TREATMENT

Refer to SELECTIONS/drawings for finish.

3.13 SURFACE CUTTING

Refer to SELECTIONS/drawings for finish.

3.14 INSTALL SAFETY GLASS

To NZS 4223.3.

Application aluminium

3.15 INSTALL GLASS TO ALUMINIUM FRAMES

Install glass to NZS4223.1.

- Bead glaze to Section 4 Glazing.
- Channel glaze to Section 4 Glazing, and Section 5 for Framed, Unframed, Partly Framed Glass Assemblies.

Finishing

3.16 SAFETY

Indicate the presence of transparent glass for the remainder of the construction period, with whiting, tape or signs compatible with the glass type.

Completion

3.17 TRADE CLEAN

Clean off or remove safety indicators at completion of the building.

3.18 REPLACE

Replace damaged, cracked or marked glass.

3.19 LEAVE

Leave work to the standard required by following procedures.

3.20 REMOVE

Remove debris, unused materials and elements from the site.



© CIL Masterspec Sep 2026

4 SELECTIONS

Performance - wind

4.1 WIND ZONE - NON-SPECIFIC DESIGN
Building wind zone: High (as determined from NZS 3604, NZS 4223.4)

Glass by type

4.2 CLEAR FLOAT GLASS

Location:	All windows unless noted on plans
Brand/type:	To be selected
Thickness:	4mm

4.3 TEXTURED, PATTERNED OR OBSCURE GLASS

Location:	as noted on Plans
Brand/pattern:	to be selected
Pattern:	to be selected
Thickness:	4 mm

4.4 TOUGHENED GLASS

Location:	as noted on plans
Brand/type:	Toughened
Thickness:	4mm

© CIL Masterspec Sep 2026

5113G GIB® PLASTERBOARD LININGS

1 GENERAL

This section relates to the supply, fixing and jointing of GIB® plasterboard linings and accessories to timber and steel framed walls and ceilings to form:

- standard systems
- bracing systems
- fire rated garage boundary wall systems
- wet area systems

1.1 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

AWCINZ	Association of Wall and Ceiling Industries New Zealand

Documents

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC C/AS2	Protection from fire for buildings other than risk group SH
NZBC E2/AS1	External moisture provisions for timber-framed buildings up to 10 m in height
AS/NZS 2588	Gypsum plasterboard
AS/NZS 2589	Gypsum linings - Application and finishing
NZS 3604	Timber-framed buildings
ISO 5660.1	Reaction-to-fire tests - Heat release, smoke production and mass loss rate - Part 1: Heat release rate (cone calorimeter method)
ISO 5660.2	Reaction-to-fire tests - Heat release, smoke production and mass loss rate - Part 2: Smoke production rate (dynamic measurement)
BRANZ Technical Paper P21	BRANZ Technical Paper P21: A wall bracing test and evaluation procedure (2010)

1.3 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer's and supplier's documents which refer to work in this section:

GIB® Site Guide (April 2024)
GIB® Noise Control Systems (September 2017)
GIB® Fire Rated Systems (September 2024)
GIB® Wet Area Systems (February 2021)
GIB Ezybrace® Systems (August 2016)
GIB Ezybrace® Bracing Design Software
GIB Ezybrace® Bracing Supplement Document (December 2016)
GIB Rondo® Metal Batten System (September 2024)
GIB-Cove®
GIB® Goldline™ Platinum Tape-on Trims
GIB® UltraFlex high impact corner mould
GIB® Tough Systems (November 2014)
BRANZ Appraisal 289 (2024) GIB® Fire Rated Systems
BRANZ Appraisal 394 (2025) GIB® Noise Control Systems
BRANZ Appraisal 427 (2021) GIB® Wet Area Systems
BRANZ Appraisal 928 (2021) GIB EzyBrace® Systems

Manufacturer/supplier contact details

Company:	Winstone Wallboards
Web:	www.gib.co.nz

© CIL Masterspec Sep 2026

Telephone: 0800 100 442

Requirements

1.4 NO SUBSTITUTIONS

Substitutions are not permitted to any specified GIB® systems, GIB® system components, GIB® plasterboard, associated GIB® products or GIB® accessories.

1.5 QUALIFICATIONS

Refer to 1270 CONSTRUCTION for requirements relating to qualifications.

1.6 INSPECTIONS AND ACCEPTANCE

Allow for inspection of the finished plasterboard surface:

- before applying sealer and
- before applying finish coatings or decorative papers,

so that after assessment of the type and/or angle of illumination and its effect on the completed decorative treatment, group approval and acceptance of the surface can be given.

1.7 FIRE RATING REQUIREMENTS

Provide the GIB® fire resistant rated garage boundary wall systems. Refer to SELECTIONS for system/FRR.

1.8 SOUND INSULATION REQUIREMENTS

Provide the GIB® Noise Control Systems. Refer to SELECTIONS for system/STC. Include for forming and treating of perimeters of openings and penetrations in the elements to ensure the specified performance. Ensure absence of adjoining flanking paths.

Compliance

1.9 COMPLIANCE - BRANZ APPRAISAL 289

GIB® Fire Rated Systems has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 289.

1.10 COMPLIANCE - BRANZ APPRAISAL 394

GIB® Noise Control Systems has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 394.

1.11 COMPLIANCE - BRANZ APPRAISAL 427

GIB® Wet Area Systems has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 427.

1.12 COMPLIANCE - BRANZ APPRAISAL 928

GIB EzyBrace® Systems has been appraised as meeting provisions of the NZBC when used within the Conditions and Limitations of its BRANZ Appraisal 928.

Performance

1.13 BRACING REQUIREMENTS

Braced wall systems to NZS 3604 when tested to BRANZ Technical Paper P21, using:

- GIB Ezybrace® Systems and/or GIB Ezybrace® Bracing Design Software
- GIB Ezybrace® Bracing Supplement Document
- GIB Ezybrace® for Steel Frame Housing (NASH) Software (to NASH Residential and Low-Rise Steel Framing Part 1 2010 Design Criteria)

Refer to drawings for location and type.

2 PRODUCTS

Materials

2.1 GIB® PLASTERBOARD

Gypsum plaster core encased in a face and backing paper formed for standard and water resistance use to AS/NZS 2588. Refer to SELECTIONS for location, type, thickness and finish.

© CIL Masterspec Sep 2026

GIB® Standard plasterboard
GIB Fyreline® fire resistant plasterboard
GIB Braceline® & GIB® Noiseline® dual purpose wall bracing & noise control plasterboard
GIB Aqualine® wet area plasterboard

2.2 GIB® COVING

GIB-Cove® plasterboard coving. Refer to SELECTIONS for profile and size.

Components

2.3 CEILING BATTENS

GIB® Rondo® metal ceiling battens, batten joiners and perimeter channel.

2.4 SCREWS

GIB® Grabber® drywall type screws as follows:

Grabber® type	**Used for fixing:**
High Thread	GIB Ezybrace® or Standard systems to timber
Self Tapping	Standard systems to light gauge steel or timber
Dual Thread Screws	GIBFix®, GIB Ezybrace®, or Standard systems, to light gauge steel or timber
Wafer Head Needle Tip	Light gauge metal to timber not directly under plasterboard
Pancake Head Drill Tip	Light gauge metal to light gauge metal directly under plasterboard

Refer to GIB® requirements for appropriate details.

2.5 TAPE ON TRIMS AND EDGES

GIB® Goldline™ tape-on trims

GIB® UltraFlex® high impact corner mould
GIB® Levelline® Tape on Trim

2.6 METAL ANGLE TRIMS

GIB® galvanized steel slim angle trims.

Accessories

2.7 ADHESIVE

Timber frame and/or steel frame:

GIBFix® One ultra low VOC water based wallboard adhesive
GIBFix® All-Bond solvent based wallboard adhesive

2.8 JOINTING COMPOUND

Bedding compound:	GIB Tradeset®, GIB Lite Blue®, GIB MaxSet®, GIB ProMix® All Purpose, GIB Plus 4®
Finishing compound:	GIB ProMix® All Purpose, GIB® Trade Finish®, GIB® Trade Finish® Lite, GIB ProMix® Lite, GIB® U-Mix, GIB Plus 4®, GIB Trade Finish® Multi
Cove:	GIB-Cove® Bond

2.9 JOINTING TAPE

GIB® jointing tape.

2.10 FIRE/ACOUSTIC SEALANT

GIB Fire Soundseal® ultra low VOC, mulit use acoustic sealant that resists passage of smoke and fire.

2.11 GAP FILLER

GIB® Gap Filler ultra low VOC multi-purpose acrylic flexible filler

© CIL Masterspec Sep 2026

3 EXECUTION

Conditions

3.1 DELIVERY, STORAGE & HANDLING OF PRODUCTS

Refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.

3.2 ROUTINE MATTERS

Refer to 1250 TEMPORARY WORKS & SERVICES for protection requirements.

Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.3 LEVELS OF PLASTERBOARD FINISH

Provide the selected plasterboard surfaces to the pre decorative levels of finish specified in AS/NZS 2589.

3.4 PRE-INSTALLATION REQUIREMENTS - TIMBER FRAMING

Check work previously carried out and confirm it is of the required standard for this part of the work.

Framing substrates shall be in accordance to AS/NZS 2589, GIB® Site Guide and GIB X-Block® Radiation Shielding Systems literature.

Check timber framing moisture content is in accordance with requirements of AS/NZS 2589. Refer to NZBC E2/AS1 and GIB® Site Guide.

Timber framing:	18% maximum for fixing plasterboard to timber (8-12% recommended for fixing plasterboard to timber framing if air conditioning and/or central heating are to be installed)

If GIB EzyBrace® systems are used in conjunction with GIBFix® Framing System, ensure that the positioning of the GIB HandiBrac® panel hold-down brackets are to the manufacturers recommended placements for the GIBFix® Framing System.

3.5 PRE-INSTALLATION REQUIREMENTS - STEEL FRAMING

Check work previously carried out and confirm it is of the required standard for this part of the work.

Framing substrates shall be in accordance to AS/NZS 2589, GIB® Site Guide and GIB X-Block® Radiation Shielding Systems requirement. Refer to GIB® Site Guide.

3.6 CONFIRM LEVELS OF PLASTERBOARD FINISH ACCEPTANCE

Before commencing work, agree in writing upon the surface finish assessment procedure towards ensuring that the quality of finish expectations are reasonable and are subsequently obtained and acceptable.

Do not apply decorative treatment until it is agreed in writing by the contractor, subcontractors and decorator that the specified plasterboard Level of Finish has been achieved.

"Levels of plasterboard finish" is a tool for specifying the required quality of finish when installing and flush stopping GIB® plasterboard **prior** to the application of a range of decorative finishes under various lighting conditions. Refer to **AS/NZS** 2589.

3.7 PROTECTION

Protect surfaces; cabinetwork, fittings, equipment and finishes already in place from the possibility of water staining and stopping damage. Refer to GIB® Site Guide.

Application

3.8 INSTALL CEILING BATTENS

Install to GIB® Rondo® Ceiling Batten Systems requirements.

© CIL Masterspec Sep 2026

3.9 LINING WALLS AND CEILINGS GENERALLY

Form to GIB® Site Guide. Ensure bulk insulation thickness shall not exceed that of the wall framing.

3.10 BOARD ORIENTATION

Minimise joints by careful sheet layout using the largest sheet sizes possible, and generally fixing horizontally. Where part sheets are required for various stud heights they should be positioned so the cut sheet is as low as possible to keep joints below eye level.

3.11 FORM FIRE RATED SYSTEMS

Form to GIB® Fire Rated Systems requirements.

3.12 FORM NOISE CONTROL SYSTEMS

Form to GIB® Noise Control Systems requirements.

3.13 FORM WET AREA SYSTEMS

Form to GIB Aqualine® Wet Area Systems requirements.

3.14 FORM BRACING SYSTEMS

Form bracing systems to:

- GIB Ezybrace® Systems.

3.15 INSTALL COVES

Install to GIB-Cove® literature using GIB-Cove® Bond.

3.16 INSTALL TAPE-ON TRIMS

Install to GIB® Goldline™ Tape-on trims literature and/or GIB® Ultraflex high impact corner mould literature.

Finishing

3.17 FINISHING GENERALLY

To GIB® Site Guide and AS/NZS 2589.

Completion & Commissioning

3.18 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

Plasterboard

4.1 GIB® STANDARD SYSTEMS WALLS

Location	Plasterboard type / Lining requirements	Thickness	Finish Level
Walls	GIB® Standard plasterboard	10mm	4

4.2 GIB® WATER RESISTANT SYSTEMS WALLS

Location	Plasterboard type / Lining requirements	Thickness	Finish Level
Bathrooms	GIB Aqualine® plasterboard	10mm	

4.3 GIB® STANDARD SYSTEMS CEILINGS

Location	Plasterboard type / Lining requirements	Thickness	Finish Level
Ceilings	GIB® Standard plasterboard	13mm	4

4.4 GIB® SOUND RATED SYSTEMS

Refer to GIB® Noise Control Systems

Location	Plasterboard type / Lining requirements	STC / System specification	Finish Level

© CIL Masterspec Sep 2026

Refer Plans	Refer Plans	GBUC 30 30/30/30 Fire Ceiling	4
Refer Plans	Refer Plans	GBDFA 60b 60/60/60 Fire Floor 57 STC	

4.5 GIB® FIRE RATED SYSTEMS

Location / Type	Plasterboard type / Lining requirements	FRR / System specification	Finish Level
Refer Plans	Refer Plans	GBUW 30a 30/30/30 Fire Wall	4
Refer Plans	Refer Plans	GBTLA 60 Gib Noise Wall 60 STC	4

4.6 GIB® BRACING SYSTEMS

Refer to:

- GIB Ezybrace® Systems

For bracing element location refer to drawn documentation.

Accessories

4.7 GIB® COVE®

Size/brand/type: 55mm GIB-Cove® Classic

4.8 GIB® RONDO® CEILING BATTENS

Location: Ceilings
Brand/type: GIB® Rondo® Ceiling battens
Batten type: Gib Rondo GR
Clip type: Clip fix 311D Clip

© CIL Masterspec Sep 2026

5230 INTERIOR DOORS

1 GENERAL

This section relates to the supply and installation of interior doors.

1.1 RELATED SECTIONS

Refer to glazing section/s for glass type and thickness.

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZS 3602	Timber and wood-based products for use in building
NZS 3610	Specification form profiles of mouldings and joinery

© CIL Masterspec Sep 2026

Requirements

2 PRODUCTS

2.1 TIMBER

To NZS 3602.

2.2 PROFILES, FACINGS, SCRIBERS AND ARCHITRAVES

Traditional profiles to NZS 3610. Proprietary profiles and special profiles as detailed. Pencil radius corners of profiled schedules for paint finish.

2.3 DOORS, PAINTED

Doors as scheduled (without clashing strips).

2.4 DOOR HINGES

Size and gauge to carry door. 3 hinges per door.

2.5 SLIDING DOOR GEAR

To suit door/sash size and glazed weight and as detailed.

3 EXECUTION

3.1 SITE MEASURE

Confirm framed openings on site for dimension, plumb and straightness prior to fabrication or ordering of timber joinery. Confirm lintel head and sill deflection for sliding or bi-fold door systems is within the manufacturer's specified tolerances. Provide not less than 10mm unless otherwise required.

3.2 EXECUTION GENERALLY

Manufacture to the methods, practices and processes contained in the unit standards for the National Certificate in Carpentry and the National Certificate in Joinery (cabinetry, exterior joinery, stairs).

3.3 FACTORY FIT HARDWARE

Factory fit the following where specified: -

- Hinges

3.4 FACTORY FINISHING

Before delivery to site: -

- Brace square and provide protection to assemblies during delivery to site. Where factory glazed, indicate the presence of transparent glasses with whiting, tape or signs compatible with the glass type.

Internal doors

3.5 INTERNAL JOINERY FRAMES

Fabricate as detailed. Wedge and rigidly fix in place without distortion, plumb, and true to line and face. Pre drill for fixings through frame. Countersink and plug frames scheduled for clear finish.

3.6 DOOR FRAMES, SOLID REBATED

Fabricate as detailed. Hang doors to operate freely on hinges, sliding, or bi-fold gear and to the door manufacturer's requirements. Pre drill for fixings through frame. Countersink and plug frames scheduled for clear finish. Fit hardware.

3.7 DOOR LINERS

Heads and jambs finished minimum 18mm, with 10mm planted door stops. Width to match width of lined walls. Hang doors on hinges, sliding, or sliding-folding gear to the door manufacturer's requirements and to operate freely. Countersink and plug frames scheduled for clear finish. Fit hardware.



© CIL Masterspec Sep 2026

3.8 DOOR LINERS, EXTENDED

Heads and jambs finished 30mm, rebated for wall linings and extended a minimum of 10mm. 10mm planted door stops. Hang doors on hinges, sliding and bi-fold gear to the door manufacturer's requirements and to operate freely. Countersink and plug frames scheduled for clear finish. Fit hardware.

Completion

3.9 CHECK

Check and adjust operation of all sashes, doors, hardware and furniture.

3.10 TEMPORARY PROTECTION

On completion remove any temporary protection and leave ready for following work.

4 SELECTIONS

4.1 HOLLOW CORE DOOR, PAINT FINISH

Brand/type:	to be selected
Door facing:	to be selected
Finish:	Paint finish
Hardware:	to be selected

4.2 SLIDING DOOR GEAR

Brand/type:	to be selected

Accessories

4.3 DOOR HINGES

Interior doors

Type:	Loose pin
Size:	89mm
Material:	Zinc-plated steel
Pin:	Loose-pin zinc-plated steel

© CIL Masterspec Sep 2026

5433E ECOPLY® FLOORING

1 GENERAL

This section relates to the supply and installation of Carter Holt Harvey Plywood Ltd Ecoply® plywood sheets for floors.

1.1 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

CCA	Copper chrome arsenate
PF	Phenol formaldehyde

Documents

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

BPS	Building Product Specifications
AS/NZS 1604.3:2012	Preservative-treated wood-based products - Part 3: Plywood
AS/NZS 2269.0	Plywood - structural - specifications
BPS	Building Product Specifications

1.3 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer and supplier documents relating to this part of the work:

Ecoply® Specification and Installation Guide (September 2025)
Ecoply® Flooring Product Technical Statement and Building Product Information Sheet

Manufacturer/supplier contact details

Company	Carter Holt Harvey Plywood Limited
Web:	www.chhply.co.nz
Email:	info@ecoply.co.nz
Telephone:	0800 326 759

Requirements

1.4 QUALIFICATIONS GENERALLY

Refer to 1270 CONSTRUCTION for requirements relating to qualifications.

1.5 NO SUBSTITUTIONS

Substitutions are not permitted to any of the specified systems, components and associated products listed in this section.

Performance

2 PRODUCTS

Materials

2.1 ECOPLY® FLOORING PLYWOOD

Tongue and groove, synthetic phenolic (PF) resin Type A bonded timber veneer plywood sheets, manufactured to AS/NZS 2269.0, untreated and H3.2 CCA to AS/NZS 1604.3:2012. Machine grooved long edges with rigid polypropylene tongue insert to one edge. Available in stress grades F8/F5 and F11/F8. Appearance grade CD. Sheets 1200mm wide, 2400mm and 2700mm long, and available in range of thicknesses. Refer to SELECTIONS.

© CIL Masterspec Sep 2026

Components

2.2 SCREWS

Hot dipped galvanized or stainless steel counter-sunk screws. Refer to SELECTIONS.

2.3 ADHESIVE

Refer to SELECTIONS.

2.4 TIMBER PRESERVATIVE TREATMENT

Soudal Metalex Concentrated Timber Preservative treatment, in clear or green colour. Refer to SELECTIONS.

3 EXECUTION

Conditions

3.1 DELIVERY, STORAGE & HANDLING OF PRODUCTS

Refer to 1270 CONSTRUCTION for requirements relating to delivery, storage and handling of products.

3.2 ROUTINE MATTERS

Refer to 1250 TEMPORARY WORKS & SERVICES for protection requirements.

Refer to 1270 CONSTRUCTION for requirements relating to defective or damaged work, removal of protection and cleaning.

3.3 PRE-INSTALLATION REQUIREMENTS

Check work previously carried out and confirm it is of the required standard for this part of the work.

Timber substrate: 18% maximum moisture content

Application

3.4 STANDARDS AND TOLERANCES

Refer to the general section 1270 CONSTRUCTION for general requirements.

3.5 INSTALLATION GENERALLY

Install in accordance with Ecoply® Specification and Installation Guide.

3.6 TREAT CUT EDGES

Brush timber preservative onto cut edges and penetration cut outs.

3.7 APPLY ADHESIVE

Apply a bead or daubs of adhesive to framing. When fastening sheets over adhesive, work from the middle of the sheet outwards to develop glueline pressure.

3.8 LAY PLYWOOD SHEETS - TONGUE & GROOVED

Lay sheets continuous over at least two spans in a staggered layout with face-grain of sheet at right-angles to support and with sheets in square, true alignment and plane. Provide 3mm expansion gap between square sawn edges at sheet ends. Provide 5mm expansion gap at the perimeter of the floor. Fully support square sawn edges at sheet ends.

3.9 FIX PLYWOOD SHEETS

Fix sheets to framing to the Ecoply fixing pattern. Maintain clearances to sheet edges to Ecoply requirements. Finish fastener heads flush with the panel surface.

Completion & Commissioning

3.10 COMPLETION MATTERS

Refer to 1270 CONSTRUCTION for completion requirements and if required commissioning requirements.

4 SELECTIONS

For further details on selections go to www.chhply.co.nz
Substitutions are not permitted to the following, unless stated otherwise.



© CIL Masterspec Sep 2026

Materials

4.1 ECOPLY® FLOORING PLYWOOD

Location:	First floor excluding bathrooms and Laundry
Manufacturer/supplier:	Carter Holt Harvey Plywood Ltd
Brand:	Ecoply® Flooring plywood
Stress grade:	F8/F5 (standard)
Appearance grade:	CD
Sheet thickness/ID code:	19mm/19-30-7
Sheet size:	1200mm wide x 2700mm long
Timber treatment:	Untreated
Timber certification:	

4.2 ECOPLY® FLOORING PLYWOOD - WET AREA

Location:	Bathrooms and Laundry
Manufacturer/supplier:	Carter Holt Harvey Plywood Ltd
Brand:	Ecoply® Flooring plywood
Stress grade:	F8/F5 (standard)
Appearance grade:	CD
Sheet thickness/ID code:	19mm/19-30-7
Sheet size:	1200mm wide x 2700mm long
Timber treatment:	H3.2 CCA
Timber certification:	

Components

4.3 SCREWS

Type:	10Gx45mm countersunk screw
Finish:	Hot dipped galvanized

4.4 SCREWS - WET AREA

Type:	10Gx45mm countersunk screw
Finish:	Stainless steel

4.5 ADHESIVE

Brand/type:	Soudal Gorilla Grip (polyurethane-based adhesive)

4.6 TIMBER PRESERVATIVE TREATMENT

Brand/type:	Soudal Metalex Concentrated Timber Preservative
Colour:	Green

© CIL Masterspec Sep 2026

6700R RESENE PAINTING GENERAL

1 GENERAL

This section relates to the general matters related to **Resene** painting work.

1.1 RELATED WORK

Refer to 6721R RESENE PAINTING INTERIOR

Refer to 6711R RESENE PAINTING EXTERIOR

1.2 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

MPNZA	Master Painters New Zealand Association Inc.
SIPDS	Surface Information & Preparation Data Sheets

Documents

1.3 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

Health and Safety at Work Act 2015

AS/NZS ISO 9001	Quality management systems - Requirements
MPNZA	Health and Safety Programme

1.4 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer's and supplier's documents related to this section are:

Resene	Surface Information & Preparation Data Sheets (SIPDS) (hard copy or at www.resene.co.nz)
Resene	Product Data Sheets (hard copy or at www.resene.co.nz)
Resene	Putting your safety first

Copies of the above literature are available from Resene

Telephone:	0800 RESENE (0800 737 363)

Warranties

1.5 WARRANTY - MANUFACTURER/SUPPLIER

Warrant this work under normal conditions of use against failure referring to the Resene Promise of Quality in the Resene One-Line specifications and product data manual.

Requirements

This painting specification is written based on information available at the time of writing.

1.6 NO SUBSTITUTIONS

Substitutions are not permitted to any specified Resene coating system, or associated components and products. Do not combine paints from different manufacturers in a paint system.

If in the applicator's own expertise and judgement an amendment to this specification is required, or where a substrate preparation, or required painting system is not covered in this specification, this shall be brought to the attention of the contract administrator and any amendment agreed before work proceeds any further.

© CIL Masterspec Sep 2026

1.7 QUALIFICATIONS

Painters to be experienced competent workers, familiar with the materials and the techniques specified and with the Resene coating systems and be members of the Master Painters New Zealand Association Inc.

The applicator is to have the necessary skill, experience and equipment to undertake the work. The applicator remains responsible for ensuring proper completion of the work.

Painters to be selected from the Resene Eco.Decorator programme. The Resene Eco.Decorator programme is designed to recognise a nationwide network of environmentally responsible, quality focussed painting contractors.
Refer to www.resene.co.nz/ecodecorator.htm for a list of Eco.Decorators in your area.

1.8 PRIOR TO WORK COMMENCING

Before any work commences painters should verify, with Architects or specifying authority, that their paint matches a previously supplied standard card or panel. Differently coloured paints will vary in price, opacity and durability. Resene normally only specify two coats of colour but with certain colours, such as yellows and oranges, three coats may be needed. Refer to SELECTIONS for location and type.

1.9 INFORMATION FOR OPERATION AND MAINTENANCE

Refer to the general section 1239 OPERATION & MAINTENANCE for provision of the following general operation and maintenance information as electronic PDF format documents:

Maintenance guide for Resene paint finishes www.resene.co.nz/comn/services/maintenance.htm.

Provide this information prior to practical completion.

1.10 HEALTH AND SAFETY

Refer to and comply with the requirements of the Health and Safety at Work Act 2015 including the obligation to:

- Eliminate hazards and if hazards cannot be eliminated or isolated, then minimise the hazards in this work by using the proper equipment and techniques as required by the MPNZA Health and Safety Programme.
- Supply protective clothing and equipment.
- Inform the contractor as well as the employees and others on site of those hazards and put in place procedures for dealing with emergencies.

1.11 SAFETY DATA SHEETS

Obtain from Resene (phone 0800 RESENE, or www.resene.co.nz) the safety data sheet for each product used and comply with the required safety procedures. Keep sheets on site.

Performance

1.12 INSPECTION OF THE WORK

Inspection of the whole of the work at each of the stages set out in SELECTIONS may be made. Agree on a programme that will facilitate such inspection, including notification when each part and stage of the work is ready for inspection.

2 PRODUCTS

Materials

2.1 MATERIALS GENERALLY

Do not combine paints from different manufacturers in a paint system.

Use only Resene products (which are guaranteed for consistency and performance under AS/NZS ISO 9001 and APAS) prepared, mixed and applied as directed in the Resene One-Line Specifications and Product Data Manual. This specification has been written using where practical and available both low/no VOC and Environmental Choice approved products.

© CIL Masterspec Sep 2026

2.2 DARK COLOURS

Darker colours in areas of high sun exposure place significant stress on the coating and substrate. Resene 'CoolColour' technology reduces heat absorption of a wide range of colours. Contact your local Resene Representative or visit www.resene.co.nz for more information or visit www.resene.co.nz/coolcolour. View a list of Resene colours that can be made using Resene CoolColour technology at www.resene.co.nz/colourlibrary.

2.3 THINNERS/ADDITIVES

Use only if and when expressly directed by Resene for their particular product in a particular application. Always wear gloves when handling any solvents including turpentine as harmful chemicals may be absorbed into the body through the skin.

Accessories

2.4 ACCESSORIES

Contact your local Resene ColorShop for a full range of accessories and usage advice.

3 EXECUTION

Conditions

3.1 EXECUTION

To conform to required trade practice, which shall be deemed to include those methods, practices and techniques contained in the Master Painters New Zealand Association Inc. Specification manual.

3.2 TREATED SURFACES

Where surfaces have been treated with preservatives or fire retardants, check with the treatment manufacturer that coating materials are compatible with the treatment and do not inhibit its performance. If they are not compatible, obtain instructions before proceeding.

3.3 BACK PAINTING

Co-ordinate with cladding and/or lining installer as to who will do the work and timing.

Exterior
For exterior cladding and trim that require on site finishing, paint the back and exposed bottom edges at the base of the cladding (generally, bottom plate overhang and horizontal flashings) to the manufacturer's requirements, but at least to 150mm up from base. Coating to match front finish, generally apply 2 coats or 1 coat if pre-primed.
Refer to appropriate exterior paint sections SELECTION clauses for claddings to be back painted.

Interior
For lining and trim that require on site finishing and/or back painting (usually wet areas), paint the back and exposed bottom edges at the base of the lining, to the manufacturer's requirements, but at least to 150mm up from base. Coating to match front finish, generally apply 2 coats or 1 coat if pre-primed, or if no front finish, seal to manufacturer's requirements.
Refer to appropriate interior paint sections SELECTION clauses for linings to be back painted.

3.4 ANCILLARY SURFACES

The descriptions of areas in schedules and elsewhere are of necessity simplified. Coat ancillary exposed surfaces to match similar or adjacent materials or areas, except where a fair-faced natural finish is required or items are completely prefinished. In cases of doubt obtain written instructions before proceeding.

3.5 HARDWARE

Do not paint hinges or hardware that cannot be removed. Before commencing work carefully remove hardware, fixtures and fittings, set aside where they cannot be damaged or misplaced and replace on completion. Refer to SELECTIONS for hardware, fixtures and fittings for removal.

3.6 PROTECTION

Supply, lay and fix drop sheets, coverings and masking necessary to protect adjoining, fixtures, fittings and spaces from paint drops, spots, spray and damage.

© CIL Masterspec Sep 2026

Application - preparatory work

3.7 SURFACE PREPARATION

Refer to the Resene Surface Information & Preparation Data Sheets (SIPDS) and product data manual for surface preparation sheets (or obtain them by phoning 0800 RESENE, or at www.resene.co.nz) listed in the materials systems schedule clauses. Carry out the preparatory work required by them for each of the substrates.

3.8 SHARP EDGES, CRACKS AND HOLES

Remove and/or repair sharp edges, cracks and holes if present, as outlined in the preamble of the Resene One-Line specifications and product data manual.

Elastomeric sealants, if used, should not be painted. The paint film will not match the flexibility of the sealant and may severely limit its effectiveness.

3.9 REMEDIAL WORK

If any substrate or surface, that even with the preparation work called for in this section, cannot be brought up to a standard that will allow painting or clear finishing of the required standard then do not proceed until remedial work is carried out.

3.10 GAP FILLING

Make good cracks, holes, indented and damaged surfaces. Use suitable gap fillers to match the surface being prepared. Any special priming requirements of the fillers must be satisfied. Allow to dry or set before sanding back level with the surface. Prime or seal timber before using putty.

Exterior and wet areas: Use only Portland cement base or water-insoluble organic base gap fillers.

3.11 OFF-SITE WORK

Carry out this work under cover in a suitable environment with suitable lighting. Store items, both before and after coating, in a clean, dry area protected from the weather and mechanical damage, properly stacked and spaced to allow air circulation and to prevent sticking. Specific instructions for transport to site to avoid damage to the factory applied paint system may be required particularly for metallic top coat paints.

3.12 PRIMING JOINERY

Pre-treat any cut surfaces of preservative treated timber before priming. Ensure L.O.S.P. treated joinery has dried sufficiently to lose solvent odour. Pre-treat bare timber with Resene TimberLock (see Data Sheet D48) to improve the durability of subsequent coats.

Liberally coat end grain, allow to soak in and then recoat.

3.13 CONCEALED JOINERY SURFACES

Where off-site coatings are specified they must be applied to surfaces including those concealed when incorporated into the building.

3.14 CONCEALED METAL SURFACES

Apply primer to suit the coating system to surfaces which will be concealed when incorporated into the building.

3.15 EXTERNAL DOORS

Prime or seal and paint bottom edges before hanging.

3.16 BEAD GLAZING

Stained, varnished, or painted joinery to have the first two coats of a suitable primer and one undercoat, applied to rebates and beads before glazing.

3.17 PUTTY FRONTING - LINSEED GLAZING PUTTIES

According to the putty manufacturer's instructions allow putty to set, then prime with Resene Wood Primer (see Data Sheet D40) or Resene Enamel Undercoat (see Data Sheet D44). Fully protect the putty by completing the Resene coating system as soon as it is sufficiently firm.

Glazing putties not based on linseed oil to be over coated according to the putty manufacturer’s instruction.



© CIL Masterspec Sep 2026

Application - generally

3.18 PAINTING GENERALLY

Comply with the Resene SIPDS Surface Information & Preparation Data Sheets or Resene One-Line specifications and product data manual data sheets and the additional requirements of this work section.

Ensure large wall areas that require more than one container of paint per coat, have enough paint boxed (mixed) together to complete the final coat. This will not apply if a single factory batch of paint, rather than shop tinted paint, is applied.

3.19 MIXING

Although generally supplied ready to use, all paints must be thoroughly mixed to lift any settled pigment and ensure the paint is homogeneous.

3.20 ENVIRONMENT

Defer painting of exterior surfaces until weather conditions are favourable - warm dry days without frost or heavy dews. Avoid painting in direct sunlight any surfaces that absorb heat excessively. As far as possible apply paint in the temperature range 15°C to 25°C. If temperatures fall outside the range of 10°C and 35°C do not paint unless paints with the necessary temperature tolerance have been specified. Resene Hot Weather Additive can be added to most Resene waterborne top coats to extend open time when application is undertaken at elevated temperatures or conditions that will cause rapid loss of water from the applied wet film. Do not apply solvent borne paint if moisture is present on the surface.

3.21 SEQUENCE OF OPERATIONS

Painting work to generally follow the following sequences:

- Back painting and pre-installation painting, then post-installation exposed-face painting
- Complete surface preparation before commencing painting.
- Apply primers, sealers, stains, undercoats, paints and clear coatings in the sequences laid down by Resene.
- Allow the full drying time between coats laid down by Resene.
- Do not expose primers, undercoats and intermediate coats beyond Resene's recommendations before applying the next coat.
- Finish broad areas before painting trim.
- Ensure batch numbers of tins are matched for whole areas.
- Internally, paint ceilings before walls and walls before joinery, trim and other items.

3.22 APPLICATION

Select brush, roller, or pad and apply coatings to the requirements of Resene to obtain a smooth, even coating of the specified thickness, uniform gloss and colour.

3.23 LIGHTLY SAND

Lightly sand primers, sealers, undercoats and intermediate coats to remove dust pick-up, protruding fibres and coarse particles. A more thorough sanding to provide a mechanical key for the new paint system may be required depending upon the condition or age of the existing paint system..

3.24 DEFECTIVE WORK

Correct defective work immediately and recoat as required, following precisely the Resene system being applied. The same applies to transportation damage to site of factory painted items.

3.25 EACH COAT

Each coat of paint and the completed paint system to have the following qualities and properties:

- Uniform finish, colour, texture, sheen and hiding power and the proper number of coats applied.
- No blemishes such as runs, sags, crinkling, fat edges, entrained paint skins, hairs, dust, bare or starved patches, cracks, significant brush marks, ladder marks and blistering.
- Proper covering of corners, crannies, thin edges, cracks, end grain and other difficult places of application.

© CIL Masterspec Sep 2026

Completion

3.26 CLEAN

Clean adjoining surfaces, glass and fittings of any paint contamination. Clean off glass indicators at the completion of the building works. Clean glass inside and out to a shining finish. Use the Resene Washwise on site 'paint equipment clean-up water' reclamation system to minimise the environmental impact of cleaning paint application tools.

3.27 LEAVE

Leave the whole of this work uniform in gloss and colour, of correct thickness, free from painting defects, clean and unmarked and to the standard required by following procedures.

3.28 REMOVE

Remove drop sheets, coverings and masking to leave surrounding surfaces and areas clean, tidy and undamaged. Remove debris, unused materials and elements from the site.

3.29 REPLACE

Replace hardware without damage to it or the adjoining surface and leave hardware properly fitted and in working order.

3.30 DISPOSAL OF PAINTS AND THINNERS

Note: The use and disposal of paint and thinners represents a significant environmental hazard.

Ensure all paint and thinners are disposed of in the following manner:

- When requested hand over part used paint containers to client for maintenance touch ups.
- Recycle leftover paint at a Resene ColorShop as part of the Resene "Paintwise programme". Contact your local Resene ColorShop for details or view information online at www.resene.co.nz/paintwise.htm.
- Donate left over paint to local community groups.
- Solvent based paints, paint thinners, turpentine, mineral spirits and solvents require special disposal procedures. Do not pour down sewer or stormwater drains, sinks or into the ground. If they cannot be recycled they must be disposed of in a refuse dump licensed to take toxic waste.

3.31 MAINTENANCE

Good maintenance of coating systems involves a routine of regular cleaning as well as regular inspections. Regular inspections of the coating systems are recommended to identify breakdown, accidental damage to or undesirable deterioration of the paint.

Wash down of exterior coatings should be undertaken on an annual basis using Resene Paint Prep and Housewash (see Data Sheet D812).

Refer the Resene Caring for your paint finish brochure and the Resene website, www.resene.co.nz/comn/services/maintenance.htm.

4 SELECTIONS

4.1 SELECTIONS

Refer to 6711R RESENE PAINTING EXTERIOR and 6721R RESENE PAINTING INTERIOR for selections.



© CIL Masterspec Sep 2026

6711R RESENE PAINTING EXTERIOR

1 GENERAL

This section relates to the surface preparation, painting and clear finishing of new and existing exterior substrates using Resene Paints Ltd architectural and decorative coating systems.

Related work

1.1 RELATED WORK
Refer to 6700R RESENE PAINTING GENERAL for general matters related to painting work.

Requirements

2 PRODUCTS

Materials

2.1 PRODUCTS
Refer to 6700R RESENE PAINTING GENERAL for product clauses.

3 EXECUTION

Conditions

3.1 EXECUTION
Refer to 6700R RESENE PAINTING GENERAL for execution clauses.

4 SELECTIONS

For further details on selections go to www.resene.co.nz
Substitutions are not permitted to the following, unless stated otherwise.

4.1 BACK PAINTING SCHEDULE
Paint 2 coats (including any pre-prime) to match exposed face coating.

Cladding type	Extent of back painting
JH Linea WB	To cladding manufacturer's requirements

Resene exterior paint systems

Exterior fibre cement cladding - new

4.2 RESENE NEW EXTERIOR LINEA™ BOARDS

Surface Prep:	Resene SIPDS No3 and Spec Sheet 3: 4A/1
1st coat:	Resene Concrete Primer D405, Acrylic Concrete Primer
2nd coat:	Lumbersider Low Sheen D34, Waterborne Acrylic
3rd coat:	Lumbersider Low Sheen D34, Waterborne Acrylic

© CIL Masterspec Sep 2026

6721R RESENE PAINTING INTERIOR

1 GENERAL

This section relates to the surface preparation, painting and clear finishing of new and existing interior substrates using **Resene** architectural and decorative coating systems.

1.1 RELATED WORK
Refer to 6700R RESENE PAINTING GENERAL for general matters related to painting work.
Refer to 6711R RESENE PAINTING EXTERIOR for exterior paint systems.

2 PRODUCTS

Materials

2.1 PAINT TYPES GENERALLY/ THINNERS AND ADDITIVES
Refer to 6700R RESENE PAINTING GENERAL for product clauses.

3 EXECUTION

Conditions

3.1 EXECUTION
Refer to 6700R RESENE PAINTING GENERAL for execution clauses.

4 SELECTIONS

Substitutions are not permitted to the following, unless stated otherwise.

Resene interior paint systems

Plasterboard - new

4.1 RESENE NEW INTERIOR PLASTERBOARD, WALLS - DRY AREAS (LEVEL 4 FINISH)

Surface Prep:	Resene SIPDS No1 and Spec Sheet 1: 1/1
Fire rating:	Group 1-S. Test Report FH4967
1st coat	Resene Broadwall D403, Waterborne Wallboard Sealer
2nd coat:	Resene Zylone Sheen D302, Waterborne Low Sheen
3rd coat:	Resene Zylone Sheen D302, Waterborne Low Sheen

4.2 RESENE NEW INTERIOR PLASTERBOARD, WALLS - WET AREAS

Surface Prep:	Resene SIPDS No1 and Spec Sheet 1A: 1/1
Fire rating:	Group 1-S. Test Report 7-593235-CO
1st coat:	Resene Sureseal D42, solvent-borne Pigmented Sealer (NEC)
2nd coat:	Resene SpaceCote Low Sheen Kitchen & Bathroom D311K Waterborne Enamel
3rd coat:	Resene SpaceCote Low Sheen Kitchen & Bathroom D311K Waterborne Enamel

4.3 RESENE NEW INTERIOR PLASTERBOARD, CEILINGS - DRY AREAS (LEVEL 4 FINISH)

Surface Prep:	Resene SIPDS No1 and Spec Sheet 1: 1/1
Fire rating:	Group 1-S, Test Report FH4967
1st coat:	Resene Broadwall D403, Waterborne Wallboard Sealer
2nd coat:	Resene Ceiling Paint D305, Waterborne Flat
3rd coat:	Resene Ceiling Paint D305, Waterborne Flat

Where durable easily cleaned coating is required substitute 2nd & 3rd coats with:

© CIL Masterspec Sep 2026

4.4 RESENE NEW INTERIOR PLASTERBOARD, CEILINGS - WET AREAS

Surface Prep:	Resene SIPDS No1 and Spec Sheet 1A: 1/1
Fire rating:	Group 1-S, Test Report 7-593235-CO
1st coat:	Resene Sureseal D42, solvent-borne Pigmented Sealer (NEC)
2nd coat:	Resene SpaceCote Flat Kitchen & Bathroom D314K, Waterborne Enamel
3rd coat:	Resene SpaceCote Flat Kitchen & Bathroom D314K, Waterborne Enamel

Interior timber - new

4.5 RESENE NEW INTERIOR TIMBER JOINERY - SKIRTING

Surface Prep:	Resene SIPDS No2 and Spec Sheet 2: 9/1
1st coat:	Resene Quick Dry D45, Waterborne Acrylic Primer Undercoat
2nd coat:	Resene Lustacryl D310, Waterborne Enamel
3rd coat:	Resene Lustacryl D310, Waterborne Enamel

© CIL Masterspec Sep 2026

7120 HOT & COLD WATER SYSTEM

1 GENERAL

This section relates to piped potable water supply systems from the network utility supply authority water main to designated points and appliances, the installation of hot water heating appliances, distributing piped hot water to other appliances, and the installation of valves.

1.1 RELATED WORK

Refer to 7151 SANITARY FIXTURES, TAPWARE & ACCESSORIES for sanitary fixtures and tapware selections.

Documents

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC B2/AS1	Durability
NZBC C/AS1-AS7	Protection from fire
NZBC G4/AS1	Ventilation
NZBC G12/VM1	Water supplies
NZBC G12/AS1	Water supplies
NZBC H1/AS1	Energy Efficiency
AS/NZS 2492	Cross Linked Polyethylene (PE-X) pipe for pressure applications
AS/NZS 2537.2	Mechanical joining fittings for use with crosslinked Polyethylene (PE-X) for pressure applications - Plastics piping systems for hot and cold water installations - Crosslinked Polyethylene (PE-X) - Fittings
AS/NZS 2642.1	Polybutylene pipe systems - Polybutylene (PB) pipe extrusion compounds
AS/NZS 2642.2	Polybutylene pipe systems - Polybutylene (PB) pipe for hot and cold water applications
AS/NZS 2642.3	Polybutylene pipe systems - Mechanical jointing fittings for use with polybutylene (PB) pipes for hot and cold water applications
AS/NZS 2845.1	Water supply - Backflow prevention devices - Materials, design and performance requirements
AS 2845.3	Water supply - Backflow prevention devices - Field testing and maintenance
AS/NZS 3500.1	Plumbing and drainage - Water services
AS/NZS 3500.4	Plumbing and drainage - Heated water services
AS/NZS 3500.5	Plumbing and drainage - Housing installations
NZS 3501	Specification for copper tubes for water, gas and sanitation
AS/NZS 4130	Polyethylene (PE) pipes for pressure applications
NZS 4305	Energy efficiency domestic type hot water systems
NZS 4602	Low pressure copper thermal storage electric water heaters
NZS 4607	Installation of thermal storage electric water heaters: valve-vented systems
NZS 4617	Tempering (3-port mixing) valves
AS/NZS 5601.1	Gas installations - general installations
DIN 8077	Polypropylene (PP) Pipes - PP-H, PP-B, PP-R, PP-RCT - Dimensions
DIN 8078	Polypropylene (PP) Pipes - PP-H, PP-B, PP-R, PP-RCT - General quality requirements and testing.

Gas (Safety and Measurement) Regulations 2010
Plumbers, Gasfitters and Drainlayers Act 2006
NZ Backflow Testing Standard: NZ Backflow Testing Standard 2011, Field testing of backflow prevention devices and verification of air gaps

© CIL Masterspec Sep 2026

Requirements

1.3 INFORMATION FOR OPERATION AND MAINTENANCE

Provide the following general operation and maintenance information as electronic PDF format documents:

~

Provide this information prior to practical completion.

Warranties

1.4 WARRANTY

Provide warranty for:

2 years: For the supply and installation of the plumbing system and fixtures

- Provide the warranty in the standard form in the general section 1237WA WARRANTY AGREEMENT.
- Commence the warranty from the date of practical completion of the contract works.

Performance

1.5 TESTING - TO AS/NZS 3500

Test to AS/NZS 3500.1, Section 18, **Testing and commissioning**, for cold water.

- Test reticulation system to a pressure of 1500 kpa for period not less than 30 minutes, to AS/NZS 3500.1, 18.3.1 **Hydrostatic test**. Test storage tanks to AS/NZS 3500.1, 18.3.2 **Storage tanks.**

and

AS/NZS 3500.4, Section 9, **Testing and commissioning**, for hot water.

- Test reticulation system (excluding tanks, water heaters, and some fixtures, valves etc) to a pressure of 1500 kpa for period not less than 30 minutes, to AS/NZS 3500.4, 9 **Testing**. Test complete system (including valves, pumps, water heaters etc) under normal working conditions for a minimum of 48 hours, then check visually, to AS/NZS 3500.4, 9.3 **Testing.**

Confirm the timing before carrying out any tests. Supply potable water and the apparatus needed. Slowly fill service pipes with water to exclude air. Test and ensure there is no measurable loss of pressure for the minimum period. Slowly fill distribution pipes with water to exclude air. Ensure that with draw-off taps closed the system must remain water-tight.

2 PRODUCTS

2.1 POLYBUTYLENE PIPE

Polybutylene tubing to AS/NZS 2642.1, AS/NZS 2642.2 and AS/NZS 2642.3 complete with fittings and accessories brand-matched with durability to NZBC B2/AS1 Durability, table 1 and NZBC G12/AS1, table1.

2.2 WATER METER

To the requirements of the network utility operator.

2.3 VALVES

Pressure reducing or limiting valve, filter, non-return valve, cold water expansion valve, pressure relief or temperature valve, pressure relief valve and isolating valves to NZBC G12/AS1.

Materials - Hot water heating appliances

2.4 ELECTRIC HOT WATER CYLINDER, MAINS PRESSURE

To NZS 4305, ceramic-coated steel thermal storage cylinder, insulated and complete with required fittings.

© CIL Masterspec Sep 2026

Components

2.5 INSULATION

Pre-formed pipe sections complete with bends and fittings, with fixing tape to the manufacturer's requirements and to NZBC H1/AS1.

2.6 PROTECTIVE TAPE

Plasticised PVC tape system with primer, mastic fixing and outer coating.

3 EXECUTION

3.1 EXECUTION GENERALLY

Generally carry out the whole of this work and tests to NZBC G12/VM1 or NZBC G12/AS1.

3.2 HANDLE AND STORE

Handle and store pipes, fittings and accessories to avoid damage. Store on site, under cover on a clean level area, stacked to eliminate movement and away from work in progress.

Store tapware in a shelved, dry and securely locked area. Retain tapware in the manufacturer's original packaging, complete with all fixings and installation instructions. Label each unit separately with its space/fixture number to match.

3.3 CORE HOLES AND SLEEVES

Review location and fit core holes and sleeves as needed throughout the structure in conjunction with the boxing, reinforcing and placing of concrete. Strip core holes and make good after installation of pipework.

3.4 CONCEAL

Conceal pipework within the fabric of the building unless detailed otherwise. Satin finish chrome plate exposed work, complete with matching ferrule at the surface penetration.

3.5 CORROSION

Separate all metals subject to electrolytic action from each other and from treated timber, concrete and other lime substances by space, painting of surfaces, taping, or separator strips.

3.6 THERMAL MOVEMENT

Accommodate movement in pipes resulting from temperature change by the layout of the pipe runs, by expansion joints and by sleeving through penetrations.

3.7 PIPE SIZE

Flow rates to each outlet to be no less than those given in NZBC G12/VM1 or NZBC G12/AS1, table 3, Acceptable flow rates to sanitary fixtures. Pipe size as determined in NZBC G12/AS1, table 4, Tempering valve and nominal pipe diameters.

3.8 ELECTROLYTIC ACTION

Avoid electrolytic action by eliminating contact or continuity of water between dissimilar metals.

3.9 EXCAVATE

Excavate for the water main to a firm, even trench base in straight runs. Allow to backfill.

Application - Jointing

3.10 JOINTING POLYBUTYLENE PIPE

Aluminium clamped, seal ring compression or push fit "O" ring seal jointing to pipe system manufacturer's requirements.

3.11 JOINTING POLYETHYLENE PIPE

Seal ring compression joints and electrofusion to NZBC G12/AS1.

Application - Pipework installation

3.12 WATER SUPPLY CONNECTION

Arrange with the network utility operator for a connection to the water main and from there through a water meter and gate valve. Provide back flow prevention to NZBC G12/AS1.

© CIL Masterspec Sep 2026

3.13 POTABLE WATER SUPPLY PIPEWORK INSTALLATION

From connection point, run pipes complete with all fittings, support and fixing, joins and install to manufacturers specifications. Size the pipes and branches in straight runs to deliver the acceptable flow rate to NZBC G12/VM1 or NZBC G12/AS1, table 3, Acceptable flow rates to sanitary fixtures at each outlet. Allow for the expected concurrent use of adjoining fixtures and size the piping layout to eliminate loss of pressure at any point by simultaneous draw-off. Pipework support spacing to be firmly fixed and buffered to eliminate noise and hammer, with preformed tee-connection take-offs and branches, with machine made 3 diameter bends, complete with necessary valves and fittings. Conceal pipework and pressure test before the wall linings are fixed.

3.14 HOT WATER PIPEWORK

Use a take-off spigot to give separate branches to each fitting, lay out pipes with support spacing to NZBC G12/VM1 or NZBC G12/AS1, table 7 Water supply pipework support spacing. Fix firmly and buffer to eliminate noise and hammer, with preformed tee-connection take-offs and branches, and preformed 3 diameter bends, complete with all necessary valves and fittings

Lag all pipes with rigid insulation to the manufacturer's requirements and G12/VM1 or G12/AS1.

3.15 IN-LINE FILTER

Install an in-line filter immediately adjacent to the main isolating valve at the point of entry to the building, in an accessible position to allow for easy cleaning.

Application - Hot water systems

3.16 HOT WATER CYLINDER INSTALLATION GENERALLY

Install hot water cylinders complete to the manufacturer's requirements and to NZBC G12/AS1, 6. 11, Water heater installation. Valve-vented systems to NZS 4607.

3.17 SEISMIC RESTRAINTS - NON-GAS WATER HEATING APPLIANCES

Non-gas (electric, wet-back, solar etc) water heating appliances to be restrained to manufacturer's requirements and NZBC G12/AS1, 6.11, Water Heater Installation.

3.18 INSTALLING HOT WATER PIPE INSULATION

Insulate all hot water pipes to NZBC H1/AS1, AS/NZS 3500.5, 3.33 **Water and Energy Efficiency**, and to the insulation manufacturer's instructions. Cut insulation sections tight between timber framing and tight between the webs of steel studs.

3.19 INSTALL ELECTRIC HOT WATER CYLINDERS AND BOILING CYLINDERS

Install where shown complete with all the necessary fittings to the cylinder manufacturer's requirements and in accordance with NZBC G12/AS1: 6.11. Valve-vented systems to NZS 4607.

3.20 INSTALL HOT WATER CYLINDER OVERFLOW TRAY

Install drained overflow tray to hot water cylinder to NZBC G12/AS1.

3.21 PENETRATIONS

Provide and fit collars and escutcheon plates to match the pipework at all penetrations through constructions.

Installation - Valves

3.22 INSTALLING BELOW GROUND ISOLATING VALVE

Install all below ground items such as main isolating valves and water meters in preformed concrete pits or approved equivalent.

3.23 INSTALLING APPLIANCE ISOLATING VALVES - CONCEALED

Install isolating valves for appliances in accessible positions. Locate in adjacent cupboards and position to allow for easy connection and operation.

Completion

3.24 LABEL

Label all pipework with permanent adhesive markers at 3 metre minimum intervals.



© CIL Masterspec Sep 2026

3.25 CLEAN IN-LINE FILTER
Clean all in-line filters on completion of works.

3.26 REPLACE
Replace damaged or marked elements.

3.27 LEAVE
Leave work to the standard required by following procedures.

3.28 REMOVE
Remove debris, unused materials and elements from the site.

4 SELECTIONS

Water main

4.1 POLYETHYLENE WATER MAIN

Size:	25mm outside diameter (i.e. DN 25 in AS/NZS 4130)

Pipework

4.2 POLYBUTYLENE PIPE

Manufacturer:	Contrctor to select
Brand:	

4.3 EXPOSED PIPES

Manufacturer:	Contrctor to select
Type:	white polyethylene composite pipe
Nominal bore:	15mm
Accessories:	white nuts and accessories

Hot water systems

4.4 ELECTRIC HOT WATER CYLINDER, MAINS PRESSURE

Brand:	Rinnai 180 Lt mains pressure
Model size:	180 tl Mains pressure

Valves and accessories

4.5 MAIN ISOLATING VALVE

Location:	contractor to confirm
Brand/type:	contractor to select

4.6 FLOOR/ZONE ISOLATING VALVES

Location:	contractor to select
Brand/type:	contractor to select

4.7 APPLIANCE ISOLATING VALVES - CONCEALED

Appliance:	contractor to select
Brand/type:	contractor to select

4.8 APPLIANCE ISOLATING VALVES - EXPOSED

Appliance:	Washing machine
Brand/type:	Refer to tapware selections

4.9 IN-LINE FILTER

Location:	contractor to select
Brand/type:	contractor to select

© CIL Masterspec Sep 2026

7420 SANITARY SYSTEMS

1 GENERAL

This section relates to above ground gravity flow sanitary systems;

- for foul water
- from sanitary fixtures to first underground drain connection
- including system wastes, floor wastes, floor waste gullies, traps, vents and valves
- with associated components and accessories to make the system work

1.1 RELATED SECTIONS

Refer to 7151 SANITARY FIXTURES, TAPWARE & ACCESSORIES for sanitary fixtures tapware and accessories.

Refer to 7430 DRAINAGE for underground drains.

1.2 DOCUMENTS

Documents referred to in this section are:

NZBC G1/AS1	Personal hygiene
NZBC G13/AS1	Foul water - Sanitary plumbing
NZBC G13/AS3	Plumbing and drainage
AS 2887	Plastic waste fittings
AS/NZS 1260	PVC-U pipes and fittings for drain, waste and vent applications
AS/NZS 2032	Installation of PVC pipe systems
AS/NZS 3500.2	Plumbing and drainage - Sanitary plumbing and drainage

Plumbers, Gasfitters and Drainlayers Act 2006

1.3 QUALIFICATIONS

Carry out all work under the direct supervision of a certifying plumber under the Plumbers, Gasfitters and Drainlayers Act 2006.

2 PRODUCTS

2.1 PVC-U WASTE, DISCHARGE AND VENT PIPES

PVC-U pipe to AS/NZS 1260 complete with fittings brand-matched to the pipe manufacturer's requirements.

2.2 EXPOSED PIPES AND TRAPS

Chrome plate on copper pipes and associated copper and brass fittings.

White polybutylene or PVC, including all associated fittings.

3 EXECUTION

3.1 EXECUTION GENERALLY - AS/NZS 3500.2

Carry out this work and complete all tests to NZBC G1/AS1: 2.0, 3.0 and AS/NZS 3500.2, as modified by NZBC G13/AS3.

3.2 ELECTROLYTIC ACTION

Avoid electrolytic action by eliminating actual contact or continuity of water between dissimilar metals.

3.3 INSTALL TRAPS, WASTE AND VENT PIPES - AS/NZS 3500.2

Connect waste outlets to traps and run waste pipes and back vents concealed, sized and fixed to AS/NZS 3500.2, as modified by NZBC G13/AS3, and AS/NZS 2032. Discharge wastes into the drainage system stack, soil pipe, or gully trap as shown. Bird proof mesh to all roof vents and vermin proof mesh to all untrapped waste pipes.

3.4 PENETRATIONS

At penetrations through constructions provide and fit collars and escutcheon plates to match pipework.

© CIL Masterspec Sep 2026

3.5 TEST

Test soil and waste disposal systems to ensure no leakage exists and leave in proper working order.

3.6 CLEAN UP

Remove labels and clean fittings. Remove unused materials from the site.

4 SELECTIONS

4.1 PVC-U WASTE, DISCHARGE AND VENT PIPES

Brand/type: Contractor to select

4.2 EXPOSED PIPES AND TRAPS

Brand/type: Contractor to select

© CIL Masterspec Sep 2026

7430 DRAINAGE

1 GENERAL

This section relates to the supply and laying of gravity foul water (sewage), stormwater and groundwater drainage.

1.1 DOCUMENTS REFERRED TO

Documents referred to in this section are:

NZBC B1/AS1	Structure
NZBC E1/AS1	Surface water
NZBC G13/AS2	Foul Water
NZBC G13/AS3	Plumbing and Drainage
AS/NZS 1254	PVC-U pipes and fittings for Stormwater and Surface Water applications
AS/NZS 1260	PVC-U pipes and fittings for drain, waste and vent applications
AS/NZS 2032	Installation of PVC pipe systems
AS/NZS 2033	Installation of Polyethylene pipe systems
AS 2439.1	Perforated Plastics Drainage and Effluent Pipes and Fittings - Perforated drainage pipe and associated fittings
AS/NZS 2566.1	Buried Flexible Pipelines - Structural Design
AS/NZS 2566.2	Buried Flexible Pipelines - Installation
NZS 3104	Specification for concrete production
AS/NZS 3500.2	Plumbing and drainage - Sanitary plumbing and drainage
NZS 3604	Timber-framed buildings
NZS 4229	Concrete masonry buildings not requiring specific engineering design
AS/NZS 4671	Steel reinforcing materials
AS/NZS 5065	Polyethylene and polypropylene pipes and fittings for drainage and sewerage applications

Plumbers, Gasfitters and Drainlayers Act 2006

1.2 AS BUILT DOCUMENTS

Supply a 1:100 scale as-built drawing of drains and fittings to the territorial authority and to the owner on completion.

1.3 QUALIFICATIONS

Drainlayers to be experienced, competent and familiar with the materials and techniques specified. Carry out all work under the direct supervision of a certifying drainlayer under the Plumbers, Gasfitters and Drainlayers Act 2006.

2 PRODUCTS

2.1 CONCRETE

17.5 MPa prescribed mix to NZS 3104.

2.2 REINFORCEMENT

Plain round and/or deformed steel bars, Grade 300 to AS/NZS 4671.

2.3 PVC-U PIPES

PVC-U pipes bends, junctions, fittings and joints to AS/NZS 1254 and AS/NZS 1260.

Underground PVC-U pipe to be Classified as follows:

Classification	Use
SN4 - SN6	Domestic & light load areas
SN8 - SN10	Commercial & Industrial medium load areas
SN16	Public roads & high load areas

© CIL Masterspec Sep 2026

2.4 GULLY TRAPS - AS/NZS 3500.2

Gully traps complete with grating to AS/NZS 3500.2, 4.6 Gullies, as modified by NZBC G13/AS3.

2.5 SURFACE WATER SUMP GRATINGS

Cast iron frame with lift-up grating.

2.6 TRENCH BACKFILLING MATERIAL - AS/NZS 3500.2

Bedding & surround:	Crushed rock or gravel screenings of nominal size of 7 - 10 mm.
Backfill material:	Excavated material from the trench (free from rock, hard matter and organic material) containing no soil lumps larger than 75 mm.

3 EXECUTION

3.1 EXCAVATE

Excavate for drains to a firm even base with correct gradients set in straight runs.

Trenches running parallel, below and close to foundations of buildings to NZS 3604 or NZS 4229 to be separated to:

- NZBC E1/AS1, 3.9.7, **Proximity of Trench to Building**, for stormwater and subsoil drains.
- NZBC G13/AS2, 5.6, **Proximity of Trench to Building**, for foul water drains.

3.2 MANUFACTURER'S REQUIREMENTS

All drainage installations to the pipe and fitting manufacturer's requirements.

3.3 DRAINAGE GENERALLY - AS/NZS 3500.2 & NZBC E1/AS1

Carry out drainage work and tests to AS/NZS 3500.2, as modified by NZBC G13/AS3 (foul water), NZBC E1/AS1 (stormwater). Lay uPVC pipe systems to relevant sections of AS/NZS 2032, NZS 2566.1 and AS/NZS 2566.2. Lay polyethylene pipes and fittings to relevant sections of AS/NZS 2033 and NZS 2566.1.

3.4 LAY FOUL WATER DRAINS

Lay drains in straight runs to correct gradients, to discharge into the network utility operator's sewer. Set inspection fittings on a concrete base.

3.5 INSTALL GULLY TRAPS

Set on concrete 50mm above the surrounding ground or paving and brought up to protect the top of the fitting. Trowel off.

3.6 LAY STORMWATER DRAINS

Confirm the required location of downpipes and finished ground levels before commencing pipework. Set downpipe bends in concrete with the concrete brought up to protect the top of the bend from damage. Lay drains in straight runs to correct gradients to discharge into the network utility operator's stormwater system.

3.7 INSTALL SURFACE WATER SUMP

To NZBC E1/AS1, complete with ceramic half-siphon pipe and cast iron frame with a lift out grating.

3.8 INSTALL FOUL WATER INSPECTION CHAMBERS - NZBC G13/AS2

Construct as detailed on a poured concrete footing to NZBC G13/AS2, 5.7 **Access points**. Provide all necessary haunching to channels. Fit a cast iron cover and frame.

3.9 CONCRETE ENCASEMENT

Concrete encase shallow drains and drains under driveways, on a 100mm deep 17.5 MPa concrete bed reinforced with three 10mm mild steel bars. Surround pipes with a polythene membrane to allow movement and encase in 100mm 17.5 MPa concrete.

3.10 FIELD TEST

Field test drains for watertightness (PVC-U to AS/NZS 2032 or AS/NZS 2566. 2 Appendix N) to the satisfaction of the territorial authority inspector.

3.11 PLACING & COMPACTING TRENCH BACKFILLING MATERIAL FOR PVC-U PIPE

Place and rake in bedding material so as to support the pipe once laid.

© CIL Masterspec Sep 2026

Embedment material shall be placed uniformly along and around the pipe to ensure uniform density of side support and overlay with no distortion, dislodgment or damage to the pipeline. Following placement, the embedment material shall be compacted in layers to uniformly support the pipe. Trench fill material shall be placed on the pipe embedment and compacted to fill the trench, with care taken to avoid impact loading of the pipe.

4 SELECTIONS

4.1 PVC-U PIPES

Brand/type: Contract to select



© CIL Masterspec Sep 2026

7701 ELECTRICAL BASIC

1 GENERAL

This section relates to the wiring for domestic and small scale commercial installations, including:

- power
- lighting
- electrical automation
- security system
- complete with componentry
- electrically-powered fittings

1.1 ABBREVIATIONS AND DEFINITIONS

Refer to the general section 1232 INTERPRETATION & DEFINITIONS for abbreviations and definitions used throughout the specification.

The following abbreviations apply specifically to this section:

CFL	compact fluorescent lamp
ELV	extra low voltage
GLS	general lighting service
IP	international (ingress) protection classification
LCD	liquid crystal display
LED	light emitting diode
MCB	miniature circuit breaker
NUO	Network Utility Operator
PCB	printed circuit board
PIR	passive infrared
RCBO	residual current-operated circuit breaker with over current protection
RCCB	residual current-operated circuit breakers
RCD	residual current device
SIA	security integration architecture
TPS	tough plastic sheathed
TCF	Telecommunications Carriers' Forum

Documents

1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

NZBC E2/AS1	External moisture
NZBC F6/AS1	Visibility in escape routes
NZBC F7/AS1	Warning systems
NZBC G4/AS1	Ventilation
NZBC G9/AS1	Electricity
AS/NZS 1125	Conductors in insulated electric cables and flexible cord
AS/NZS 1768	Lightning protection
AS/NZS 2201.1	Intruder alarm systems - Client's premises - Design, installation, commissioning and maintenance
AS 2293.1	Emergency escape lighting and exit signs for buildings - System design, installation and operation
AS 2293.3	Emergency escape lighting and exit signs for buildings - Emergency escape luminaires and exit signs
AS/NZS 3000	Electrical installations (known as the Australian/New Zealand Wiring Rules)
AS/NZS 3008.1.2	Electrical installations - Selection of cables - Cables for alternating voltages up to and including 0.6/1 kV - Typical New Zealand installation conditions

© CIL Masterspec Sep 2026

AS/NZS 3100:2009	Approval and test specification-general requirements for electrical equipment
AS/NZS 3112	Approval and test specification - Plugs and socket-outlets
AS/NZS 3113	Approval and test specification - Ceiling roses
AS/NZS 3190	Approval and test specification - Residual current devices (current-operated earth-leakage devices)
AS/NZS 3350.1	Safety of household and similar electrical appliances - General requirements
AS/NZS 3439.3	Low-voltage switchgear and controlgear assemblies - Particular requirements for low-voltage switchgear and controlgear assemblies intended to be installed in places where unskilled persons have access for their use - Distribution boards
AS 3786	Smoke alarms
NZS 4514	Interconnected smoke alarms for houses
AS/NZS 5000.2	Electric cables - Polymeric insulated - for working voltages up to and including 450/750v
AS/NZS 60598.2.2:2001	Luminaires - Particular requirements - Recessed luminaires
IEC 61643	Components for low voltage surge protection devices

Electricity (Safety) Regulations 2010 (Reprint as at 4 April 2016)
TCF Premises Wiring Code of Practice 2011

Warranties

1.3 WARRANTY

Warrant the complete electrical installation under normal environmental and use conditions against failure of materials and execution.

1 year:	Warranty period

Refer to the general section for the required form of 1237WA WARRANTY AGREEMENT and details of when completed warranty must be submitted.

Requirements

1.4 COMPLY

Comply with the Electricity (Safety) Regulations 2010, AS/NZS 3000, AS/NZS 3008.1.2 and TCF Premises Wiring Code of Practice for listed and prescribed work and with the utility network operator's requirements. Apply for the service connection. Arrange for the required inspections of listed work. Pay all fees.

1.5 QUALIFICATIONS

Carry out work under the supervision of an electrical licensed supervisor.

1.6 ELECTRICAL CERTIFICATE OF COMPLIANCE

Supply a certificate of compliance (CoC) to the owner, and if required the NUO, as required by the Electricity (Safety) Regulations (2010), prior to connection.

- Arrange for the NUO to inspect before the meter installation, listed work inspection, polarity check and supply becoming live.
- Arrange for an inspector to inspect as required by regulation 70.

1.7 ELECTRICAL SAFETY CERTIFICATE

Provide an Electrical Safety Certificate (ESC), as required by the Electrical (Safety) Regulations 2010, to the owner and when required the BCA. To be provided no later than 20 working days after connection and prior to Practical Completion.

© CIL Masterspec Sep 2026

2 PRODUCTS

2.1 MAINS SUPPLY, SINGLE PHASE

Tough plastic sheathed neutral screened cable to AS/NZS 4961 and AS/NZS 3008.1.2, with a minimum rating of 60 amps per phase. Include pilot cable where required by network utility company.

2.2 CABLES

Tough plastic sheathed copper conductors to AS/NZS 5000.2, stranded above 1.0mm², and to AS/NZS 3008.1.2. Minimum sizes as below. Increase sizes if the method of installation, thermal insulation, cable length or load will reduce the cable rating below that of the MCB rating, or produce an excessive voltage drop.

Lighting circuits:	Domestic: 1.5mm² on 10 amp MCBs
Lighting circuits:	Commercial: 1.5mm² on 16 amp MCBs
Power circuits:	2.5mm² on 16 amp MCBs for domestic and unenclosed or unfilled cavity construction
	2.5mm² on 16 amp MCBs for domestic insulated construction, or filled cavity
	2.5mm² on 20 amp MCBs for unenclosed or unfilled cavity construction
	2.5mm² on 16 amp MCBs for insulated construction, or filled cavity, or lengths over 30 metres
Hot water cylinder circuits:	Single phase: 2.5mm² on 20 amp MCBs
Range/oven/hob circuits:	Single phase: 6mm² on 32 amp MCBs

Heat resistant cable for final connections to all heated appliances, and high temperature cable in ambient conditions that may be above 35°C.

2.3 METER BOX

Proprietary manufactured, zinc plated powder coated metal case, or ABS plastic, with glazed panel door, weatherproof where mounted outdoors, and complete with meter mounting, main switch and fuse.

2.4 DISTRIBUTION BOARD

Flush surface mount boards manufactured to AS/NZS 3439.3 and installed in accordance with AS/NZS 3000. Manufactured from engineering grade resin with a glow wire rating of 850°C, complete with neutral and earth busbars, and insulated comb phase bar. Distribution boards to have 20% spare capacity for future additions and alterations.

2.5 CIRCUIT PROTECTION

General requirements including main switch 63A or 100A. Residual current protection 30mA, ensure RCCBs' meet Type A and comply with AS/NZS 3190. MCBs to 4.5kA or 6kA rated.

2.6 WALL BOXES

Standard grid size or equivalent to be manufactured from plastic or metal, with 2 or more gang size to be metal with steel inserts for accessory securing screws. Screw fixed.

2.7 SWITCH UNITS

Single pole switches to be 16 amp minimum rated, double pole or intermediate to be 16 amp minimum rated. All switches to be 230 volt a.c. polycarbonate flushplate units. Refer to drawings/schedules for number of switches per unit, dimmer units, neon (indicator or toggle) units and 2 way units.

2.8 HOT WATER SYSTEM SWITCH

One way 20 amp switch complete with cable clamp for flexible PVC conduit to element enclosure.

2.9 SWITCHED SOCKET UNITS

10 amp, 230 volt flat 3 pin socket outlets fitted with safety shutters and manufactured to AS/NZS 3100, AS/NZS 3112 and AS/NZS 3113, single or multi gang as detailed.

2.10 SMOKE ALARMS

Type 1 domestic smoke alarm to NZBC F7/AS1. 1.2 **Descriptions of alarm systems**. Alarm to AS 3786. A wired 230 volt ionised smoke detector type.

© CIL Masterspec Sep 2026

2.11 SURGE PROTECTION

Protection for the homes appliances with IEC 61643 Class ll surge protection devices fitted to the switchboard. For variable electronic equipment fit IEC 61643 Class lll surge protection to switched socket outlets.

2.12 EXHAUST FANS

Ceiling, wall or duct mounted exhaust fans for ventilation to NZBC G4/AS1, and compliant with AS/NZS 3350.1.

2.13 HEATED TOWEL RAILS

Fixed wired heated towel warmers, double insulated, IPX4 splash-proof, compliant with AS/NZS 3350.1, scratch resistant powdercoated or chrome finish.

2.14 OUTDOOR SWITCHES & SOCKETS

Using materials with superior UV protection, impact strength, and addition chemical resistance when compared with interior polycarbonate fittings. Weather protected, switches to IP56 minimum, and sockets to IP53 minimum. Sockets fitted with safety shutters behind socket pins, and all products able to be padlocked off or on.

3 EXECUTION

3.1 MAIN SUPPLY

Lay underground mains to the NUO requirements. Excavate trench, install cable and marker tape and backfill.

3.2 METER BOX

Fit to meter box manufacturer's and Electricity Retailer's requirements. Recess into external wall in sheltered area and flash to weatherproof to NZBC E2/AS1 fig 69. Arrange for meter installation and connection.

3.3 DISTRIBUTION BOARD

Fit to AS/NZS 3000 and board manufacturer's requirements. Recess into wall or surface mount and ensure fire containment properties of the enclosure are maintained.

3.4 CIRCUIT PROTECTION

Install MCBs at distribution board to AS/NZS3000 to protect each final sub circuit.

3.5 EARTH BONDS

Bond together and to earth all plumbing fittings not adequately isolated, to AS/NZS 3000, the Electricity (Safety) Regulations 2010 and the fitting manufacturer's requirements.

3.6 MAIN EARTH

Provide a plastic toby box to contain and protect the earth electrode. Fix the connecting earth wiring closely and securely against wall surfaces.

3.7 EARTH LEAKAGE PROTECTION

Install RCD protection to AS/NZS 3000.

3.8 RCD - DOMESTIC INSTALLATIONS

Install 30mA RCD protection at the switchboard for all final sub circuits to control outlets and lighting except for fixed or stationary cooking equipment, to AS/NZS 3000.

3.9 RCD - SPECIFIC INSTALLATIONS

Install 30mA RCDs at the distribution board.

Install fixed wired RCD protected outlets (SRCD) in the following areas:

- Wet areas: bathrooms, laundries, kitchens.
- Near pools and water features.
- Where intended for use with cleaning equipment.
- Hand-held tools subject to movement in use, i.e. work-shops, garages.



© CIL Masterspec Sep 2026

3.10 SET-OUT

The position of outlets and equipment shown on drawings is indicative of requirements. Confirm documents and site conditions are not in conflict with other services or features. Resolve conflicts and discrepancies before proceeding with work affected. Confirm on site the exact location, disposition and mounting heights of all outlets, fittings, equipment, penetrations, and use of exposed wiring. Fix outlet items level, plumb and in line.

3.11 CABLING

Install wiring systems to AS/NZS 3000. All cabling run concealed. No TPS cable laid directly in concrete. Locate holes in timber framing for the passage of cables at the centre line of the timber member. Install cable in conduits where required to pass through concrete or underground. In walls run cabling horizontally and vertically in straight lines. In ceilings either run cabling along ceiling framing or attached to catenary wires. Clip cabling to ceiling framing/catenary wires.

3.12 CABLING CIRCUITS

Install all circuits with the appropriately rated cable and circuit protection. Install with a maximum of 8 light switch units or 4 double or single switched socket units on any circuit. Minimum 2 lighting circuits per floor. Separate circuits for all electric heating appliances. Kitchen sockets to be on at least two different circuits.

3.13 WALL BOXES

Mount flush in cavity construction size to fit products selected. Fix vertically mounted wall boxes to studs. Screw fix horizontally mounted switched socket outlet wall boxes to solid blocking or nogs. Fix switch panel wall boxes to solid blocking.

3.14 SWITCH AND SOCKET UNITS

Fit all single and double switch units, all sockets to the following heights (to the centre of the unit) unless shown otherwise on the drawings.

Switch Units:	1000mm above finished floor
Socket Units:	150mm above work benches
	400mm above finished floor

Mount light switches and switch socket outlets vertically and socket units horizontally. Label all switch units that control electrical equipment or special lighting circuits by colour filled engraving on the switch. Use proprietary engraved switch mechanisms where applicable.

3.15 ISOLATING SWITCHES

Locate isolating switches in positions as confirmed by the owner, when not specifically shown on the drawings.

3.16 ELECTRIC HOT WATER SYSTEM

Wire as a separate circuit through a wall-mounted isolating switch, with the cable from switch to element encased in flexible PVC conduit, clamp fixed at each end. Hot water cylinders, thermostats and 3000 watt element supplied and fitted under the hot and cold water system section.

3.17 SMOKE ALARMS

Install Type 1 domestic smoke alarm system to NZBC F7/AS1 3.0 **Domestic smoke alarms**, NZS 4514 and to the alarm manufacturer's requirements. Fit neatly and without damage to the surrounding finish.

3.18 SURGE PROTECTION

Install surge protection devices to manufacturer's requirements and in accordance with AS/NZS 3000 and AS/NZS 1768. When fitting IEC 61643 Class ll protection at the switchboard, protect the device by a dedicated MCB.

3.19 ELECTRIC POWERED FITTINGS AND EQUIPMENT

Install and wire fittings and equipment to individual fittings and equipment manufacturer's requirements. Refer to the drawings for required layouts and locations for equipment. Refer to SELECTIONS for schedules of fittings.

3.20 BATHROOM ELECTRICAL FIXTURES

Install all electrical fixtures. Connect the following bathroom and toilet electrical items:

- Heated towel rails: Install to manufacturers requirements and installed in accordance with AS/NZS 3000 and the NZBC G9/AS1

© CIL Masterspec Sep 2026

- Mirror demisters: Locate centrally above the wash hand basin(s). Connect wiring to room lighting unless specified otherwise.
- Exhaust fans: Install exhaust fans to manufacturer requirements. Installed in accordance with AS/NZS 3000 and NZBC G4/AS1.

3.21 OUTDOOR/EXTERIOR SERVICES

Install all wiring systems in accordance with AS/NZS 3000 and in accordance with the manufacturer's recommendations:

Provide circuits and connections for exterior installations, including ELV 12/24 Volt path lighting and electronic irrigation systems. Refer to drawings for connection points. Where underground, ensure appropriate protection, such as thickness of sheathing, conduit, depth of cabling, and proximity to other services.
Use the appropriate rated fittings for power control and power supply. Weather protected switches to IP56, and sockets to IP53 as a minimum. Install to manufacturer's specifications using recommended fittings and sealants to maintain the products integrity.
Earth leakage protection to be provided for in areas where there is increased risk to human safety in the form of either RCDs at the distribution board, or socket outlet. RCDs are recommended for visible awareness of protection.

3.22 LABELLING

Include label under each controller, switch and circuit breaker on distribution boards. Include a warning notice if light dimmers are used in the installation. List the rating of each circuit.

Completion

3.23 COMPLETION

Leave installation operating correctly, with equipment clean and operational.

4 SELECTIONS

Materials

4.1 SELECTIONS - FITTINGS AND HARDWARE

Confirm selections of all outlet fittings and hardware with the owner in writing before ordering.

4.2 METER BOX

Location:	Refer Electrical Plan
Brand / type:	Contractor to select

4.3 DISTRIBUTION BOARD

Location:	Refer Electrical Plan
Brand / type:	Contractor to select
MCB:	Contractor to select
RCCB:	Contractor to select
RCBO:	Contractor to select
Surge protectors:	Contractor to select
Modular contactors:	Contractor to select
Main switch:	Contractor to select
Timers	Contractor to select

Outlets - fittings

4.4 INTERIOR OUTLETS

Item	**Brand / type**
Switch / socket outlets:	to be selected
Coverplate colour:	to be selected
Switch module colour:	to be selected

Item	**Brand / type**
Light dimmers:	to be selected

© CIL Masterspec Sep 2026

Timer switch:	to be selected
Push button switch:	to be selected
Symbol switch:	to be selected
PIR sensor switch:	to be selected
Toggle switch:	to be selected as required
Waterproof switches:	to be selected as required

Item - RCD	**Brand / type**
Socket outlet:	Contractor to select
Shaver outlet:	Contractor to select
Safety switch:	Contract to select

4.5 SMOKE ALARMS

Location:	to be selected
Brand / type:	to be selected

4.6 EXTERIOR SWITCHES AND SOCKETS

Item	**Brand / type**
Weatherproof socket outlets:	to be selected
Timer switch:	to be selected
Weatherproof switch:	to be selected
Daylight switch:	to be selected

4.7 MISCELLANEOUS ELECTRICAL ITEMS

Item	**Brand / type**
Door bell system:	to be selected
Extractor fan:	to be selected

4.8 HEATED TOWEL RAILS

Location	**Brand / type**
	to be selected

4.9 BATHROOM FANS AND HEATERS

Location	**Brand / type**
Bathroom / ensuite-Extract:	Manrose EL 100S

© CIL Masterspec Sep 2026