Premier Services Limited

P R O J E C T S P E C I F I C A T I O N

JCO26005 Utton

93 Stalker Road

Lower Shotover

Queenstown

Issued for Tender/Consent

JCO26005

PROJECT OVERVIEW

Scope

Addition of garage to existing dwelling. Existing Garage converted to additional bedroom. Re-roof and re-clad walls

Address

Site Address	93 Stalker Road
Suburb	Lower Shotover
Region	Queenstown
Lot #	821
DP #	503962

Site Conditions

Wind Zone	H - High Wind Speed
Earthquake Zone	Zone 3
Exposure Zone	Zone B - Low
Snow Loading Zone	Zone N5

© Productspec 2026

TABLE OF CONTENTS

Preliminaries & General....5
Project Overview - RMBF....5
Siteworks....12
Site & Scope....12
Excavation & Siteworks....13
Waterproofing....15
Membrane Tanking & Damp Proofing....15
Carpentry....18
James Hardie Eaves & Soffits....19
Timber Framing....21
Workmanship & Materials....25
Underlay, Foil & DPC....34
GIB® Plasterboard Linings....38
GIB® EzyBrace® Systems....49
GIB® Wet Area Systems....54
Marshall Weatherization System & Underlay Systems....60
Cladding & PreCladding....65
James Hardie Linea™ Weatherboard....65
External Window & Door Joinery....68
APL Residential Aluminium Windows & Doors....68
Insulation....76
Pink Batts Insulation....76
Roofing....82
COLORSTEEL® - Roofing Specification....82
Tiling....84
Tiling....84
Painting & Decorating....87
General....87
Plumbing....90
Aquatherm Flexi Pipe System....91
Materials....94
Plumbing Elements....94
Systems....94
Workmanship....94
Drainage....95
Workmanship....95
Elements....96
Stormwater Drainage....97
Electrical....107
Workmanship....107
Elements....109
Interconnected Smoke Alarms....110
Systems....112
Materials & Control....112
HVAC....113
Panasonic Heat Pumps....113
Appendix....115
Dektite Premium Spec 03 Sep 24....115
VENT DriSpace Roll Panel Vent G502 - January 2024....115

© Productspec 2026

Continuous Quartz gutter profile 115
James Hardie Eave & Soffit Installation Manual (Feb 2025) 115
CodeMark Certificate of Conformity - James Hardie Linea Weatherboard Direct Fixed and Cavity Cladding 115
Linea™ Weatherboard Cavity Fix Technical Specification 115
BRANZ Appraisal No.767 - Pink® Batts® Skillion Roof Insulation 115
Pink Batts Acoustic Silencer Product Sheet 115
Pink® Batts® Wall Installation 115
Pink® Batts® Skillion Roof Installation 115
BRANZ Appraisal No. 238 PINK® BATTS® INSULATION 115
Belgotex Amtico 115
BRANZ Appraisal No.708 - Aquatherm Flexi Pipe System 115
BRANZ Appraisal No.928 - GIB EzyBrace Systems 115
BRANZ Appraisal No.427 (2021) - GIB Aqualine Wet Area Systems 115
BRANZ Appraisal No.548 - Tekton® Building Wrap 115
BRANZ Appraisal No.1071 - HYDRA Roof Underlay 115
BRANZ Appraisal No.446 - Linea Weatherboard Direct Fixed Cladding 115
COLORSTEEL Maxam™ Product Information Sheet 115

© Productspec 2026

1 PRELIMINARIES & GENERAL

1.1 Project Overview - RMBF

1.1.1 Contract Documents

The Contract Documents are complementary and comprise this Specification, the accompanying drawings, the Registered Master Builders Federation Contract together with Schedules as specified below, any written documentation clarifications issued during tendering/estimating, any manufacturer/supplier information issued with this Specification, any list of agreed Subcontractors, the contract establishment letter and any other relevant correspondence, and any Site Instructions or additional details or instructions issued as Variations. (The Registered Master Builders Federation Contract will be emailed upon request).

If the Architect/Designer has not been engaged to administer the Contract or observe the works, then the term Architect/Designer, where referred to in this specification, means Contract Administrator.

These Project Specific Conditions supersede the Standard Conditions where they are in conflict. Refer any ambiguity or apparent discrepancy within or between any Contract Documents to the Architect/Designer, whose interpretation shall be binding on all parties.

Ensure that all Trades are aware of all Conditions and that subcontract prices are accepted on this basis, and in a form acceptable to the Registered Master Builders Federation or the Certified Builders Association. Ensure that all persons engaged on the works are aware of all items in this specification and on the drawings that may in any way affect their section of the works.

1.1.2 Site

Relevant site conditions are believed to be correctly represented in the Contract Documents, however the Contractor (and Subcontractors where appropriate) are requested to inspect the site to ascertain for themselves the nature and extent of the works and the rights and interests that may be interfered with in the execution of the works, as no claims for additional payment will be recognised on the grounds of insufficient description.

1.1.3 Adjacent Owners

Carry out whatever actions or precautions are required to avoid or to absolutely minimise noise, dirt, dust, access, etc. inconvenience or disruption of any nature to the adjacent owners or tenants. Indemnify the Principal against any claims arising from this source.

1.1.4 Protection

Take all appropriate precautions to protect all third party property, services, etc., and indemnify the Principal against any claims arising from the construction operations. Any damage to third party property caused by construction activities or failure to protect shall be rectified as soon as possible by the person causing the damage, or by appropriately qualified trades-persons employed by the person responsible for the damage if necessary.
Suspend operations during weather which would affect the quality of work in progress. Secure the

works as soon as possible against adverse weather, dust and vandals. Avoid structural damage that is caused by overloading.
Adequately protect all finished work and maintain until the date of Practical Completion. Each trade shall protect the work of all other trades, and each trade is responsible for making good any damage they cause to finished works. Arrange special protection as required for windows and doors, finished timber work, plumbing fittings and hardware, cabinets and other joinery, and similar items.

1.1.5 Responsibility

The Contractor will be held responsible for the full period of their legal responsibility in connection with this Contract for ensuring that all work execution, materials, and fittings, are completely in accordance with Contract requirements.
The Contractor is responsible to the Principal for the appropriateness and fitness, in relation to a reasonable expectation or requirement, of all of the materials and workmanship incorporated into the works by themselves or their subcontractors; for this reason few specific guarantees are required in these contract documents. The terms and conditions of any warranty or guarantee required or provided shall not in any way negate the minimum remedies available under common law as if no warranty or guarantee had been furnished.
No apparent expression of the Architect's/Designer's reasonable satisfaction shall be deemed to be acceptance of defective materials or workmanship within the terms of the Contract or to be an authority for any Variation except where such Variation is authorised as provided for in the Contract. Instructions that are given verbally are deemed to be instructions for proper execution of the works and do not involve extra charges.

Workmanship in all trades is required to be equal to or better than recognised good trade practice. The Contractor shall provide all necessary setting out information and component dimensions for subcontractors and shall check and be responsible for the accuracy of their work.

Should any tradesperson consider that the surface finish or general conditions of previous work are unsatisfactory to ensure a proper finish for their own work thereon, that tradesperson shall give immediate notice to the Contractor or Architect/Designer as appropriate and shall not proceed until all necessary improvements have been made. Failing such notice the trade concerned will not be relieved of responsibility for a poor finish due to such unsatisfactory condition.
Specialist Finishes Subcontractors are responsible for ensuring that substrates are completely appropriate for them to achieve first class results, and to this end shall, in sufficient time, instruct the Contractor with regard any fixings, primings, sealings or whatever for the substrate that vary in any way from the substrate manufacturer's standard recommendations. The Contractor shall advise the Architect/Designer with regard these variances, and not proceed until the Architect/Designer has agreed to them.

The Contractor and all Subcontractors affected shall be jointly and severally responsible for completion of the whole of the works in a completely watertight condition and shall therefore examine all details to be satisfied that this condition can be achieved. If any detail is considered unsatisfactory the Architect/Designer shall be notified immediately and he/she will then either interpret the detail to the Contractor's satisfaction, or accept responsibility for watertightness at the points in question, always assuming reasonable workmanship.

Ensure that all materials or items incorporated into any particular construction or finish are compatible and that their individual use is approved by the manufacturers and/or suppliers of the other parts of the system.
For all electronic/electrical/mechanical operating systems all work and all necessary materials and items incidental to the primary item specified, that are incorporated into the works, shall be such as to leave a neat, efficient, easily maintained and robust installation, completely in accordance with all of the recommendations of the primary items' manufacturers. Where appropriate, source all parts of a system from a single supplier or manufacturer.

The Contractor shall make provision for all temporary works and services required for the satisfactory completion of the contract works. The Contractor shall pay all associated costs and fees; carry out all necessary maintenance, alterations and servicing requirements; and remove temporary works and services on completion of the contract works. Temporary works and services shall comply with the requirements New Zealand Building Code.

1.1.6 Specification

This Specification covers contract administration, standards, materials quality, workmanship and the scope of works only: the exact nature of the works and all specialist items, descriptions, etc., are contained on the drawings, which also take full precedence.
All clauses in all specification sections apply to their full extent and meaning to the entire Contract.
Trade sections and paragraphs have been introduced into this specification for reference only and it shall not be construed that each trade section is a complete segregation of the materials and labour of that trade. The onus is on all trades to be conversant with any and all clauses which in any way affect their work.
(Be aware that the ‘scope’ noted in the ‘Project Overview’, and scope and general extent clauses within this specification, are included to provide a general indication only and must NOT be interpreted as schedules of quantities - the exact nature and extent of all aspects of the works are shown on the drawings).

1.1.7 Standards

New Zealand Standards (NZS), Australian Standards (AS), Joint Standards (AS/NZS), British Standards (BS), Acts of Parliament, Regulations made thereunder, Codes of Practice, and any specific Manufacturer's Instructions or Manufacturer's Recommendations that are referred to in these Contract Documents shall all be deemed to be the latest published edition thereof at the time of drawings issue, and shall be followed by the Contractor and all Subcontractors to the full extent applicable consistent with the intent of this Contract. Documents cited within other cited publications are deemed to form part of this specification.
Where Standards have a number of Divisions, e.g. AS/NZS 3500.1, AS/NZS 3500.2, etc., each of the Divisions relevant to this project is deemed to form part of this specification.
Retain current copies of significant cited documents and manufacturer's technical literature on the site.

1.1.8 Authorities and Charges

Comply with all relevant provisions of the NZ Building Code, and with all relevant territorial or statutory authority regulations, by-laws, obligations, etc. Give all required notices.

The Principal has obtained a Land Use Consent. The Principal has applied for and paid for the Project Information Memoranda, the Building Consent and other approvals required for the works to start. The PIM and Building Consent will be forwarded to the Contractor as quickly as possible after they are issued by the Territorial Authority. Note: It is an offence under the Building Act to carry out work not in accordance with a Building Consent.
Should the Building Consent be subject to any conditions which modify the requirements of the Contract Documents in any way, the Architect/Designer reserves the right to negotiate any or all of these modifying conditions with the Building Consent Authority. If after these negotiations additional work is required, it will be handled as a Variation to the Contract.

1.1.9 Code Compliance Certificate

The Principal will apply for the Code Compliance Certificate (CCC) and any other licenses or approvals for the building to be used. However, Practical Completion will NOT be certified until the CCC inspection has occurred and any additional works required by the local Building Consent Authority have been completed. To this end it is recommended that the Contractor obtains all required certificates, guarantees, Producer Statements, as-built drawings, etc., required for the CCC application as work proceeds, to facilitate application for the CCC as soon as the works are completed. For their part, the Principal hereby undertakes to apply for the CCC within one day of all required material being in hand. Likewise, the Contractor should have capacity available to attend as quickly as possible to any items identified by the Building Consent Authority as being required prior to the issue of the CCC.

1.1.10 Coordination of the Works

Coordinate the works of all trades to ensure efficient progress of the works. Ensure that all holes, sleeves, penetrations, supports, etc., that are required for services are correctly incorporated as work proceeds. Identify and sufficiently forward-notify the appropriate persons of all deadlines for the supply of fittings, components, information, etc.

1.1.11 Documentation Interpretation

Except where they are clearly to the contrary, all dimensions are deemed to be to the bare surface of concrete, masonry, timber framing or other basic construction material. All figured dimensions take precedence over scaled sizes. Where any detail is included in more than one drawing the larger scale detail takes precedence. Where any ambiguity exists refer to the Architect/Designer for interpretation.
The word ‘provide' and the word ‘fix' used separately in the Documents shall be taken to mean ‘provide and fix' unless otherwise stated.
When the term ‘allow' occurs in the Documents, except with reference to Monetary Allowances, the cost of the item shall be at the risk of the Contractor.
The terms ‘approved', ‘directed', and ‘selected' when used in the Documents refers to the approval, direction or selection of or by the Architect/Designer. Please give adequate notice of when these decisions are required. ‘Architect/Designer' shall mean the Architect or Designer, their representative or any Consulting Engineer engaged by the Architect/Designer.

1.1.12 Work Shown and Mentioned

The Contract Documents show the extent and nature of the works but there is no warranty expressed or implied that they show each and every minor detail or item required to be included by the Contractor. Should any material, structural member, fixing, or item or work appear to be inadequately described, yet obviously necessary for the neat, strong and satisfactory completion of the work, it shall be incorporated into the Contract Works.

1.1.13 Site Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance. Comply with the relevant provisions of the New Zealand Building Code, in particular Clause F5.

So far as is reasonably practicable and according to a PCBUs (person conducting a business or undertaking) primary duty of care, take all necessary steps required to make the site and the contract works safe, and to provide and maintain a safe working environment. Ensure that all those working on or visiting the site are aware of the site safety rules and are not unnecessarily exposed to hazards.

Each PCBU, so far as is reasonably practicable, must ensure the health and safety of workers, and that other people are not put at risk by its work. If more than one PCBU has a duty in relation to the same matter, each PCBU with the duty must, so far as is reasonably practicable, consult, co-operate with, and co-ordinate activities with all other PCBUs who have a duty in relation to the same matter. PCBUs can enter reasonable agreements with other PCBUs to meet their duties, but cannot contract out of their duties.

Notify WorkSafe as soon as possible when a notifiable event occurs. Take all reasonable steps to preserve the site of the notifiable event in accordance with WorkSafe requirements. Ensure that the site of the event is not disturbed until authorised otherwise by WorkSafe. Keep records of all notifiable events.

Scaffolding shall comply with all Statutory and Local Authority Regulations, with the WorkSafe 'Best Practice Guidelines for Scaffolding', AS/NZS 1576 (Scaffolding equipment), AS/NZS 4576 (Guidelines for Scaffolding), and AS/NZS 4994 (Roof edge scaffolding), and shall be maintained for the duration and removed on completion.

The use of ballistic fixings must absolutely comply with all relevant safety recommendations at all times. No rubbish fires are allowed on site. Portable/personal disc/tape players, radios and iPods must not be used anywhere on the site. No smoking on site, except in the designated location in accordance with the Smoke Free Environments Act 1990, the location of which will be determined by the Contractor, with the approval of the Principal.

A PCBU's primary duty of care includes, but is not limited to, so far as is reasonably practicable:
- providing and maintaining a work environment that is without risks to health and safety;
- providing and maintaining safe plant and structures;
- providing and maintaining safe systems of work;

- ensuring the safe use, handling and storage of plant, structures and substances;
- providing adequate facilities for the welfare at work of workers in carrying out work for the business or undertaking, including ensuring access to those facilities;
- providing any information, training, instruction, or supervision that is necessary to protect all persons from risks to their health and safety arising from work carried out as part of the conduct of the business or undertaking;
- monitoring the health of workers and the conditions at the workplace for the purpose of preventing injury or illness of workers arising from the conduct of the business or undertaking.

Before commencing work on the site, the Contractor shall prepare and submit to the contract administrator a health and safety plan. The health and safety plan shall include, but not be limited to:
- the health and safety of all people on the site and on other properties, and the general public;
- identification of existing and potential construction hazards and risks;
- safety procedures to eliminate, isolate or minimise construction hazards;
- the equipment to be used to minimise the hazards;
- the maintenance of a register of hazards for the site;
- the name and qualifications of the site safety person;
- emergency procedures;
- first aid facilities and safety equipment;
- the methodology for notifying, recording and investigating accidents and injuries.

Carry out all construction operations in accordance with the submitted health and safety plan.

1.1.14 Variations

The Architect/Designer will issue Site Instructions (SI) to amend or clarify the works. Upon receipt of a SI the Contractor shall immediately notify the Architect/Designer if they believes there are price or timing adjustment implications. The Architect/Designer will then issue a Variation Price Request (VPR) for pricing of the possible Variation by the Contractor, within the time stipulated, or within 10 days if no time is stipulated. If the Contractor does not return the VPR within the time stipulated the Architect/Designer will assess it at reasonable rates. Once agreement is reached on price and/or timing a Variation Order (VO) for the item will be issued. Note that works covered by a SI or a VPR must NOT be actioned until the VO is issued.

When a Variation is contemplated and timing does not allow SI and VPR action the Contractor is to advise, and record in the site diary, an estimate of price and timing implications. If accepted by the Architect/Designer, a VO will be issued immediately. The Contractor shall then co-operate with the Architect/Designer to establish agreed pricing.
Claims for Variations neither priced nor estimated prior to being put in hand (but considered valid) will be incorporated into Progress Payment Certificates or the Draft Final Accounts as claimed and accepted but with a proviso allowing 5 (five) days for written objections by either the Principal or the Contractor, to any aspect of them, for further consideration.

The Main Contractor's Variations Margin agreed pre-contract will be the maximum accepted for any trade unless higher rates are nominated pre-contract and are accepted. The Main Contractor's agreed Variations Margin shown shall be deemed to include all preliminary and general costs, overheads, variation processing costs, and profit. If no margin is given, a 5% overall margin will be

applied.
Note that ‘loss of anticipated profit' claims consequent upon reduction of works extent will NOT be recognized, and that the cost of processing Variations is deemed to be included in the P & G Allowance.
Also note that for Variations pricing all materials shall be charged at the actual net invoiced cost plus margin; i.e. recognised ‘Trade Price’, volume discounted where appropriate.

1.1.15 Cleaning and Completion

Clear construction debris and rubbish from the works at regular intervals, and additionally if so instructed by the Architect/Designer. Clean each space thoroughly before commencing any finishing works.

In preparation for the Practical Completion inspection carry out the following:
- Clean the works thoroughly, removing all debris, surplus materials, splashes, marks, temporary markings, etc. (All cleaning methods and materials shall be as recommended by the manufacturer of the item being cleaned).
- Remove protective wrappings and coverings unless otherwise directed.
- Touch up minor painting faults, carefully matching colour, and brushing out edges. Repaint any badly marked surfaces back to suitable break-lines.
- Adjust, ease and/or lubricate as required all doors, drawers, controls and other moving parts to ensure their efficient operation.
- Any other works required to leave all spaces ready for immediate occupation and all electronic/electrical/mechanical systems fully operational.
- Clean out all spoutings, gutters, downpipes, and gullies and flush out all drains.
- Clean all sanitary appliances and check all aspects of the water services.
- Thoroughly re-inspect all aspects of the works (and have any defects fully rectified) to be certain that the works are completely ready for the Practical Completion inspection - if an unreasonable number of items are noted by the Architect/Designer during the inspection it will be terminated and then rescheduled for at least a week forward to allow proper completion to be achieved.

(Note that a Code Compliance Certificate must be obtained before Practical Completion will be certified. Obtain all required certificates, guarantees, as-built drawings, etc., as work proceeds to enable the CCC application to be submitted as soon as construction is completed).

2 SITEWORKS

2.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

2.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

2.3 Site & Scope

2.3.1 Site

Note that no claims will be recognised on the grounds of insufficient description of existing site conditions in the Contract Documents.

Take great care to excavate/cut up to the boundary, but not over.

Note that bulk landforming, building platform excavation and roadway construction will be carried out prior to this contract.

2.3.2 Scope

This section covers:

Rabbits control
Demolition work
Boulders salvage

Removal of vegetation
Excavation of topsoil and stockpiling and final distribution
Excavation of topsoil and stockpiling and final distribution (and new topsoil)

Excavation as required for foundations and slabs
Excavation as required for foundations, slabs, and drive
Excavation as required for foundations, slabs, and carpark
Excavation as required for foundations, slabs, carpark and drive

Supply, placing and compaction of hardfill basecourse and sand blinding
Supply and placing of any site concrete required

Supply and installation of retaining walls waterproofing systems and field drains
Backfilling behind retaining walls

Preparation for, and installation of asphalt driveway paving
Supply and installation of asphaltic concrete

Preparation for paving works, and sandstone and asphalt paving
Preparation for sandstone and schist paving
Preparation for and installation of paving
Preparation for, and installation of exposed aggregate paving
Supply and installation of flagstone paving

Preparation for, and installation of topsoil to planter areas
Instant lawn supply and installation
Grass for disturbed areas around the works areas

Polythene groundcover under the timber floor
Preparation for and installations of Gobi blocks
Supply and installation of the trampoline

2.3.3 Waahi Tapu

During excavation, should a waahi tapu or other cultural site be unearthed, cease excavation operations immediately, and inform the Contract Administrator. Inform the local Iwi, and inform Heritage New Zealand Pouhere Taonga and apply for an appropriate authority if required. Take appropriate action, following discussions with Heritage NZ Pouhere Taonga and Territorial Authority, and runanga/runaka/iwi if Maori, to remedy any damage and/or to restore the site.

Note; in accordance with the Heritage New Zealand Pouhere Taonga Act 2014, where an archaeological site is present (or uncovered), an authority from Heritage New Zealand is required if the site is to be modified in any way. An archaeological site is defined in the Heritage New Zealand Pouhere Taonga Act 2014 as any place in New Zealand (including buildings, structures or shipwrecks) that was associated with pre-1900 human activity, where there is evidence relating to the history of New Zealand that can be investigated using archaeological methods.

2.4 Excavation & Siteworks

2.4.1 Excavation

Excavation work shall be carried out in accordance with the WorkSafe NZ Excavation Code of Practice. Co-ordinate with other trades as to set-out and timing to ensure that all cut faces are covered or finished etc. as soon as possible after the excavation is complete.

Plan the excavation carefully to ensure that stockpiles will not interfere with concrete construction, to stockpile just sufficient material for the filling, backfilling and reshaping required later, and to avoid overlaying areas outside the works area with material.

As the bulk scope of excavations works will have been carried out prior to commencing work on site, advise and co-ordinate with the separate contractor to ensure that the main building platform is consistent with what is expected. If any concerns are raised please immediately advise the Architect for direction.

Cease machine excavation above final levels and trim to the finish profiles by hand where appropriate. Any over excavation in critical foundation, etc. areas made up with 10MPa concrete unless otherwise approved. Trim slab benches exactly to the required level to allow for hardfill and blinding.

Noisy excavation equipment shall be used only during hours which will avoid undue nuisance to the occupants of adjacent properties.

Excavate accurately in position and true to line and minimum sizes and to levels and grades required for all slabs, footings and foundations, and over the rest of the areas shown for levels adjustment.

Excavations down to firm undisturbed ground, and footings and foundations 200mm minimum into solid, except where shown otherwise.

Below slabs on ground the general intent is to excavate to a stable undisturbed subgrade (of 300 kPa ultimate bearing capacity).

From the excavated material select the most appropriate material for compacted filling and stockpile it in appropriate positions sufficient for filling and backfilling (but NOT for hardfilling).

Keep excavations free of water - remove foundation trench material which becomes water-softened.

Ensure that rainwater runoff from excavated surfaces does not carry material onto adjacent properties.

Report for instruction when any unexpected voids, made-up ground or similar are encountered.

Report the finding of antiquities or other items of value, and leave them undisturbed until approval (and instruction) is given for their removal - they remain the property of the Principal.

2.4.2 Excavation Completion

As soon as excavation and filling is complete and before any concrete is placed or other work proceeded with the foundation material will be inspected by the Engineer, and any necessary changes to foundation widths or details will be directed.

2.4.3 Hardfill & Blinding

Hardfill under slabs on grade shall be 150mm of standard TNZ AP40 basecourse free of clay or organic matter compacted to 95% relative compaction in accordance with NZS 4402 Test 4.1.1.

Blind hardfill under all slabs to a minimum 20mm thickness with clean damp sand.

3 WATERPROOFING

3.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

3.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

3.3 Membrane Tanking & Damp Proofing

3.3.1 Scope

Supply and install the specified below-ground membrane tanking and damp-proofing, complete with all components and accessories, to the locations shown on the drawings. All aspects of this work shall be in strict accordance with the manufacturer's technical guidelines, installation specifications and details, other relevant product manufacturers' recommendations, and as shown on the drawings.

3.3.2 Membrane System

3.3.2.1 Torch-on Membrane Tanking System

Torch-on Membrane Tanking System.
A flexible, fibre reinforced, asphalt waterproofing membrane, installed as a waterproof tanking system to properly prepared concrete/concrete block substrates, either fully (shallow depth) or partly below ground where there IS RISK of hydrostatic water pressure, in accordance with the manufacturer's requirements and as shown on the drawings.
Fabricated from modified bitumen reinforced with non-woven polyester.

Manufacturer, brand name & type: Ardex WPM196
Membrane thickness: 4mm
Primer: Ardex WPM240
Location: Footing Membrane and Underslab Memrbrane

3.3.2.2 Self-Adhesive Membrane Tanking System

Self-Adhesive Membrane Tanking System.
A flexible self-adhesive waterproofing sheet membrane, installed as a waterproof tanking system to properly prepared concrete/concrete block substrates, either fully (shallow depth) or partly below ground where there IS RISK of hydrostatic water pressure, in accordance with the manufacturer's requirements and as shown on the drawings.
Fabricated from high density polyethylene film and a self adhesive bitumen/polymer compound.

Manufacturer, brand name & type: Ardex WPM 3000X Shelterseal
Membrane thickness: 1.5mm

Primer: Ardex WPM240 or WPM247
Location: Tiltslab wall

3.3.3 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings. Co-ordinate with other trades to install below-ground membrane tanking and membrane damp proofing as required.

3.3.4 Workmanship

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All installation work shall be carried out by experienced contractors, authorised by the manufacturer, familiar with the specified products and installation techniques, to fully comply with all of the manufacturer's warranty requirements in accordance with the manufacturer's installation requirements and as noted and detailed on the drawings.

3.3.5 Delivery & Handling

Store products off the ground on a flat surface undercover, keep materials dry and out of direct sunlight, and protect from damage and freezing conditions. Do not use damaged or faulty products, or products beyond the designated shelf life. Handle materials and products in accordance with the manufacturer's recommendations.

3.3.6 Preparation

3.3.6.1 Concrete/Concrete Block

Ensure that the concrete/concrete block substrate is sound, clean and dry, and free of all contaminants and loose particles, and is smooth and regular with all sharp protrusions ground off, with any blockwork mortar struck flush. New structural concrete should be aged for a minimum of 28 days prior to application. Check that all substrate edges and corners, and all required chases, have been formed and completed to the manufacturer's requirements, and as specified and shown on the drawings.

3.3.7 Primer

Apply the tanking membrane primer to properly prepared substrates for optimum membrane adhesion in accordance with the manufacturer's requirements. Limit priming to no more than can be covered by the membrane in one working day or as recommended by the manufacturer, and protect the primed surface from contamination until membrane installation.

3.3.8 Installation

3.3.8.1 Torch-on Membrane Tanking System

Install the specified single layer tanking system, including all surface priming, membrane application, jointing, flashing and sealing, etc., and all system manufacturer supplied fillets and metal edge trims, in strict accordance with the manufacturer's specifications and details, and as shown on the drawings. Membrane heat fused to the primed substrate correct face out with joints fully heat welded,

overlapped as recommended by the manufacturer, and neatly finished straight, parallel and plumb.
All pipe and duct penetrations correctly flashed, sealed and completed to the manufacturer's details.
Consult the manufacturer regarding any detail where a standard tanking system detail does not exist.
Protect installed membrane as required, avoid puncturing or damaging the membrane during installation; repair or replace as necessary.

3.3.8.2 Self-Adhesive Tanking System

Install the specified Self-Adhesive Tanking System, including all surface priming, membrane application, jointing, flashing and sealing, etc., and all system supplied fillets and metal edge trims, in strict accordance with the manufacturer's specifications and details, and as shown on the drawings.
Apply reinforcing gussets to internal and external corners and other high stress areas. Membrane firmly applied to the primed substrate with joints pressure sealed, minimum side-laps and end-laps as specified by the manufacturer, neatly finished straight, parallel and plumb. Avoid entrapped air as the sheet as applied.
All pipe and duct penetrations correctly flashed, sealed and completed to the manufacturer's details.
Consult the manufacturer regarding any detail where a standard system detail does not exist.
Protect installed membrane as required, avoid puncturing or damaging the membrane during installation; repair or replace as necessary.

3.3.9 Completion

Check that the tanking system has been installed correctly, and that all system accessories are correctly installed and finished. Check membrane for damage and punctures, repair or replace as necessary.
Complete all tanking leak free and watertight in accordance with the manufacturer's requirements in preparation for backfilling against protected wall membranes and/or for concreting over under-slab membranes.
Completely clean the works area and remove all rubbish and waste material from the site.

All drainage coils, and backfilling etc. installed by others in accordance with the manufacturer's recommendations and as specified and shown on the drawings.

Issue to the Owner a copy of any necessary maintenance requirements and the system product and installation warranties.

4 CARPENTRY

4.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

4.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1170.2:2011(AS/NZS)	Structural design actions - Wind actions
1491:1996(AS/NZS)	Finger jointed structural timber
1859.1:2017(AS|NZS)	Reconstituted wood-based panels - Specifications - Part 1: Particleboard
1859.2:2017(AS|NZS)	Reconstituted wood-based panels - Specifications - Part 2: Dry process fibreboard
2270:2006(AS/NZS)	Plywood and blockboard for interior use
2271:2004(AS/NZS)	Plywood and blockboard for exterior use
2295:2006(NZS)	Pliable, permeable building underlays
2588:2018(AS|NZS)	Gypsum plasterboard
2589:2017(AS/NZS)	Gypsum linings - Application and finishing
2904:1995(AS/NZS)	Damp-proof courses and flashings
2908.2:2000(AS/NZS)	Cellulose-cement products - Flat sheets
3601:1973(NZS)	Metric dimensions for timber
3602:2003(NZS)	Timber and wood-based products for use in building
3603:1993(NZS)	Timber Structures Standard
3604:2011(NZS)	Timber-framed buildings
3617:1979(NZS)	Specification for profiles of weatherboards, fascia boards, and flooring
3622:2004(NZS)	Verification of timber properties
3631:1988(NZS)	New Zealand timber grading rules
3640:2003(NZS)	Chemical preservation of round and sawn timber
4200.1:2017(AS|NZS)	Pliable building membranes and underlays - Part 1: Materials
4200.2:1994(AS/NZS)	Pliable building membranes and underlays - Installation requirements
4389:2015(AS/NZS)	Roof safety mesh
4534:2006(AS/NZS)	Zinc and zinc/aluminium-alloy coatings on steel wire
AS/NZS 1080.1:2012	Timber - Methods of test - Method 1: Moisture content
AS/NZS 2269.0:2012	Plywood - Structural - Part 0: Specifications

NASH Standard	Residential and Low-rise Steel Framing - Part 1: Design Criteria
NZBC C/AS2-AS6	Protection from Fire
NZBC E2/AS3	Concrete and concrete masonry buildings
NZBC E2/VM1	External Moisture
NZBC G6	Airborne and Impact Sound
NZMRM Code of Practice	NZ Metal Roof and Wall Cladding Code of Practice - Version 2.2
SNZ HB 3604:2011	Timber-framed buildings - Selected extracts from NZS 3604:2011

4.3 General

This section includes the receiving, stacking and storage of all Carpenter's materials and the fabrication, erection and fixing of all framing, sheathings and finishing timbers, including all work incidental to neatly finishing in other trades and all temporary work and temporary bracing.

The Carpenter shall attend upon all trades, and shall supply and fix all obviously necessary but not specifically mentioned fixings and materials.

4.4 James Hardie Eaves & Soffits

4.4.1 Scope

Supply and install the specified James Hardie products as a fibre-cement sheet lining material to the eaves and soffits identified on the drawings, complete with all accessories. All aspects of this work shall be in complete accordance with James Hardie Eaves And Soffits Installation Manual (check www.jameshardie.co.nz, or call 0800 808 868 for the latest edition) and other relevant product manufacturers' recommendations.

4.4.2 Eaves & Soffit Lining

Hardie™ Flex Eaves Lining - 4.5mm. 4.5mm thick fibre-cement sheet lining with an un-sanded surface finish. The sheets are to be finished with a paint system. Installed in accordance with the James Hardie Eaves And Soffits Installation Manual to the locations shown on the drawings.

4.4.3 Co-operation

Co-ordinate with other trades to ensure that the panels correctly allow for fascia and wall cladding installation and associated flashings etc., and that services penetrations are correctly handled to maintain full weathertightness and sheet integrity.

Ensure that other trades are aware of the James Hardie Safe Working Practices.

4.4.4 Preparation

Check that the timber framing elements are in accordance with NZS 3604, or in accordance with NZS 3603 and AS/NZS 1170 for specific design, and in accordance with James Hardie requirements. The fascia and framing shall be in true alignment, complete and suitable for the sheets, and maximum moisture content as per NZS 3602. Ensure that the framing is true in line with no projections due to

structural and bracing bracketry etc. Ensure that any hold-downs from the roof framing to the wall framing are correctly installed.

Check that the building underlay or rigid air barrier to the wall framing has been installed in full accordance with the manufacturer's requirements and the drawings. Check junctions to all other building elements and ensure that all necessary works have been completed eg. flashings etc that will enable the sheets and all accessories to be installed.

4.4.5 Flexible Sealant

Flexible silicone sealant to be SIKA Silaflex MS. Use to seal the sheets and accessories in accordance with the sealant manufacturer's recommendations and to James Hardie requirements. Ensure sealant compatibility with selected finish.

4.4.6 Workmanship

All installation work shall be carried out by an LBP, or supervised by an LBP, in accordance with James Hardie Eaves And Soffits Installation Manual and other relevant product manufacturers' recommendations.

4.4.7 Delivery & Handling

Carry all sheets on edge. Stack sheets flat on a level platform off the ground ie. use the supplied delivery pallet on level ground (if no pallet then evenly spaced bearers on level ground at 600mm crs maximum). Keep sheets and accessories dry at all times. Avoid damage to sheet edges, ends, and surfaces. Keep uPVC flashings etc. out of direct sunlight, and store all accessories on flat and avoid damage. All installers to be familiar with and comply with the James Hardie Safe Working Practices in the Installation Manual, to use appropriate safety gear, and in particular to be aware to avoid breathing silica dust. Do not use any damaged or blemished sheets or accessories.

4.4.8 Installation

Install the sheets to the framing in accordance with the Installation Manual, complete with all accessories eg. mouldings, sealant, underflashings, etc.

Ensure that all cut edges of panels are primed prior to installation with Dulux 1 Step Prep, Resene Quick Dry, or similar. Ensure that the bottom edge of the fascia forms a drip edge of 15mm minimum to the sheet. Seal around services penetrations to maintain weathertightness and air pressure resistance.

Install James Hardie mould accessories as shown on the drawings.

Install H3.1 finger-jointed pine timber trim, scribers, eaves moulds, etc. to complete the sheet junctions as shown on the drawings.

4.4.9 Fixings

Hardie™ Flex Sheet 4.5mm sheets with galvanised nails in accordance with James Hardie requirements.

4.4.10 Completion

Ensure that the sheets have been fixed correctly, that all joints and accessories have been completed correctly, and that all penetrations have been taped correctly. Check that no damage has occurred to any installed sheet element or associated component, and replace as necessary. Ensure that the sheets are painted within 90 days of the sheet installation, complete with all accessories and flashings. Hand over a copy of the latest edition of the **James Hardie Hardie™ Flex Eaves Lining** Product Warranty to the client. Hand over a copy of the latest James Hardie Eaves and Soffits Installation Manual to the client for their maintenance information.

4.5 Timber Framing

4.5.1 Scope

Supply and install timber framing to the floors, walls, roofs, and other timber framed elements, as identified and detailed on the drawings. All aspects of this work shall be in accordance with NZS 3604, product manufacturers' recommendations, and as shown on the drawings and the specification.

4.5.2 Workmanship

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All work shall be carried out to current best trade practise by experienced and competent tradesmen, familiar with the materials and installation techniques, in accordance with NZS 3604 and as shown on the drawings.

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings prior to installing timber framing.
Co-ordinate with other trades to install timber framing as required.

4.5.3 Timber Framing

4.5.3.1 Timber Grade and Quality

Unless otherwise noted or specified on the drawings or specification, all framing timber shall be minimum structural grade SG 8 Radiata pine in accordance with NZS 3622.
Framing timber shall be seasoned or kiln dried, and be straight and true and free from wind, warp and distortion, and in lengths suitable for the members required, and shall have a moisture content of between 12% and 18% before installation.
Do not used damaged, faulty or defective materials.

4.5.3.2 Timber Treatment

All non-durable timber framing shall be appropriately treated against moisture and/or insect decay by treatment plants with recognised quality assurance systems that are administered by the Timber Preservation Council (NZTPC). Treatment of timber and wood-based building products shall be to the requirements of NZS 3602 as an absolute minimum, and all treated timber shall be identified and marked as required.

Carefully manage treated framing during installation to avoid accidental use of timber with a lower performance or durability treatment than that required or specified.

4.5.3.3 Storage & Handling

Check timber framing upon delivery and reject sub-standard or damaged material.
Store timber framing dry under cover, fillet stacked and well clear of the ground, and protect from damage, moisture, and contamination.
Ensure all appropriate personal protection equipment is worn at all times when handling and cutting treated framing.

4.5.3.4 Framing Installation

All timber framing members, including all dwanging, strutting, blocking, bracing etc, shall be sized, setout, fitted and fixed to the requirements of NZS 3604 and as shown on the drawings to accommodate structural loadings, cladding and lining setout and support, and the installation of other building components, fixtures and fittings.

All framing shall be erected without deviation, true to line, level, angle and plumb, and evenly aligned and square, and within the tolerances allowed in NZS 3604 Table 2.1. Framing members accurately cut, lapped, housed, joined, and seated so as to provide full contact over the bearing surfaces.

Temporarily prop, brace, tie, and secure framing members and elements as required until the framing is complete and self supporting. Leave in place for safety purposes as long as required.

Protect timber framing as required during installation against damage and moisture, and against significant variation of moisture content until ready for lining. Avoid ponding of water around floor plates.

4.5.3.5 Concrete Separation

Separate timber framing with an approved continuous damp proof course when in direct contact with concrete or masonry. Ensure that the DPC material is compatible with the timber treatment.
Free draining separations to external vertical faces shall be 12mm minimum and as noted on the drawings.

4.5.3.6 Timber Re-treatment

All cut or drilled surfaces of H4 and H5 treated timber framing shall be flood coat re-treated, with a suitable product recommended by the original treatment plant, before installation.

4.5.3.7 Edge Notching and Centre Holes

The notching, checking, and boring of framing members shall be in strict accordance with the requirements of NZS 3604.
Avoided checking and cutting where possible and keep to such dimensions so as not to prejudice the purpose for which the member is used. Keep edge notching to a minimum and where possible use centrally bored holes instead.
Concealed services pipes and wiring shall not project beyond the framing face and where possible shall be beyond the lining's fixing reach.

4.5.3.8 Framing Protection

Protect timber framing as required during installation against damage and moisture, and against significant variation of moisture content until ready for lining. Avoid ponding of water around floor plates.

4.5.3.9 Built-up Framing Members

Except for jack studs, bottom plates and top plates, framing members may be substituted with built-up members in accordance with the limitations of NZS 3604 2.4.4.7 with the prior approval of the Architect/Designer only.

4.5.4 Steel Fixings

4.5.4.1 Fastenings and Connectors

Unless otherwise noted or specified, timber framing fastenings and connectors shall be as specified in the relevant fixing schedules of NZS 3604 or have an equivalent capacity as specified therein. Timber framing connectors and fixings shall comply with the product information as required in NZS 3604 2.4.6, and shall be used and installed in accordance with the manufacturer's recommendations. Pre-drill nail holes in split-prone framing as necessary.

4.5.4.2 Durability of Fixings & Fastenings

Unless otherwise noted or specified, the minimum durability of timber framing fixings and fastenings, excluding nails and screws, shall comply with the durability requirements of NZS 3604 Table 4.1.
Galvanised steel fixing components, excluding nails and screws, shall have galvanised coating masses in accordance with NZS 3604 Table 4.2.
Unless noted or specified otherwise, the materials for nails and screws shall be as given in NZS 3604 Table 4.3.
Steel fixings and fastenings in contact with timber treated with copper based timber preservatives (H3.2 or higher) shall be in accordance with NZS 3604 4.4.4.
Stainless steel nails shall be minimum Grade 304 unless otherwise specified or noted.

4.5.4.3 Bolts and Coachscrews

Unless specified or shown otherwise, all bolted and coach screwed connections shall be M12 or M16 in accordance with the relevant fixing requirements given in NZS 3604.
Bolted and coach screwed connections shall have either a 50mm x 3mm square, or a 55mm x 3mm round, washer to each head and nut for M12 and M16 fixings. Washers shall be of the same material and durability as the bolt or coach screw.

4.5.5 Wall Framing

4.5.5.1 Plates

Top and bottom plates shall be to the dimensions and layout shown on the drawings. Unless specified or shown otherwise, top and bottom plates shall be fixed in accordance with NZS 3604 7.5.12 and Tables 8.18 and 8.19, true to line and level or angle.
Joints in top plates shall be made over a stud or over blocking between studs, and all top plate connections shall be in accordance with NZS 3604 8.7.3. Form all holes and edge notches in top and bottom plates in accordance with NZS 3604 8.7.5.

4.5.5.2 Studs

Studs shall be to the dimensions and spacings shown on the drawings, and installed true to line and plumb in both directions between top and bottom plates.
Unless noted otherwise, non-load bearing wall studs shall be to the spacings given in NZS 3604 Table 8.4, stud width as shown on the drawings.
Form all holes and edge notches in studs in accordance with NZS 3604 8.5.1.5. Do not notch, check, cut, or bore holes in the middle third of any trimming stud.
Should the need arise, studs shall be straightened in accordance with NZS 3604 8.5.3 with prior approval from the Architect/Designer only.

Unless noted otherwise, studs in loadbearing walls for 3 kPa floor loads shall be in accordance with NZS 3604 Table 14.10.

4.5.5.3 Lintels

Lintels shall be to the dimensions and locations shown on the drawings, and installed true to line and level, and shall be supported by a 45mm thick doubling stud or jack stud fixed to a trimming stud, and secured against uplift in accordance with NZS 3604 8.6.1.8 as required.
The thickness of a lintel may be made from two or more members, where each member is the length of the lintel, in accordance with NZS 3604 2.4.4.7.

4.5.5.4 Sill & Head Trimmers

Unless specified or shown otherwise, sill and head trimmers to openings shall be the same width as the wall stud and to the thickness given in NZS 3604 Table 8.15, and installed at the required opening height true to line and level, and supported by a 45mm thick doubling stud or jack stud fixed to a trimming stud.

4.5.5.5 Dwangs

Dwangs shall be the same width and thickness as the wall stud, and installed at the centres noted on the drawings, and accurately cut and fixed in place true to line and level and flush with stud edges.
Dwangs fixed in accordance with NZS 3604 Table 8.19.

4.5.5.6 Ribbon Boards

Ribbon boards shall be as dimensioned and located on the drawings, and installed on edge and checked 25mm into studs at the required height, true to line and level, and fixed in place in accordance with NZS 3604 Table 8.19.

4.5.6 Roof Framing

4.5.6.1 Rafters

All rafters (including hip, valley and jack rafters) shall be to the dimensions, spacings, pitch, and layout shown on the drawings.
Rafters shall be aligned and paired at the required spacings to ridge boards, ridge beams, hip rafters and valley rafters, and as shown on the drawings, and installed parallel, true to line, pitch and plane, and fixed in accordance with NZS 3604 Table 10.1.
Any required jointing of rafters shall be made over supports shown on the drawings only.
Unless shown otherwise, rafter seating to top plates, beams, and lintels shall have a minimum bearing

of 32mm without reducing the rafter depth to less than 65mm, or 80%, at the birds mouth.
Extend rafter ends to form eaves as detailed on the drawings and in accordance with NZS 3604 10.2.1.14.
Fly rafters and outriggers installed to form gable verges as detailed on the drawings and in accordance with NZS 10.2.1.15.3

4.5.6.2 Ridge Beams

Ridge beams shall be to the dimensions and locations shown on the drawings, and installed true to line and level.
Unless specified or shown otherwise, ridge beam ends shall be secured by and fixed to wall framing in accordance with NZS 3604 Table 10.2.

4.5.6.3 Roof Trusses

Roof trusses shall be Specific Engineering Design (SED) in accordance with NZBC B1/VM1 and manufactured by an accredited fabricator, and shall comply with all aspects of NZS 3604 10.2.2. Roof trusses shall be fabricated to meet the specific design requirements of the roof including, but not limited to; roof layout, pitch, and details, in accordance with the drawings and specification.
Roof trusses shall be supported and fixed to the truss fabricator's specifications but shall be no less than that required by NZS 3604 Tables 10.14 and 10.15. Roof trusses shall be braced as shown on the drawings and in accordance with NZS 3604 10.3.

4.5.6.4 Roof Bracing

Roof bracing shall be as shown on the drawings and in accordance with NZS 3604 10.3 and 10.4 as necessary.

4.5.7 Ceiling Framing

Ceiling framing shall be to the dimensions, layout, spacings, and details shown on the drawings, and shall be installed true to line, level and plane, and securely fixed in accordance with NZS 3604 Table 13.3.

4.6 Workmanship & Materials

4.6.1 Workmanship

4.6.1.1 Supervision

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner. It is the main contractor's responsibility to ensure that the construction of all structural timber complies in all respects with the drawings and the specification.

All non-restricted building work shall be carried out by or under the direct supervision of competent tradespersons, suitably qualified for the work undertaken, and in accordance with the best and latest trade practice.

4.6.1.2 Timberwork

All timber shall be worked and cut to be true and square and free from wind and warp with all joints matching and mating to a proper contact fit over the full surface of the joint. All connections whether nailed screwed, glued, mortised or dovetailed shall be accurately made and properly executed to provide sound satisfactory connections for the class of work required.

Timber containing unacceptable defect or distortion shall not be cramped to provide mating at connections but shall be discarded and replaced by true defect-free timber before connections are made. Distribute any acceptable defects in timber so as not to impair the strength or the appearance of the finished work. Do not cut studs across the grain to straighten them.

The checking and cutting away of timbers shall be avoided where possible and shall be limited to such dimensions as will not prejudice the purpose for which the timber is used. Observe NZS 3604 restrictions on holing and checking of timber joists and beams. Concealed services pipes and wiring shall not project beyond the framing face and where possible shall be beyond the linings/claddings fixings reach.

Neatly punch exposed nailing to the diameter of the nail head below the surface. Completley remove bruises and tool marks, and replace all split timbers and hammer-marked finishing timbers.

Fit a 3-ply bituminous DPC or a single layer high impact polyethylene DPC at all timber to concrete junctions to provide complete separation. Ensure that the DPC material is compatible with the timber treatment.

Clean out framing voids before fixing sheathings or linings. Ensure framing voids are fully vermin proofed to the exterior. Build in as necessary all required flashings (supplied by others) to windows, doors, roof edges, etc.

4.6.1.3 Window Installation

Prepare window and external door framing openings for joinery installation by neatly cutting the building wrap at 45º into corners, returning turning the wrap through the frame depth and fixing to the inside face.
Over-flash the underlay along the sill with a flexible flashing tape, installed full frame depth and length of the opening, returned minimum 100mm up the jambs, and with minimum 50mm return over the outside edge.
Over-flash the underlay at head/lintel corners with a flexible flashing tape, extending minimum 100mm each way from the corner, full frame depth, and with minimum 50mm return over the outside face.

Install external joinery frames with metal flashings as detailed and/or as required to completely weatherproof all frame-to-cladding junctions.
Unless shown otherwise, head flashings shall be carried minimum 75mm up behind claddings, extended at 15º out over the joinery head or facing board and returned down to cover the joinery or facing board minimum 10mm and finished with a 5mm, 45º 'kick out' drip-edge.
Neatly dress down the head flashings at the ends of the facings - for drained cavity construction, also form up-turned stop-ends in-line with the outside edge of cavity above.

Install metal (as specified) head flashings, fixed over the wall underlay, with the flashing upstand over-flashed minimum 50mm with a flexible flashing tape against the underlay, or with an additional piece of underlay extended over and lapped behind the underlay above, behind the inter-storey flashing or sill flashing above, or to the underside of the eaves.
Unless shown otherwise, sill flashings, where required, shall have a minimum 5º slope, minimum 8mm rear upstand with sealed sloping stop-ends, and be carried down minimum 35mm over the lower cladding and finished with a 5mm, 45º 'kick out' drip-edge.

Take delivery of window and door joinery. Check substrates for correct profile and alignment and that the joinery is fabricated to the correct wall construction set-out and depth. Set shims or pack as necessary to install joinery exactly true and square. Use appropriate separators between aluminium and other materials, and fix securely with due regard for any anticipated movements and for linings, trim, etc.

Install neat sealant beads as detailed or required.

After joinery installation, install closed cell backing rods as required and expanding foam seal the gap between the opening substrate and joinery liners/reveals (all round, from the inside).

On completion ensure that all sashes and doors neatly fit the openings with regular tolerances to all edges, and that all moving components and hardware are correctly adjusted and operating smoothly, without binding, to the required functionality.

4.6.1.4 Joinery Installation

Take delivery of all scheduled joinery items (doors, cabinets, shelves, etc.) and install in the positions shown, accurately aligned, true to level, plumb and square, and securely fastened as noted and in accordance with best trade practice and with due regard for adjacent linings, finishes and trim, and anticipated movements.

Cabinets scribed and/or recessed packers scribed to adjacent surfaces as detailed or directed. Protect all installed Joinery from damage including surface marking and contamination, dirt and dust, and moisture until completion. Do not use Joinery items for working supports or platforms or for storage of materials or tools and equipments.

On completion ensure that joinery item doors and drawers all neatly fit the openings with regular tolerances to all edges, and that all moving components and hardware are correctly adjusted and operating to the required functionality.

4.6.2 Timber

4.6.2.1 Timber Materials

All timber shall be graded in accordance with NZS 3631 - Structural Grade MSG8 or better for all framing timber - (to meet the requirements of Table 2.3 of NZS 3603 for mechanically graded timber), and Dressing Grade for all finishing timber. Timber that is deemed below standard, in the opinion of the Architect/Designer, shall be removed from the site.

All non-durable timber, including components in manufactured items, shall be appropriately treated against moisture and/or insect decay by treatment plants with recognised quality assurance systems that are administered by the Timber Preservation Council (NZTPC). Treatment of timber and wood-based building products shall be to the requirements of NZS 3602 as an absolute minimum, and all treated timber shall be identified and marked as required.
Ensure that similar timbers with different treatment levels are carefully managed during construction to avoid accidental use of an H1 treated item where H3 hazard class treatment is required by the NZS 3602.
Do not use LOSP (light organic solvent-based preservative) treated timber that has not adequately 'flashed-off'.
Ensure that all cut or drilled surfaces of H4 and H5 hazard class treated timbers are flood coat re-treated, with the product recommended by the original treatment plant, before installation.

All timber shall be seasoned or kiln dried, to the stable moisture content, be straight and true and free from wind, warp and distortion, and in lengths suitable for the members required and the location in the finished construction. All framing timber shall have a moisture content between 12% and 18 % before being installed. If the use of inadequately seasoned timber results in damage or opening joints in the finished building the timber shall be replaced. Fixing of internal linings shall be delayed after closing in until the timber framing has dried back below 20% moisture content and to allow for the maximum settling of substrates.

All kiln dried, dressed and/or finishing timbers shall be stacked under cover on delivery to the site, and all timber shall be full to the nominal sizes shown or specified, subject only to normal cutting and dressing tolerances.
All finishing timber shall have machine marks, stains and roughness removed and shall be sanded smooth.

Ensure that enclosed surfaces and ends of paint-finished exterior finishing timbers are fully primed before fixing. If this trade (Carpentry) carries out the priming it shall be to the specification and standard required of the Painter.

Unless specified otherwise, exposed framing timbers shall be unfinished to the exterior, and be fine bandsawn milled, treated with a minimum of discolouration, handled carefully at all times to avoid surface damage, and delivered free of crayon or pencil or other markings. Hazard class treatment markings shall be on the ends, NOT on the faces.

4.6.2.2 Timber Species

Unless noted or specified on the drawings, in the list below, or elsewhere in this specification all timber used shall be Radiata pine.
Other timbers shall be as follows:

- Douglas Fir (*NZ Oregon, Psuedotsuga menziesii*)
- Jarrah Clears (*Eucalyptus marginata*)
- Kwila Clears (*Merbau*)
- Balau (*Shorea spp*)
- Kwila (*Merbau*)
- Cedar Clears (*Western Red Cedar, Thuja plicata*)

- Rimu - (*NZ Red Pine*)
- Vitex Clears - (*Vitex cofassus*)
- Eucalypt Saligna Clears - *(Sydney Blue Gum*)
- Tasmanian Oak - (*Eucalyptus delegatensis / obliqua / regnans*)

Note: the use of alternate grades and varieties to those specified is subject to approval in each instance.

4.6.2.3 Timber Cavity Battens

To wall areas as noted install H3.1 treated ex.50mm x 25mm timber battens to form a drained vertical cavity complying with E2/AS1 in all respects. Ensure that flexible wall underlay and flexible flashing tape are completely and correctly installed before fixing battens in place. Fix the battens with 60mm hot-dip galvanised flat head nails at maximum 400mm centres, ensuring that the batten set-out completely fulfils the cladding's fixing requirements. Install 1:12 sloping horizontal cavity spacers where required to suit claddings, keeping the ends 50mm clear of the vertical battens.

4.6.2.4 Other Materials

Materials shall be delivered to site with the packaging and labelling intact, shall be of the same type, finish or colour to maintain continuity, shall be stored, and conditioned if required, in accordance with manufacturer's recommendations, and shall be protected from damage, contamination, and moisture - as appropriate.
Handle all materials in accordance with best practice and the manufacturer's requirements, and in a manner that prevents damage or deterioration to the material. Do not use damaged or defective materials or products, or products that are beyond their designated shelf life.

4.6.3 Laminated Veneer Lumber

Laminated Veneer Lumber (LVL) shall comply with AS/NZS 4357.0. Each piece of structural LVL shall be branded at least once with the manufacturer's logo and a registered brand or marking that clearly identifies the structural properties that apply to the product and its limitations on end use; all in conjunction with associated published literature.

Structural properties identified in the associated published literature shall be:
- details of marking specific to the product
- veneer details
- physical properties including
  - modulus of elasticity
  - bending stress
  - tension stress parallel to grain
  - compression stress perpendicular to grain
  - compression stress parallel to grain
  - shear stress
- joint group
- density
- dimensional tolerances
- adhesives used
- limitations on end use

The storage and handling of LVL shall comply with Appendix A of AS/NZS 4357.0. In particular:
- LVL should be kept dry during storage and transit
- LVL should be stacked on bearers well clear of the ground and arranged so that their supporting surfaces are in the one plane
- Bearers should be spaced sufficiently close so that LVL spanning between them does not deflect excessively under its own weight.
- Bearers or spacers within a stack should be located near direct vertical alignment
- Care should be taken in lifting and handling LVL in order to avoid mechanical damage
- Wrapping should avoid and prevent entrapment of moisture
- LVL should not be used in high humidity conditions or exposed to the weather.

4.6.4 Proprietary Roof Trusses

Roof trusses shall be of proprietary design, complying with the requirements of NZS 3603, NZS 3604, and AS/NZS 1170, and manufactured by suitably qualified fabricators.

Make allowance for all notching and holing to timber members to accommodate roof bracing etc., in the design of member sections of the roof trusses. Allow for all additional rafters, purlins, fixings and bracing necessary to complete the roof framing system with all accessories and incidental items necessary for proper installation even where not specifically shown on the drawings.
Proprietary roof trusses shall be designed to carry all imposed gravity and lateral loads. Refer to the approved design drawings for truss set-out and specified design loads. Roof trusses are assumed to be generally at 900mm centres spanning clear between walls or roof beams as shown on the drawings. The Main Contractor is responsible for the design of proprietary roof trusses, including their layout and interaction with and dependence on adjoining elements.

Provide all necessary design information and shop drawings for all proprietary roof trusses to be incorporated in the works for review prior to fabrication.
Provide Producer Statements from a Charted Professional Engineer covering the design and construction of the roof trusses. Provide all information required by the Territorial Authority for the purpose of obtaining a Building Consent.

4.6.5 Fixings

4.6.5.1 Nails

Comply with the requirements of NZS 3604 Section 2.4.4 and the Nailing Schedules of NZS 3604 as applicable. Unless noted or specified on the drawings or elsewhere in this specification, all nails fixing exterior timbers shall be Grade 304 or 316 stainless steel. Nails that will be covered with plaster or any similar material shall be hot-dipped galvanised, unless noted or specified otherwise.

Finishing brads to all finishing timbers shall be set out neatly and punched to the diameter of the nail below the surface. Bore slightly undersize holes for nailing that could cause splitting of the timber. Power-driven staples are completely unacceptable in finishing timbers.

4.6.5.2 Screws

Screw fastenings shall be of suitable gauge, head type, thread design, and length to provide secure fastening into the substrate material, and be suitable for the assembly/construction of the fixed

item/element and the substrate material.
Unless noted or specified otherwise, screws exposed to the exterior shall be Grade 304/316 stainless steel or hot-dipped galvanised, and hot-dipped galvanised or similar corrosion resistant for damp situations.
Self-drilling screws shall be in accordance with AS 3566 for fastener type and corrosion resistance class.
Unless noted or specified otherwise, screws fixing hardware or similar shall be of the same material and finish as the hardware. Except where raised head screws are shown or specified, screws shall be countersunk flush or recessed where stopped/filled.

4.6.5.3 Bolts

Where bolts are used they shall be complete with nuts and washers unless specified otherwise. All bolts, nuts and washers shall at least meet the durability requirements of NZS 3604 Table 4.1. Where a higher durability material is specified on the drawings, the higher durability material shall be used.
The diameter of a hole for a bolt shall not be less than the bolt diameter nor exceed it by 1.5mm.

For the following bolt diameters use washer sizes as below unless noted otherwise on the drawings:
- up to M8: 25x 25 x 1.5mm;
- up to M12: 50 x 50 x 3mm;
- up to M20: 65 x 65 x 5mm;
- up to M20: 75 x 75 x 6mm.

Round washers may be used proving they are of a thickness and area not less than those specified above.

Subfloor framing - unless noted otherwise on the drawings, cast-in holding down bolts for subfloor framing fixed to concrete foundation walls shall be M12 Grade 304 stainless steel, embedded minimum 150mm into concrete, to the spacings required by NZS 3604, and located centrally on the timber.
Bottom plates - unless noted otherwise on the drawings, cast-in holding down bolts for bottom plates fixed to a concrete slab shall be M12 galvanised, embedded minimum 120mm into concrete, to the spacings required by NZS 3604, and located centrally on the timber.
Framing - timber/timber and timber/steel - Unless noted otherwise on the drawings, M16, hexagonal head mild steel and with 50 x 50 x 3mm washers.
Timber/concrete (dry situations) - Unless noted otherwise on the drawings, Ramset Trubolts, T12140 at maximum 900mm centres - for damp or exterior situations use stainless steel Trubolts.
Bolts shall be tightened until the washer just indents the timber surface. Exposed bolts shall be re-tightened just prior to Practical Completion to remove any slack consequent on timber shrinkage.
Allow to countersink bolt heads and nuts as necessary to clear linings.

4.6.5.4 Framing Hardware

Proprietary timber framing hardware and fixings, including multigrips, joist shoes, Z nails, gang nails and similar hardware, may be used where specifically approved, or where required on the drawings or by NZS 3604 schedules, in accordance with the manufacturer's requirements.
Proprietary timber framing structural brackets and ties, including post and bearer brackets, beam supports, angle brackets, tie cleats and similar hardware, shall be as noted on the drawings and

installed in accordance with the manufacturer's requirements.
Refer to Metalwork or Structural Steel section of this specification for specific design engineered fabricated steel components that connect structural timber framing.

4.6.5.5 Powder Fastening Systems

Powder powered fasteners are not permitted for fastening structural timber framing unless specifically noted on the drawings. All applications are subject to specific approval.

4.6.5.6 Adhesives

Aliphatic PVA for dry timber applications - all other adhesives for timber jointing are subject to specific approval or as specified. Check surfaces are in appropriate condition to receive adhesive, and that adhesives are used strictly in accordance with the manufacturer's instructions. Clamp adhesive-jointed timber connections and check alignment of members before the adhesive has set.

4.6.6 Flashings

Flashing materials shall be in accordance with the requirements of NZBC E2/AS1 Sections 2.2 Materials, 4.0 Flashings, Table C.1.1.1B: Compatibility of materials in contact , and Table C.1.1.1C: Compatibility of materials subject to run-off, and as noted on the drawings.
All flashings around windows, doors and other openings and apertures, at internal and external corners, inter-storey junctions, soffit junctions, and at junctions with other building elements and cladding systems, etc., shall all be carefully constructed, fixed and finished to the details shown on the drawings.

4.6.7 Sealants

4.6.7.1 Sealants

For critical joints such as primary water/weatherproofing seals, precast panels primary seals, structural floor slab control joints, structural glazing, immersion or hydrostatic pressure seals, etc., either use the sealant noted on the drawings or obtain a reputable sealant manufacturer's recommendation for the precise situation, and submit the manufacturer's specifications covering all relevant criteria and characteristics of the proposed sealant, primers, joint surfaces preparation, etc. to the Architect/Designer for review and confirmation to proceed.
If so requested, additionally submit a sample of the proposed sealant made up into a demonstration joint, incorporating the same materials, preparation, finish tooling, etc. After confirmation to proceed with the proposed sealant install a sample joint to approval, length approximately 2% of the overall length of the joints required, with a minimum length of two metres; when accepted this joint becomes the quality control sample for all subsequent similar joints.

For less critical joints such as those in covered or protected situations, and bathroom and kitchen ceramics and sanitaryware etc., either use the sealant noted on the drawings or select the sealant from a reputable manufacturer's range for the substrate materials involved, with due regard for the flexibility required, acid or neutral curing, mould resistance, paintability or clear or standard colours, slumping characteristics, temperature range expected, etc. - silicone, polymer or polyurethane sealants are anticipated.
For all simple gap-filling and draught sealing situations, either use the sealant noted on the drawings or select from a reputable manufacturer's range for a paintable acrylic sealant with good adhesion

characteristics for the substrates involved - pay particularly care in the sealant selection where bare metal, polycarbonate, polystyrene or similar substrates or where bituminous-based membranes are adjacent or where exposure to solvents is possible.

All joint surfaces preparation and priming and all sealant application work shall be exactly in accordance with the sealant manufacturer's recommendations, and carried out by competent and experienced applicators familiar with the materials and techniques required.
Ensure that the sealant is being used within the manufacturer's stated design parameters, particularly with regard joint design and anticipated cyclic movement.
Check that the joint faces are sound, completely dry, and frost free, clean and free of dirt, rust, oil, grease, laitance, etc., and they are primed to suit the surface porosity - particularly for critical locations.
Insert a polyethylene tape slip layer at the back of the joint or a closed cell polyethylene PEF backer rod where required and to the sealant manufacturer's recommendations. Mask off joint edges where a clean straight finish line is required.
Check the toxicity of the selected sealant and handle it appropriately. Check that the temperature during sealant installation is within the manufacturer's guidelines.
Apply the sealant and tool the filled joint's surface smooth and even, utilising a lubricant as necessary and strictly within the manufacturer's guidelines.
Remove any masking tape immediately after tooling, clean up all adjacent surfaces using the recommended cleaning agents as required, and protect the finished joint until the sealant has properly cured.

4.6.8 Interior Finishing Trim

All interior finishing trim shall be cut to the exact dimensions and fine sanded smooth, and with lightly sanded arrisses, and all fixed with plated finishing pins. Machine staple fixing is NOT acceptable.
Note that even traces of planer marks are unacceptable on architraves. Margins between interior trim and other elements shall be exactly even, and all mitres shall be exact and tight.

4.6.9 Garage Door

Garage door(s) as shown and noted on the drawings, installed complete.

4.6.10 Sundry Items

Supply and install, complete with all normal incidentals, and in total compliance with the item manufacturer's recommendations and instructions and with all of the appropriate preceding clauses:

Wardrobe rails, shelves to wardrobes, linen cupboards, etc., as shown and noted on the drawings.

Supply and install the toughened glass shower screens to the shower room and/or bathroom, all as detailed and noted on the drawings.

Supply and install proprietary skylights and or daylighting systems, as specified and/or scheduled, to the locations and details shown on the drawings. Installation shall be exactly in accordance with the manufacturer's requirements and as shown on the drawings.
Skylight penetrations in the roof shall be carefully formed, accurately sized and trimmed, with the

roof underlay neatly cut, folded and dressed, and the roof cladding fully supported, fixed and correctly flashed around the skylight in accordance with the roof cladding manufacturer's requirements.
Form any required upstand to the dimensions as detailed, and finish and flash the roof cladding and underlay around the upstand to the details shown on the drawings.
Form and trim ceiling openings, and line and finish the skylight void sides to the required opening size and as detailed. Reinstate any roof/ceiling insulation around the installed opening without voids or gaps.

4.7 Underlay, Foil & DPC

4.7.1 Scope

Supply and install Underlays, Foil and DPC materials, as specified herein, to the locations identified on the drawings, complete with all accessories required for proper installation and performance. All aspects of this work shall be in accordance with the product manufacturer's technical literature and installation requirements, other relevant product manufacturers' recommendations, and as shown on the design drawings.

This specification should be read in conjunction with other relevant specification sections as they are interrelated.

The following is a list and general description of the extent of the Underlays, Foil and DPC works, which are more specifically defined in the contract documents, required for the completion of the contract works:

4.7.2 Requirements

4.7.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

4.7.2.2 Inspections

Inspections shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

4.7.2.3 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades as required to install underlays, foils and DPC.

4.7.2.4 Workmanship

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All installation work shall be carried out by experienced and competent tradespersons, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements.

All cutting, joining, fixing and sealing techniques shall be exactly as recommended by the manufacturer, and carried out with the use of suitable tools and equipment appropriate for the application. All work shall be such as to leave a neat, efficient, and weathertight installation.

4.7.2.5 Delivery & Handling

Inspect materials for damage and defects upon delivery; reject any damaged or defective products, and immediately contact the supplier for replacement. Do not used damaged or defective products, or products that are beyond their designated shelf life.

Store underlay rolls on end, under cover in a clean, dry environment, in accordance with the manufacturer's recommendations. Keep stored products dry, out of direct sunlight, and protected from damage, moisture and contamination at all times.

Handle products in accordance with the manufacturer's requirements, and in a manner that prevents damage to the product and does not reduce its performance.

Installers shall be familiar with and comply with the manufacturer's safe handling requirements and precautions for use, and shall use appropriate safety gear when handling materials.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including the Best practice guidelines for working on roofs and the General risk and workplace management - part 1.

4.7.2.6 Completion

Check underlay, flashing tape, etc., have been installed correctly, and that all edges, joins and ends are correctly finished prior to closing off with wall/roof cladding.

Check for damage and defective work - replace and/or repair as necessary to the required standard in accordance with the manufacturer's requirements.

Leave all of this work complete, free of damage and defects, and to the standard required for the installation of subsequent cladding and/or roofing, and in accordance with all warranty requirements.

Remove all associated rubbish and excess material from the site.

4.7.3 Roof Underlay

4.7.3.1 Self-Supporting Synthetic Roof Underlay - Fire Retardant

Self-Supporting Synthetic Roof Underlay - Fire Retardant. NZS 2295 Type R4 synthetic. Kraft A proprietary, self-supporting, breathable, absorbent, fire-retardant, synthetic roof underlay with a Flammability Index (FI) of 5 or less when tested to NZS/AS 1530: Part 2. Installed as a roof underlay in accordance with the manufacturer's requirements, AS/NZS 2295:2006 and NZBC E2/AS1. Maximum 1200mm unsupported span. When support spans are greater than 1200mm and / or, the roof pitch is less than 10 degrees, the roof underlay must be supported with galvanised wire netting or safety mesh (as specified). The installation of roof underlay must be considered as part of the overlaying cladding system, not in isolation.

Brand:
Material:
Nominal Weight (g/m²):
Roll Width:
Installed Location:
Support material:

4.7.3.2 Self-Supporting Synthetic Roof Underlay - Non-Fire Retardant

Self-Supporting Synthetic Roof Underlay - Non-Fire Retardant. NZS 2295 Type R4 synthetic. A proprietary, self-supporting, breathable, absorbent, synthetic roof underlay (non-fire retardant) complying with the requirements of NZBC E2/AS1 and AS/NZS 2295:2006.

Installed as a roof underlay, where fire retardancy is not required, in accordance with the manufacturer's requirements and NZBC E2/AS1. Maximum 1200mm unsupported span. When support spans are greater than 1200mm, and / or, the roof is less than 10 degrees, the roof underlay must be supported with galvanised wire netting or safety mesh (as specified). The installation of roof underlay must be considered as part of the overlaying cladding system, not in isolation.
Brand:
Material:
Nominal Weight (g/m²):
Roll Width:
Installed Location:
Support material:

4.7.4 Preparation

4.7.4.1 Roof Structure Check - Roof Underlay

Roof Structure - prior to roofing underlay installation check all aspects of preparatory works, including but not limited to:
- Check that the supporting purlins or battens are set-out to the required set-out and spacings, are straight and true to line and plane, and are securely fixed.
- Check that all barge and fascia boards have been installed to the correct line and plane with all edge blocking complete and secure.
- Check that valley gutter and hidden gutter framing is to the required dimensions with solid backing

supports securely fixed, true to line and plane.
- Check that internal gutter membrane linings are complete, and dressed back and adhered to a solid substrate along the roof edge as shown on the approved drawings.
- Check that all trimming for roof penetrations, all roof/wall junction blocking, and all necessary work by other trades is complete.
- Check that solid sarking required for fully-supported roofing is complete and securely fixed in accordance with the approved drawings.
- Check that any required anti-ponding boards for masonry tiled roofs have been correctly installed to a minimum 5° (1:12) fall to the eaves gutter.

4.7.5 Installation - Roof Underlay

4.7.5.1 Self-Supporting Roof Underlay - profiled metal roof

Install self-supporting roof underlay in accordance with the manufacturer's requirements, to the locations and details shown on the design drawings.

Roof Pitches above 10º:
Unless otherwise specified on the design drawings, lay roof underlay horizontal or vertical to the roof slope, starting from the gutter/lowest point up to the ridge/highest point, overhanging fascia boards 20-25mm, and with minimum 150mm side-laps and end-laps, and lapped away from the prevailing wind, and sufficiently tensioned to prevent ponding of condensation. All end-laps must be made over solid framing. Individual lengths shall not exceed the maximum run length permitted by NZS 2295.

Roof Pitches below 10°:
- Unless otherwise specified on the design drawings, lay roof underlay horizontal to the roof slope, starting from the gutter/lowest point up to the ridge/highest point, overhanging fascia boards 20-25mm, with minimum 150mm side-laps and end-laps, lapped away from the prevailing wind, and sufficiently tensioned to prevent ponding of condensation. All end-laps must be made over solid framing. Individual lengths shall not exceed the maximum run length permitted by NZS 2295.

Fix roof underlay at maximum 300mm centres across the width of the underlay and capturing all edges using 8mm stainless steel staples, or 20mm large-head galvanised clouts, or proprietary underlay fasteners, or self-drilling wafer head screws.

Finish roof underlay along roof edges and junctions, valley gutters, and at the ridge as shown on the drawings. Extend the underlay over ridges by at least 150mm.

Carefully cut roof underlay at openings and penetrations, at 45º angle away from each corner, and lap-tape closed to framed up-stands, ducts and other services penetrating the underlay, in accordance with the manufacturer's requirements and as detailed.

Flue penetrations in the roof must have a minimum distance of 50mm from the outer liner to the underlay.

4.8 GIB® Plasterboard Linings

4.8.1 Scope

Supply and install GIB® Plasterboard Linings specified herein, as sheet lining materials to the walls, ceilings and other elements identified on the drawings, complete with all accessories required for proper installation, finishing and performance. All aspects of this work shall be in complete accordance with the current GIB® Site Guide and relevant GIB® Systems literature (check www.gib.co.nz, or call 0800 100 442 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for GIB® Plasterboard Linings, GIB® Systems or GIB® System components and accessories.

This specification must be read in conjunction with relevant GIB® Systems specifications - GIB® EzyBrace® Systems, GIB® Fire Rated Systems, GIB® Noise Control Systems, GIB® Aqualine® Wet Area Systems, GIB® X-Block® Systems, GIB® Quietline®, GIB® Intertenancy Barrier System, and GIB® Rondo® Metal Batten Systems - and other specifications sections, as they are interrelated. .

4.8.2 Requirements

4.8.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

4.8.2.2 Warranty

GIB® Product & System Warranty:

GIB Systems Durability.
The following systems have, unless stated otherwise in GIB® technical literature, a serviceability life in excess of that stated and satisfy the requirements of NZBC Clause B2 Durability:
15 Years:
- GIB Aqualine® Wet Area Systems.

50 Years:
- GIB® Fire Rated Systems
- GIB EzyBrace® Systems
- GIB X-Block® Systems
- GIB Noise Control® Systems.

Provide the GIB® Product & System Warranty on the manufacturer's standard warranty form.
Commence the warranty from the date of practical completion of the contract works.

Include with the warranty: a copy of the completed GIB® Installation Sign-Off sheet, and the GIB® Plasterboard Lining Systems Care and Maintenance bulletin.

4.8.2.3 Quality Assurance

Ensure that the installation and finishing of GIB® Plasterboard Linings and associated GIB® Systems comply in all respects with the approved design drawings and specifications, and Building Consent.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

4.8.2.4 Inspection & Acceptance of GIB® Plasterboard Linings

Carry out all necessary pre-installation, installation and finishing inspections of GIB® Plasterboard Linings for each area of work in accordance with the requirements of the GIB® Site Guide and associated industry Code of Practice (AWCI) recommendations.

Complete the GIB® Site Guide Pre-Installation Checklist prior to installing GIB® plasterboard linings, and relevant GIB® Performance Systems Installation Checklists.

Complete the GIB® Interior Plasterer/Stopper Installation Sign-Off Certificate upon completion and before handover for subsequent decoration.

4.8.2.5 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected GIB® Plasterboard Linings and GIB® Systems materials and work shall be repaired and/or replaced to the satisfaction of the Architect/Designer, without delay and at no additional cost to the Principal.

4.8.2.6 Substitution of GIB® Plasterboard Linings

GIB® plasterboard linings shall be as specified herein and as indicated on the approved drawings. The substitution of GIB® branded plasterboard linings and GIB® System components for alternative brands is not permitted under any circumstances.

The substitution of a specified GIB® plasterboard lining for an alternative GIB® plasterboard lining by the Contractor shall be in strict accordance with the requirements of the GIB® Site Guide: 2.3 - Board Substitution Options, and relevant GIB® Systems literature. Such substitutions shall only be permitted with the Architect's/Designer's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative GIB® Plasterboard Linings to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

4.8.3 Performance

4.8.3.1 Limitations of GIB® Plasterboard

GIB® plasterboard products must NOT be:
- used in external situations, or
- exposed to water or be installed in situations where extended exposure to humidity above 90% RH can reasonably be expected, or
- exposed to temperatures in excess of 52°C for prolonged periods.

4.8.4 Components & Accessories

4.8.4.1 Metal Ceiling Battens

Metal Ceiling Battens - GIB® Rondo® Metal Batten Systems. Installed in accordance with the manufacturer's requirements to the layout and details shown on the approved drawings. Refer to the GIB® Site Guide, and to separate specification GIB® Rondo® Metal Batten Systems.

4.8.4.2 Plasterboard Fasteners

GIB® Plasterboard Fasteners. Fasteners for fixing GIB® Plasterboard Linings shall be selected and used according to best fixing practices and the GIB® Site Guide and relevant GIB® Systems literature. Fastener heads shall be set slightly below the plasterboard sheet surface without breaking the paper facing.

Screw Fixing to Timber Framing:
- GIB® Grabber® High Thread Drywall Screws: A coarse high-thread screw for fixing into timber with superior holding power and ease of penetration.
- GIB® Grabber® Self Tapping Drywall Screws: A fine self-tapping thread, needle point screw, suitable for fixing to timber and light gauge steel framing.
- GIB® Grabber® Dual Thread Drywall Screws: A dual coarse/fine threaded, needle point screw, as a component of the GIBFix® Framing System and for fixing to timber framing.

Nail Fixing to Timber Framing:
- GIB Nail: Passivated coated, annular grooved, bugle head drywall nails with chequer-keyed head.

Screw Fixing to Light Steel Framing:
- GIB® Grabber® Self Tapping Drywall Screws: A fine self-tapping thread needle point screw, suitable for fixing to light gauge (0.45-0.95mm) steel framing.
- GIB® Grabber® Dual Thread Drywall Screws: A dual coarse/fine threaded, needle point screw, suitable for fixing to light gauge (0.45-0.95mm) steel framing.

4.8.4.3 Adhesives

GIB® Adhesives. In addition to GIB® plasterboard fasteners, fix GIB® Plasterboard Linings using GIB® adhesives in accordance with the requirements of the GIB® Site Guide and GIB® System literature.

GIB® Adhesives:
- GIBFix® One: An acrylic based plasterboard adhesive with ultra low VOC, suitable for use on timber and metal substrates, including all treated timber. Minimum application temperature - 10°C.
- GIBFix® All-Bond: A solvent based plasterboard adhesive, suitable for use on timber and metal substrates, including all treated timber. Do not use on polystyrene surfaces.

4.8.4.4 Metal Trims

GIB® Metal Trims. Perforated metal corner beads and edge trim made from galvanised steel. Installed in accordance with the requirements of the GIB® Site Guide and GIB® Systems literature.

GIB® Metal Trim Profiles:
- External 90° Perforated Corner Trim (P01): GIB® Slim Angle - Standard. Available in

2.4/2.7/3.0/3.6m lengths.
- External 135° Perforated Corner Trim (P01A): GIB® Slim Angle - Off Angle. Available in 2.4/2.7/3.0m lengths.
- Perforated Curvable Corner Edge trim (P10): GIB® Slim Arch Bead. Available in 2.4/3.0m lengths.
- L-Trim for Stopped End Trim: Rondo® Stopping Angle. Profiles available for 10/13/16mm thick plasterboard. Available in 3.0m lengths.
- End Cap Bead - stopped: Rondo® Stopping Bead. Profiles available for 10/13mm thick plasterboard. Available in 2.4/3.0m lengths.
- Reveal or Z-trim: Rondo® Shadowline Stopping Bead. Profile available for 10mm thick plasterboard. Available in 3.0m lengths.
- End Cap Bead - un-stopped (P50): Rondo® Casing Bead. Profiles available for 10/13mm thick plasterboard. Available in 2.4/3.0m lengths.

4.8.4.5 Paper Faced Metal Trims

GIB® Goldline® Paper Faced Metal Trims. Paper-faced metal corner beads and edge trim made with a patented, high quality paper laminated to galvanised steel forms. Paper faced metal trims shall be embedded in jointing compound - do not mechanically fasten paper faced trims. Installed in accordance with the requirements of the GIB® Site Guide and GIB® Systems literature.

GIB® Goldline® Profiles:
- External 90° Corner Trim (G1-W): profile available in 2.4/2.7/3.0m lengths.
- External 135° Corner Trim (G1-O): profile available in 2.4m lengths.
- Internal 90° Corner Trim (G2): profile available in 2.4/2.7/3.0m lengths.
- Internal 135° Corner Trim (G2-O): profile available in 2.4m lengths.
- Bullnose External 90° Corner Trim (G1-B): profile available in 2.4/2.7/3.0m lengths.
- Reveals (GR): profiles available for 10mm thick and 13mm thick plasterboard.
- L-Trims (G4): profiles available for 10mm thick and 13mm thick plasterboard.

4.8.4.6 Proprietary Control Joints

GIB® Plasterboard Control Joints. Form movement control joints in plasterboard lined walls and ceilings to the locations and details shown on the approved drawings. Where not indicated on the drawings, movement joints shall be positioned in accordance with the requirements and recommendations given in the GIB® Site Guide and relevant GIB® Systems literature.

When not specified on the drawings, select the most suitable GIB® Plasterboard Control Joint according to location, application, durability, and finish detail required.

GIB® Plasterboard Control Joints:
- Metal Control Joint: GIB® Rondo® P35 Control Joint, with perforated metal flanges. 18mm wide. Available in 3.0m lengths.
- Plastic Smooth Control Joint: GIB® Plastic Smooth Control Joint, with flush face. 10mm wide. Available in 3.0m lengths.
- Plastic W-Profile Control Joint: GIB® Plastic W-Profile Control Joint, with tear-away beads. 14mm wide. Available in 3.0m lengths.

4.8.4.7 Joint & Finishing Compounds

GIB® Compounds. Use the most suitable GIB® Compounds to joint and finish GIB® Plasterboard Linings according to the plasterboard type, location, application, durability, and quality of finish required. GIB® Compounds shall be applied and finished in accordance with the manufacturer's requirements to the specified finish level, and used in conjunction with GIB® Paper Joint Tape and GIB® Plasterboard Trims.

GIB® Compounds:
- GIB TradeSet®: Setting type compound. Suitable for Tape Coat, 2nd Coat. Easy to scrape. 20/45/90/150 minute working/set times.
- GIB MaxSet®: Setting type compound. Suitable for Tape Coat, 2nd Coat. Scrape while 'green'. 90 minute working/set time.
- GIB Lite Blue®: Setting type compound. Suitable for 2nd Coat. Easy sanding. 90 minute working/set time.
- GIB Trade Finish® Heavy Weight: Air drying ready-mix type compound. Suitable for Finishing Coat. Moderate sanding.
- GIB Trade Finish® Multi: Air drying ready-mix type compound. Suitable for Tape Coat, 2nd Coat; Finishing Coat. Easy sanding.
- GIB Trade Finish® Lite: Air drying ready-mix type compound. Suitable for Finishing Coat. Very easy sanding.
- GIB Promix® Lite: Air drying ready-mix type compound. Suitable for Finishing Coat. Very easy sanding.
- GIB® U-Mix: Air drying powder-mix type compound. Suitable for Finishing Coat. Easy Sanding.
- GIB Plus 4®: Air drying ready-mix type compound. Suitable for Tape Coat, 2nd Coat, Finishing Coat. Very easy sanding.
- GIB Promix® All Purpose: Air drying ready-mix type compound. Suitable for Tape Coat, 2nd Coat, Finishing Coat. Moderate sanding.
- GIB-Cove® Bond: Setting type compound. Suitable for bonding GIB-Cove® cornice, back-blocking plasterboard linings, and direct-bonding plasterboard to concrete and masonry walls. Hard to scrape. 45/90 minute working/set times.
- GIB X-Block® Jointing Compound: Used in conjunction with GIB X-Block® plasterboard wall and ceiling linings in accordance with the GIB X-Block® Radiation Shielding publication.

4.8.4.8 Joint Tape

GIB® Paper Joint Tape. A 50mm wide, spark perforated paper joint tape used to strengthen joints between plasterboard sheets. Centre-creased for internal and external corner applications. Recommended for jointing GIB® plasterboard wall and ceiling linings in accordance with the GIB® Site Guide and GIB Systems literature.

4.8.4.9 Wet Area Sealant

Wet Area Sealant. A mould resistant, flexible, neutral curing silicone sealant with strong adhesion, suitable for wet area applications and where there is high humidity, including bathrooms, toilets, showers, wash-down areas, kitchens, laundries.

Applied in accordance with the sealant manufacturer's instructions, as required by the GIB® Site Guide and GIB® System literature. Sealant joints shall be in accordance with the sealant manufacturer's joint design width-to-depth ratio.

Manufacturer & Brand:

4.8.4.10 Gap Filler

GIB® Gapfiller. A general purpose, gun applied, one-part water based, paintable acrylic gap filler. Provides excellent adhesion for gaps and cracks and other low movement joints. Used in strict in accordance with the manufacturer's requirements. Refer to the GIB® Site Guide.

4.8.5 Level of Finish

4.8.5.1 Level of Finish

To the areas noted as a specific Level of Finish (3-5) on the drawings, additionally comply with all relevant aspects of the GIB® Site Guide and AS/NZS 2589, complete with all system accessories, and other relevant product manufacturers' recommendations.

NOTE: Unless stated otherwise, Level 4 is the default Level of Finish.

4.8.5.2 Acceptance of Levels of Finish

Carry out all necessary inspections and assessments of completed plasterboard jointing and finishing prior to hand-over for subsequent decoration.

Do not apply surface sealers and decorative treatments until written agreement between the Contractor and Painter/Decorator is given confirming the specified Finish Levels have been achieved and the plasterboard linings are ready for subsequent sealing and decoration.

4.8.6 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.
Co-operate with the Decorator to ensure that the specified Finish Levels for plasterboard jointing and finishing is achieved before decorating commences.

Coordinate with other trades to install GIB® Plasterboard Linings as required, and to ensure that:
- appropriate tolerances and clearances allow for adjacent internal linings, fixtures, fittings, services, etc; and
- the linings correctly allow for proper door and window installation; and
- penetrations for building services are correctly handled to maintain sheet integrity and system performance.

4.8.7 Workmanship

Where required by the NZ Building Act 2004, it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

Installation and finishing work of GIB® Plasterboard Linings shall be carried out by qualified and experienced tradespersons, familiar with the specified materials and installation and finishing techniques, in accordance with the GIB® Site Guide and the relevant GIB® product technical literature, and to fully comply with all warranty requirements. Submit evidence of experience on request, e.g. National Certificate of Interior Systems, or Certified Business Member of AWCINZ.

GIB® Plasterboard Linings shall be jointed and finished to the specified Finish Levels in accordance with AS/NZS 2589 and GIB® Site Guide. Make all necessary arrangements for the quality assessment of plasterboard jointing and finishing Finish Levels prior to commencing decorating.

All cutting, fixing, jointing, finishing and sealing techniques shall be exactly as recommended by the manufacturer. All work shall be such as to leave a neat, efficient and robust installation, to the required standard and free from damage and defects.

Protect surrounding surfaces and areas from jointing compound splashes and sanding dust.

4.8.8 Delivery & Handling

Store GIB® Plasterboard Linings indoors, in neat, flat stacks off the floor, in dry conditions and without any sagging or distortion, in accordance with the GIB® Site Guide. Keep plasterboard linings, compounds and accessories dry, out of direct sunlight, and protected from damage, moisture and contamination at all times.

Do not use damaged or defective materials and products, or products that are beyond the designated shelf life.

Should a problem be encountered with any GIB® product during installation or delivery, immediately contact the GIB® Helpline on 0800 100 442. Do not continue to use the product that is not performing to specification or expectation. Keep samples of the product in question and where possible, document batch numbers and/or manufacturing dates.

Handle all products and materials in accordance with the manufacturer's requirements and relevant Product Data Sheets and GIB® Site Guide, and in a manner that prevents damage. Carry plasterboard sheets on edge, and avoid damage to sheet edges, ends, and surfaces.

Installers shall be familiar with and comply with the requirements of the GIB® Site Guide precautions for use, and use appropriate safety gear when handling materials.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice.

4.8.9 Preparation

4.8.9.1 General

All framing and substrates shall be complete and ready for GIB® Plasterboard Lining installation.

Timber framing shall comply with NZS 3604, or with NZS 3603 and AS/NZS 1170 for specific design, and have a maximum moisture content 18% at the time of plasterboard lining installation.

Light structural steel framing shall comply with the requirements of AS/NZS 4600 or the NASH Standard for Residential and Low-rise Steel Framing, Part 1: Design Criteria. All light structural steel framing members shall satisfy the requirements of AS/NZS 1170. Comply with the steel framing fabricator's specifications and requirements for plasterboard installation.

Steel stud partitioning shall comply with AS 1397 and as specified and shown on the drawings. Comply with the manufacturer's specifications and requirements for plasterboard installation.

Concrete substrates shall comply with the CCANZ CP 01:2011 or with NZS 3109. New concrete must have aged for a minimum of 28 days. Ensure that concrete surfaces are within the tolerances specified. For of direct bonded plasterboard linings, concrete substrates must below 75% relative humidity prior to installation.

Concrete masonry substrates shall comply with NZS 4229, or with NZS 4230 and AS/NZS 1170 for specific design. For of direct bonded plasterboard linings, concrete masonry substrates must below 75% relative humidity prior to installation.

Carry out all necessary moisture readings. Do not commence installation until the moisture readings are below the required level.

Carry out all necessary substrate inspections and preparatory work in accordance with the manufacturer's recommendations and the GIB® Site Guide prior to installation. Complete and sign the GIB® Site Guide Pre-Installation Checklist.

Check that the building envelope has been finished at all penetrations including doors, windows, services, etc., and the building is weathertight.

Check junctions to all other building elements and ensure that all necessary works have been completed, including cavity insulation.

Check that all fixtures, fittings and built-in items are correctly installed, and that all framing and substrate edges are completed as detailed.

Confirm the location and details of movement control joints, as indicated on the drawings, prior to installation.

Ensure all pre-wiring and service piping is installed and complete.

Check that any required cavity insulation has been installed correctly and its bulk thickness does not exceed the framing thickness.

Remove all debris and rubbish from framing voids prior to installing linings.

The commencement of work on each section/area shall be deemed to indicate full acceptance by the installer that all preparatory works by other trades is complete.

4.8.9.2 Framing Check

Framing - check all aspects of preparatory works, including but not limited to:
- Check that the framing is straight and true to line, and is plumb/level and correctly aligned.
- Check that the framing is within the required deviation tolerances defined in AS/NZS 2589 according to the specified Finish Level.
- Check that vertical and horizontal framing members are at the spacings shown on the drawings, and that any required battens or furring channels are installed to the required layout.
- Check that the framing has no projections due to structural and bracing bracketry, etc. Ensure that framing brackets, plates, braces, hold-downs, etc., are correctly installed.

4.8.10 Installation

4.8.10.1 General

Install GIB® Plasterboard Linings and accessories in accordance with the requirements of the GIB® Site Guide and product technical literature and associated fixing schedules, to the locations and details shown on the drawings. For GIB® Performance Systems, refer to the relevant GIB® system specification.

Prior to installation, confirm:
- The locations and construction details of all movement control joints;
- The locations and installation details of all building services items within framed structures;
- The specified GIB® plasterboard installation and fixing requirements;
- The specified Finish Level(s) for the plasterboard linings.
- Subsequent surface treatments and finishes applied to GIB® plasterboard.

4.8.10.2 Standard Ceiling Fixing - Metal Ceiling Battens

GIB® Plasterboard Ceiling Linings - Standard Ceiling Fixing with Metal Ceiling Battens. Metal ceiling battens shall be from the GIB® Rondo® Metal Batten Systems - refer to separate specification GIB® Rondo® Metal Batten Systems.

Unless independently supported, uniformly distributed loads (fixtures and fittings and/or overlaid insulation) supported by GIB® plasterboard ceiling linings shall not exceed 3.0 kg/m².

Metal ceiling batten spacings shall be shall be as given in the GIB® Site Guide according to the specified plasterboard thickness - 600mm for 13mm or greater thickness, 450mm for 10mm thickness. Ceiling battens shall all run in the same direction within the ceiling area. In no case shall ceiling battens be continuous over movement control joints in the structure.

Install GIB® Plasterboard sheets right angles to ceiling battens, with sheet end-joints staggered minimum 600mm and located off battens and back-blocked. Fully support sheets during positioning and fixing - for ceiling installations, the use of a mechanical lifting machine is recommended.

Plasterboard sheets shall be fixed to ceiling battens in conjunction with GIBFix® adhesive applied at maximum at 200mm centres. Do not apply adhesive at sheet edges or within 200mm of fasteners. Firmly press the plasterboard where adhesive has been applied to ensure full contact.

Fix sheets to timber ceiling battens with GIB® Grabber® Self Tapping Screws in accordance with GIB® Site Guide fastener schedule according to the plasterboard thickness. Position fasteners no closer than 12mm from a tapered edge or 18mm from a cut sheet edge.

Install all necessary paper-faced metal beads, casing beads, shadow and reveal beads and other edge trims to plasterboard corners and edges as necessary and as detailed on the drawings.

Form movement control joints to the locations and details shown on the approved drawings. Where not indicated on the drawings, movement joints shall be positioned at maximum 12m intervals in both directions on any single ceiling, and where there is a change in ceiling lining material, and shall coincide with the junctions between adjoining spaces.

Accommodate recessed light fittings, heating and ventilating diffusers and grilles and other utility fixtures and fittings that penetrate the ceiling lining.

4.8.10.3 Wall Linings - Horizontally Fixed - Timber Frame

GIB® Plasterboard Wall Linings Horizontally-Fixed to Timber Framing. Install GIB® plasterboard sheets horizontally, at right angles to studs, with any end-joints staggered, and with the bottom edge of the lower sheet gapped 5–10mm off finished floor level.

All joints between sheets shall be touch fitted. Eliminate or minimise the butting of sheet end-joints by using full-length or long-length sheets. Give careful consideration to the placement of sheet joints. Where possible, place joints in situations where they are less likely to be affected by critical lighting.

It is recommended that sheet end joints in horizontally fixed plasterboard be unsupported, off-stud and back blocked - stud centres must not exceed 600mm. For plasterboard linings with Level 3 Finish and Level 4 Finish, sheet end joints can be located on-stud.

Sheet end joints at openings, such as window and door openings, shall not coincide with the vertical edges of the opening - sheets shall be fitted so that the vertical end joint falls minimum 200mm either side of the edge of the opening.

Plasterboard sheets shall be fixed to timber framing in conjunction with GIBFix® adhesive applied at maximum at 300mm centres to intermediate studs. Do not apply adhesive at sheet edges or within 200mm of fasteners. Firmly press the plasterboard where adhesive has been applied to ensure full contact.

Fix sheets to timber framing with GIB® Grabber® High Thread Screws or GIB® Nails in accordance with GIB® Site Guide fastener schedule. Place fasteners at 300mm centres to top and bottom plates and to perimeter studs, and to each stud where the horizontal joint crosses the stud, with screws no closer than 12mm from sheet edges. It is recommended that fasteners at wall corners are placed 50mm in from the corner in each direction (horizontal/vertical).

Install all necessary paper-faced and metal beads, casing beads, shadow and reveal beads and other edge trims to plasterboard corners and edges as necessary and as detailed on the drawings.

Form movement control joints to the locations and details shown on the approved drawings. Where not indicated on the drawings, movement joints shall be positioned at maximum 12m intervals in both directions (horizontally/vertically), and shall coincide with movement joints in the primary structure, and where there is a change in wall lining material.

Accommodate piped and cabled services and other building services fixtures and fittings that penetrate the wall lining.

4.8.10.4 Jointing & Finishing

Joint and finish GIB® Plasterboard Linings with GIB® joint and finishing compounds appropriate for the plasterboard type and durability, and the finish level required. Refer to Joint & Finishing Compounds clause.

Carry out jointing and finishing according to the specified Finish Level in accordance with the GIB® Site Guide and GIB® Compounds brochure. Reinforce sheet joints and internal corners with joint tape or paper-faced trim embedded into the Taping (first) Coat.

Sheet joints, internal and external corners, and fastener heads shall be evenly finished with GIB® compounds. When dry, lightly sand to a smooth finish with 220 grit sandpaper or drywall sanding screen to remove tool marks, ridges and other imperfections prior to subsequent sealing and decorating.

4.8.11 Completion

Check that GIB® Plasterboard Linings have been installed in accordance with the GIB® Site Guide and GIB® Systems literature, and are finished to the specified finish levels.

Check for any damage and defective work - repair or replace as necessary to the required standard.

Ensure that inspection and assessment of the plasterboard Finish Level has been carried out, and that written agreement stating the completed jointing and finishing is acceptable for subsequent surface sealing and decoration has been provided.

Ensure that the GIB® Installation Sign-Off Certificate has been completed and signed by the Interior Plasterer/Stopper.

Leave all of this work complete and to the required standard in accordance with the manufacturer's warranty requirements, as shown on the drawings and the conditions of the Building Consent.

Clean up thoroughly and leave the finished work and surrounding surfaces clean and free of contamination from compound splashes and dust. Remove all associated rubbish and excess material from the site.

Issue to the Owner a copy of the GIB® Plasterboard Lining Systems Care and Maintenance bulletin, and a copy of the GIB® Product and System Warranty.

Preparation and painting (by others) of GIB® Plasterboard Linings shall be carried out in accordance with AS/NZS 2311 and with the paint manufacturer's recommendations. Refer to separate specification section Painting & Decorating.

Preparation, including application of under-tile waterproofing membranes, and tiling (by others) of GIB® Plasterboard Linings shall be carried out in accordance with AS 3589.1 and the BRANZ Good Practice Guide: Tiling. Refer to separate specification section Tiling.

4.9 GIB® EzyBrace® Systems

4.9.1 Scope

Supply and install the specified GIB EzyBrace® Systems to the locations identified on the drawings, incorporating GIB® plasterboards and all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the GIB EzyBrace® Systems publication, GIB EzyBrace® Bracing Software and the current GIB® Site Guide (check www.gib.co.nz, or call 0800 100 442 for the latest editions), BRANZ Appraisal No.928, other relevant product manufacturers' recommendations, and as shown on the drawings.

No substitutions are permitted for GIB EzyBrace® Systems, GIB® Plasterboard Linings, or GIB® System components and accessories.

This specification section must be read in conjunction with the GIB® Plasterboard Linings specification and relevant GIB® Systems specifications, and other specification sections, as they are interrelated..

4.9.2 Requirements

4.9.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

4.9.2.2 Warranty

GIB® Product & System Warranty:

- 10 Years Warranty - for all GIB® Products and Systems installed, according to warranty conditions.
- Provide the GIB® Product & System Warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

Include with the warranty: a copy of the completed GIB® Installation Sign-Off sheet, and the GIB® Plasterboard Lining Systems Care and Maintenance bulletin.

4.9.2.3 Quality Assurance

Ensure that the installation and finishing of GIB EzyBrace® Systems comply in all respects with the approved design drawings and specifications, and Building Consent.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

4.9.2.4 Inspection & Acceptance of GIB EzyBrace® Systems

Carry out all necessary pre-installation, installation and finishing inspections necessary for GIB EzyBrace® Systems for each area of work in accordance with the requirements of the GIB EzyBrace® Systems Manual, GIB® Site Guide, and BRANZ Appraisal No.928.

Complete the GIB® Site Guide Pre-Installation Checklist prior to installing GIB® plasterboard linings.

Complete the GIB® Interior Plasterer/Stopper Installation Sign-Off Certificate upon completion and before handover for subsequent decoration.

4.9.2.5 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected GIB EzyBrace® System materials and/or work shall be repaired and/or replaced to the satisfaction of the Architect/Designer, without delay and at no additional cost to the Principal.

4.9.2.6 Substitution of GIB® Plasterboard Linings

GIB® plasterboard linings shall be as specified herein and as indicated on the approved drawings. The substitution of GIB® branded plasterboard linings and GIB EzyBrace® Systems components for alternative brands is not permitted under any circumstances.

The substitution of a specified GIB® plasterboard lining for an alternative GIB® plasterboard lining by the Contractor shall be in strict accordance with the requirements of the GIB EzyBrace® Systems Manual and GIB® Site Guide: 2.3 - Board Substitution Options. Such substitutions shall only be permitted with the Architect's/Designer's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative GIB® plasterboard linings to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

4.9.3 Performance

4.9.3.1 Limitations of GIB® Plasterboard

GIB® plasterboard products must NOT be:
- used in external situations, or
- exposed to water or be installed in situations where extended exposure to humidity above 90% RH can reasonably be expected, or
- exposed to temperatures in excess of 52°C for prolonged periods.

GIB EzyBrace® Systems must NOT be used in showers or behind baths. GIB EzyBrace® Systems may be used in watersplash areas provided they are protected with an impervious finish in accordance with the requirements of NZBC E3/AS1, and the GIB Aqualine® Wet Area Systems publication.

4.9.3.2 Bracing Performance - Timber Framing

Bracing Performance - GIB EzyBrace® Systems - Timber Framing. To the timber framed elements noted as 'Bracing' on the drawings, additionally comply with all relevant aspects of the GIB EzyBrace® Systems (2016) publication and GIB Ezybrace® Bracing Software according to the specified bracing unit rating, BRANZ Appraisal No.928, and other relevant product manufacturers' recommendations. Refer to separate specification GIB EzyBrace® Systems.

4.9.3.3 Wet Areas

Wet Area Plasterboard Linings - GIB Aqualine® Wet Area Systems. To the areas noted as 'Wet Area' on the drawings, additionally comply with all relevant aspects of the GIB Aqualine® Wet Area Systems (2007) publication, BRANZ Appraisal No.427, and other relevant product manufacturers' recommendations. GIB EzyBrace® Systems must not be located in shower cubicles or behind baths or the like. Refer to separate specification GIB Aqualine® Wet Area Systems.

4.9.4 Components & Accessories

4.9.4.1 Components & Accessories

GIB EzyBrace® Systems components and accessories, including, but not limited to:
- GIB® Plasterboard Linings;
- GIB® Plasterboard Fasteners;
- Plywood Sheathing;
- GIB® HandiBrac® Panel Hold-down Bracket with Bowmac® Blue Head Screw Bolt;
- Galvanised Steel Strap Plate Connectors;
- Ceiling Diaphragm Ceiling Battens;
- GIB® Adhesives - GIBFix® One and/or GIBFix® All-Bond;
- GIB® Metal Trims & Paper Faced Trims;
- GIB® Plasterboard Control Joints;
- GIB® Joint and Finishing Compounds;
- GIB Soundseal® Acoustic Sealant;
- Fire Resistant Sealant.

Refer to the GIB EzyBrace® Systems literature and the GIB® Site Guide for further information.

4.9.5 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.
Co-operate with the Decorator to ensure that the specified Finish Levels for plasterboard jointing and finishing is achieved before decorating commences.

Coordinate with other trades to install GIB EzyBrace® Systems to the required set-out and standard, and to ensure:
- appropriate tolerances and clearances allow for adjacent internal linings, fixtures, fittings, services, etc; and
- GIB® plasterboard linings correctly allow for proper door and window installation; and
- penetrations for building services are correctly handled to maintain sheet integrity and system performance.

4.9.6 Workmanship

Where required by the NZ Building Act 2004, it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

Installation of GIB EzyBrace® Systems shall be carried out by experienced and competent tradespersons, who are familiar with the specified materials and installation techniques, in accordance with the manufacturer's installation requirements, and to fully comply with all warranty requirements. Submit evidence of experience on request, e.g. National Certificate of Interior Systems, or Certified Business Member of AWCINZ.

Carry out all necessary installation inspections in accordance with the GIB EzyBrace® Systems Manual and the GIB® Site Guide, and to fully comply with the manufacturer's warranty requirements as the works progress.

All cutting, jointing, fixing and sealing techniques shall be exactly as recommended by the manufacturer. All work shall be such as to leave a neat, efficient and robust installation, to the required standard, free from damage and defects.

Make all necessary provisions to protect adjacent work and surfaces from damage during installation.

On Completion:
- Check that GIB EzyBrace® Systems have been correctly installed and finished in accordance with the requirements of the GIB EzyBrace® Systems Manual and GIB® Site Guide, to the correct set-out, dimensions and details shown on the drawings.
- Check for any damage and defective work - repair or replace as necessary to the required standard.
- Ensure that inspection and assessment of the plasterboard Finish Level have been carried out, and that written agreement stating the completed jointing and finishing is acceptable for subsequent surface sealing and decoration has been provided.
- Ensure that the GIB® Installation Sign-Off Certificate has been completed and signed by the Interior Plasterer/Stopper.
- Leave all of this work complete and to the required standard in accordance with the manufacturer's warranty requirements, as shown on the drawings and the conditions of the Building Consent.
- Clean up thoroughly and leave the finished work and surrounding surfaces clean and free of contamination from compound splashes and sanding dust. Remove all associated rubbish and excess material from the site.
- Issue to the Owner a copy of the GIB® Plasterboard Lining Systems Care and Maintenance bulletin, and a copy of the GIB® Product and System Warranty.

4.9.7 Delivery & Handling

Store all GIB EzyBrace® Systems plasterboard linings and system components indoors, off the floor, on a flat, level surface in accordance with the manufacturer's requirements. Keep stored plasterboard linings and system accessories dry, out of direct sunlight, and protected from damage, moisture and contamination at all times.

Do not use damaged or defective materials and products, or products that are beyond the designated shelf life. Cracked or damaged GIB Aqualine® sheets must never be used.

Should a problem be encountered with any GIB® product during installation or delivery, immediately contact the GIB® Helpline on 0800 100 442. Do not continue to use the product that is not performing to specification or expectation. Keep samples of the product in question and where possible, document batch numbers and/or manufacturing dates.

Handle all materials in accordance with the manufacturer's requirements and relevant Product Data Sheets, and in a manner that prevents damage.

Installers shall be familiar with and comply with the manufacturer's Material Safety Data Sheet precautions for use, and use appropriate safety gear when handling materials. Carry plasterboard sheets on edge, and avoid damage to sheet edges, ends, and surfaces.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including General risk and workplace management - part 1.

4.9.8 Preparation

4.9.8.1 General

All framing shall be complete and ready for GIB® Ezybrace Systems and associated GIB® plasterboard linings installation.

Timber framing shall comply with NZS 3604, or with NZS 3603 and AS/NZS 1170 for specific design, and have a maximum moisture content 18% at the time of plasterboard lining installation.

Light structural steel framing shall comply with the requirements of AS/NZS 4600 or the NASH Standard for Residential and Low-rise Steel Framing, Part 1: Design Criteria. All light structural steel framing members shall satisfy the requirements of AS/NZS 1170. Comply with the steel framing fabricator's specifications and requirements for plasterboard installation.

Steel stud partitioning shall comply with AS 1397 and as specified and shown on the drawings. Comply with the manufacturer's specifications and requirements for plasterboard installation.

Concrete substrates shall comply with the CCANZ CP 01:2011 or with NZS 3109. New concrete must have aged for a minimum of 28 days. Ensure that concrete surfaces are within the tolerances specified.

Concrete masonry structures shall comply with NZS 4229, or with NZS 4230 and AS/NZS 1170 for specific design.

Carry out all necessary moisture readings. Do not commence installation until the moisture readings are below the required level.

Carry out all necessary substrate inspections and preparatory work in accordance with the manufacturer's recommendations and the GIB® Site Guide prior to installation. Complete and sign the GIB® Site Guide Pre-Installation Checklist.

Check that the building envelope has been finished at all penetrations including doors, windows, services, etc., and the building is weathertight.

Check junctions to all other building elements and ensure that all necessary works have been completed, including cavity insulation.

Check that all fixtures, fittings and built-in items are correctly installed, and that all framing and substrate edges are completed as detailed.

Confirm the location and details of movement control joints, as indicated on the drawings, prior to installation.

Ensure all pre-wiring and service piping is installed and complete.

Check that any required cavity insulation has been installed correctly and its bulk thickness does not exceed the framing thickness.

Remove all debris and rubbish from framing voids prior to installing linings.

The commencement of work on each section/area shall be deemed to indicate full acceptance by the installer that all preparatory works by other trades is complete.

4.9.8.2 Framing Check

Framing - check all aspects of preparatory works, including but not limited to:
- Check that the framing is straight and true to line, and is plumb/level and correctly aligned.
- Check that the framing is within the required deviation tolerances defined in AS/NZS 2589 according the specified Finish Level.
- Check that vertical and horizontal framing members are at the spacings shown on the drawings, and that any required battens or furring channels are installed to the required layout.
- Check that the framing has no projections due to structural and bracing bracketry, etc. Ensure that framing brackets, plates, braces, hold-downs, etc., are correctly installed.

4.10 GIB® Wet Area Systems

4.10.1 Scope

Supply and install the specified GIB Aqualine® Wet Area Systems to the locations identified on the drawings, incorporating GIB® plasterboards and all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the GIB Aqualine® Wet Area Systems publication and the current GIB® Site Guide (check www.gib.co.nz, or call 0800 100 442 for the latest editions), BRANZ Appraisal No.427, other relevant product manufacturers' recommendations, and as shown on the drawings.

No substitutions are permitted for GIB Aqualine® Wet Area Systems, GIB® Plasterboard Linings, or GIB® System components and accessories.

This specification section must be read in conjunction with the GIB® Plasterboard Linings specification and relevant GIB® Systems specifications, and other specification sections, as they are interrelated.

For the purpose of this specification, the GIB Aqualine® Wet Area Systems publication is referred to as the GIB® Wet Area Systems Manual..

4.10.2 Requirements

4.10.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

4.10.2.2 Warranty

GIB® Product & System Warranty:
- 10 Years Warranty - for all GIB® Products and Systems installed, according to warranty conditions.
- Provide the GIB® Product & System Warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

Include with the warranty: a copy of the completed GIB® Installation Sign-Off sheet, and the GIB® Plasterboard Lining Systems Care and Maintenance bulletin.

4.10.2.3 Quality Assurance

Ensure that the installation and finishing of GIB Aqualine® Wet Area Systems comply in all respects with the approved design drawings and specifications, and Building Consent.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

4.10.2.4 Inspection & Acceptance of GIB® Wet Area Systems

Carry out all necessary pre-installation, installation and finishing inspections necessary for GIB Aqualine® Wet Area Systems for each area of work in accordance with the requirements of the GIB® Wet Area Systems Manual, GIB® Site Guide, and BRANZ Appraisal No.427.

Complete the GIB® Wet Area Systems Manual and GIB® Site Guide Pre-Installation Checklists prior to installing GIB® plasterboard linings.

Complete the GIB® Interior Plasterer/Stopper Installation Sign-Off Certificate upon completion and before handover for subsequent decoration.

4.10.2.5 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected GIB Aqualine® Wet Area System materials and/or work shall be repaired and/or replaced to the satisfaction of the Architect/Designer, without delay and at no additional cost to the Principal.

4.10.2.6 Substitution of GIB® Plasterboard Linings

GIB® plasterboard linings shall be as specified herein and as indicated on the approved drawings. The substitution of GIB® branded plasterboard linings and GIB Aqualine® Wet Area Systems components for alternative brands is not permitted under any circumstances.

The substitution of a specified GIB® plasterboard lining for an alternative GIB® plasterboard lining by the Contractor shall be in strict accordance with the requirements of the GIB Aqualine® Wet Area Systems Manual and GIB® Site Guide: 2.3 - Board Substitution Options. Such substitutions shall only be permitted with the Architect's/Designer's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative GIB® plasterboard linings to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

4.10.3 Performance

4.10.3.1 Limitations of GIB® Plasterboard

GIB® plasterboard products must NOT be:
- used in external situations, or
- exposed to water or be installed in situations where extended exposure to humidity above 90% RH can reasonably be expected, or
- exposed to temperatures in excess of 52°C for prolonged periods.

In addition to the limitations above, GIB Aqualine® plasterboard must NOT be:
- used for bracing purposes in shower cubicles or above baths; or
- applied directly to solid plaster (gypsum or cement), wood based sheet linings or similar materials, masonry or concrete; or
- installed over a vapour barrier or a wall acting as a vapour barrier.

4.10.3.2 Bracing Performance - Timber Framing

Bracing Performance - GIB EzyBrace® Systems - Timber Framing. To the timber framed elements noted as 'Bracing' on the drawings, additionally comply with all relevant aspects of the GIB EzyBrace® Systems (2016) publication and GIB Ezybrace® Bracing Software according to the specified bracing unit rating, BRANZ Appraisal No.928 (2016), and other relevant product manufacturers' recommendations. Refer to separate specification GIB EzyBrace® Systems.

4.10.4 GIB Aqualine® Non-Tiled Wall Systems

4.10.4.1 Non-Tiled Walls - Timber Frame

GIB Aqualine® Wet Area Systems - Non-Tiled Walls - Timber Framing. A timber frame, wet area lining system for non-tiled walls incorporating one layer of 10mm or 13mm GIB Aqualine® on the wet area side. Refer to the GIB® Aqualine® Systems literature.

4.10.5 GIB Aqualine® Tiled Wall Systems

4.10.5.1 Tiled Walls (tile weight - max. 26kg/m²) - Timber Frame

GIB Aqualine® Wet Area Systems - Tiled Walls - Timber Frame. A timber frame, wet area lining system for tiled walls with a maximum tile weight of 26kg/m², incorporating one layer of 10mm GIB Aqualine® on the wet area side. Refer to the GIB® Wet Area Systems literature.

4.10.6 GIB Aqualine® Ceiling Systems

4.10.6.1 Metal Ceiling Battens

GIB Aqualine® Wet Area Systems - Ceilings - Metal Ceiling Battens. A wet area drywall ceiling lining system over metal ceiling battens incorporating one layer of 10mm or 13mm GIB Aqualine®. Refer to the GIB® Wet Area Systems literature.

4.10.7 Components & Accessories

4.10.7.1 Components & Accessories

GIB Aqualine® Wet Area Systems components and accessories, including, but not limited to:
- GIB® Plasterboard Linings;
- GIB® Plasterboard Fasteners;
- GIB® Adhesives - GIBFix® One and/or GIBFix® All-Bond;
- GIB® Rondo® NZ18 Perimeter Angle: shower corner reinforcing, 32 x 32 x 0.55mm thick galvanised steel angle.
- GIB® Metal Trims & Paper Faced Trims;
- GIB® Plasterboard Control Joints;
- GIB® Joint and Finishing Compounds;
- Wet Area Sealant.

Refer to the GIB® Wet Area Systems literature and the GIB® Site Guide for further information.

4.10.8 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.
Co-operate with the Decorator to ensure that the specified Finish Levels for plasterboard jointing and finishing is achieved before decorating commences.

Coordinate with other trades to install GIB Aqualine® Wet Area Systems to the required set-out and standard, and to ensure:
- appropriate tolerances and clearances allow for adjacent internal linings, fixtures, fittings, services, etc; and
- GIB® plasterboard linings correctly allow for proper door and window installation; and
- penetrations for building services are correctly handled to maintain sheet integrity and system performance.

4.10.9 Workmanship

Where required by the NZ Building Act 2004, it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

Installation of GIB Aqualine® Wet Area Systems shall be carried out by experienced and competent tradespersons, who are familiar with the specified materials and installation techniques, in accordance with the manufacturer's installation requirements, and to fully comply with all warranty requirements. Submit evidence of experience on request, e.g. National Certificate of Interior Systems, or Certified Business Member of AWCINZ.

Carry out all necessary installation inspections in accordance with the GIB® Wet Area Systems Manual and the GIB® Site Guide, and to fully comply with the manufacturer's warranty requirements as the works progress.

All cutting, jointing, fixing and sealing techniques shall be exactly as recommended by the manufacturer. All work shall be such as to leave a neat, efficient and robust installation, to the required standard, free from damage and defects.

Make all necessary provisions to protect adjacent work and surfaces from damage during installation.

On Completion:
- Check that GIB Aqualine® Systems have been correctly installed and finished in accordance with the requirements of the GIB® Wet Area Systems Manual and GIB® Site Guide, to the correct set-out, dimensions and details shown on the drawings.
- Check for any damage and defective work - repair or replace as necessary to the required standard.
- Ensure that inspection and assessment of the plasterboard Finish Level have been carried out, and that written agreement stating the completed jointing and finishing is acceptable for subsequent surface sealing and decoration has been provided.
- Ensure that the GIB® Installation Sign-Off Certificate has been completed and signed by the Interior Plasterer/Stopper.
- Leave all of this work complete and to the required standard in accordance with the manufacturer's warranty requirements, as shown on the drawings and the conditions of the Building Consent.
- Clean up thoroughly and leave the finished work and surrounding surfaces clean and free of contamination from compound splashes and sanding dust. Remove all associated rubbish and excess material from the site.
- Issue to the Owner a copy of the GIB® Plasterboard Lining Systems Care and Maintenance bulletin, and a copy of the GIB® Product and System Warranty.

4.10.10 Delivery & Handling

Store all GIB Aqualine® Wet Area Systems plasterboard linings and system components indoors, off the floor, on a flat, level surface in accordance with the manufacturer's requirements. Keep stored plasterboard linings and system accessories dry, out of direct sunlight, and protected from damage, moisture and contamination at all times.

Do not use damaged or defective materials and products, or products that are beyond the designated shelf life. Cracked or damaged GIB Aqualine® sheets must never be used.

Should a problem be encountered with any GIB® product during installation or delivery, immediately contact the GIB® Helpline on 0800 100 442. Do not continue to use the product that is not performing to specification or expectation. Keep samples of the product in question and where possible, document batch numbers and/or manufacturing dates.

Handle all materials in accordance with the manufacturer's requirements and relevant Product Data Sheets, and in a manner that prevents damage.

Installers shall be familiar with and comply with the manufacturer's Material Safety Data Sheet precautions for use, and use appropriate safety gear when handling materials. Carry plasterboard sheets on edge, and avoid damage to sheet edges, ends, and surfaces.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including General risk and workplace management - part 1.

4.10.11 Preparation

4.10.11.1 General

All framing shall be complete and ready for GIB Aqualine® Wet Area Systems and associated GIB® plasterboard linings installation.

Timber framing shall comply with NZS 3604, or with NZS 3603 and AS/NZS 1170 for specific design, and have a maximum moisture content 18% at the time of plasterboard lining installation.

Light structural steel framing shall comply with the the requirements of AS/NZS 4600 or the NASH Standard for Residential and Low-rise Steel Framing, Part 1: Design Criteria. All light structural steel framing members shall satisfy the requirements of AS/NZS 1170. Comply with the steel framing fabricator's specifications and requirements for plasterboard installation.

Steel stud partitioning shall comply with AS 1397 and as specified and shown on the drawings. Comply with the manufacturer's specifications and requirements for plasterboard installation.

Concrete substrates shall comply with the CCANZ CP 01:2011 or with NZS 3109. New concrete must have aged for a minimum of 28 days. Ensure that concrete surfaces are within the tolerances specified.

Concrete masonry structures shall comply with NZS 4229, or with NZS 4230 and AS/NZS 1170 for specific design.

Carry out all necessary moisture readings. Do not commence installation until the moisture readings are below the required level.

Carry out all necessary substrate inspections and preparatory work in accordance with the manufacturer's recommendations and the GIB® Site Guide prior to installation. Complete and sign the GIB® Site Guide Pre-Installation Checklist.

Check that the building envelope has been finished at all penetrations including doors, windows, services, etc., and the building is weathertight.

Check junctions to all other building elements and ensure that all necessary works have been completed, including cavity insulation.

Check that all fixtures, fittings and built-in items are correctly installed, and that all framing and substrate edges are completed as detailed.

Confirm the location and details of movement control joints, as indicated on the drawings, prior to installation.

Ensure all pre-wiring and service piping is installed and complete.

Check that any required cavity insulation has been installed correctly and its bulk thickness does not exceed the framing thickness.

Remove all debris and rubbish from framing voids prior to installing linings.

The commencement of work on each section/area shall be deemed to indicate full acceptance by the installer that all preparatory works by other trades is complete.

4.10.11.2 Framing Check

Framing - check all aspects of preparatory works, including but not limited to:
- Check that the framing is straight and true to line, and is plumb/level and correctly aligned.
- Check that the framing is within the required deviation tolerances defined in AS/NZS 2589 according the specified Finish Level.
- Check that vertical and horizontal framing members are at the spacings shown on the drawings, and that any required battens or furring channels are installed to the required layout.
- Check that the framing has no projections due to structural and bracing bracketry, etc. Ensure that framing brackets, plates, braces, hold-downs, etc., are correctly installed.

4.11 Marshall Weatherization System & Underlay Systems

4.11.1 Scope

4.11.1.1 Scope

The Marshall Weatherization System provides a secondary weather-resistant barrier for timber and steel framed buildings, installed behind wall and roof claddings. The system is supported by BRANZ Appraisal 621 and consists of components that are individually BRANZ appraised. It is suitable for use with direct-fixed (absorbent) and cavity-fixed (absorbent or non-absorbent) claddings, as well as masonry veneer systems.

The system includes a range of wall and roof underlays designed to suit different construction methods, including direct-fix and drained cavity applications. Tekton® Building Wrap and HYDRA wall underlays are installed to the exterior face of framing or to a rigid air barrier where specified. Around

openings, the underlay is cut and dressed to the internal face of the framing, with all joints sealed using Marshall Construction Tape.

Flashing and sealing around openings is achieved using SUPER-STICK or MAXI Butyl tapes. For service penetrations, TRADE-SEAL is used, which consists of an EPDM sleeve bonded to a polyethylene backing to provide an effective air and moisture seal around pipes and conduits. HYDRA roof underlay is used on pitched roofs beneath tile or profiled metal roof claddings.

Note: HYDRA Classic and MAXI Butyl flashing tape are excluded from the BRANZ Appraised Marshall Weatherization System.

For further information and technical advice, contact Marshall Innovations on 0800 776 9727, email headoffice@mwnz.com, or visit www.mwnz.com.

4.11.2 Flexible Wall Underlays

4.11.2.1 Tekton Building Wrap

Tekton Building Wrap. A light weight, flexible, fire retardant, breathable, synthetic wall underlay, manufactured from spun-bonded polypropylene, 100g/m² nominal weight. Tekton Building Wrap can be fixed to timber and steel framing with studs at maximum 0.6mm centres and nogs/dwangs at maximum 1.2mm centres. Supplied in rolls 2740mm x 37m and 1370mm x 37m.

In Low, Medium, High, and Very High NZS 3604 Wind Zone situations:
- Tekton Building Wrap shall be installed over timber or steel wall framing as a wall underlay, in accordance with the manufacturer's requirements, BRANZ Appraisal No.548 (2013) and BRANZ Appraisal No.621 (2014) and as shown on the drawings, with absorbent direct-fixed wall claddings, or with absorbent and non-absorbent wall claddings over a 20mm drained cavity, and with masonry veneer in accordance with NZBC E2/AS1 and SNZ HB 4236.

In Extra High NZS 3604 Wind Zone situations:
- Tekton Building Wrap shall be installed directly over a rigid air barrier, in accordance with NZBC E2/AS1 9.1.7.2, to the manufacturer's requirements, BRANZ Appraisal No.548 (2013) and BRANZ Appraisal No.621 (2014) and as shown on the drawings, with absorbent and non-absorbent wall claddings over a 20mm drained cavity, and with masonry veneer in accordance with NZBC E2/AS1 and SNZ HB 4236.

Tekton Building Wrap must be separated from fireplaces, heating appliances, flues and chimneys in accordance with the NZ Building Code.

Do not leave Tekton Building Wrap exposed for more than 60 days before covering with the wall cladding.

Do not use Tekton Building Wrap behind direct-fixed non-absorbent claddings.

4.11.3 Flexible Roof Underlay

4.11.3.1 Hydra Roof Underlay-Self-Supporting Synthetic Underlay

HYDRA Roof Underlay. A premium tri-laminate Synthetic, Fire Retardant, Absorbent, Breathable, Self-Supporting roof underlay.

Suitable for all roofing types including concrete & clay tiles, pressed metal tiles & profiled metal roofing.Masonry tile roofs with pitches ‹17 degrees must have anti-ponding boards in accordance with E2/AS1 Paragraph 8.2.5 and figure 25.

Supplied in rolls 1250mm x 20m and 1250mm x 40m.

HYDRA Roof Underlay can be used on timber and steel framed roofs situated in NZS 3604 Wind Zones up to and including 'Extra High' and can be used in conjunction with profiled metal roofing, masonry roof tiles, metal roof tiles.

HYDRA Roof Underlay is suitable for use on roof slopes 3° and greater; and can be installed directly under direct-fixed roof claddings, or directly under roof cavity battens or tile battens, in accordance with the manufacturer's requirements and BRANZ Appraisal No.1071.
When used on roof slopes less than 10°, HYDRA Roof Underlay can be installed horizontally, or it can be installed vertically when fully supported by a corrosion-resistant material
When used on roof slopes 10° and greater, HYDRA Roof Underlay can be installed vertically or horizontally, spanning no more than 1200mm between supports.
Installed as a roof underlay in accordance with the manufacturer's requirements and as shown on the drawings. Do not install HYDRA Roof Underlay on roof slopes less than 3°.
Do not leave HYDRA Roof Underlay exposed to weather or UV light for more than 14 days before being covered by roofing

4.11.4 Co-operation

4.11.4.1 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.
Coordinate with other trades to install Marshall Weatherization System components as required

4.11.5 Workmanship

Workmanship where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All installation work shall be carried out by experienced and competent tradespersons, familiar with the specified products and installation techniques, in accordance with the manufacturer's installation requirements and as noted and detailed on the drawings.

Substitutions are not permitted for the Marshall Innovations Limited systems, components, or associated products specified in this section.

4.11.6 Delivery & Handling

Store Marshall Weatherization System materials undercover, away from direct sunlight, on a flat, clean and dry surface. Protect stored materials from damage, moisture and contamination.
Do not use or install damaged or defective materials.
Handle products in accordance with the manufacturer's requirements and in a manner that prevents damage or deterioration to the material

4.11.7 Substrate Preparation

4.11.7.1 Timber Framing

Timber Framing - check all aspects of preparatory works, including but not limited to:
- Check that timber framing has been completed as shown on the drawings, complies with NZS 3604, or NZS 3603 and AS/NZS 1170 for specific design, and is in accordance with Marshall Weatherization System requirements.
- Check that the framing has studs and nogs/dwangs at the required centres, is plumb and in true alignment, and includes all blocking required for fixing the cladding at openings, joints, corners and soffits etc., and that there are no projections due to structural bracing and bracketry.
- Check that timber framing has a maximum moisture content of 20% at the time of installation.
- Check that window and door openings and any other opening in the wall framing have been trimmed correctly, and that all timber frame junctions with other building elements have been completed to the details shown on the drawings.
- Where Marshall Weatherization System components will be in contact with LOSP (light organic solvent preservative) treated timber; the solvent from the timber treatment must be allowed to evaporate prior to the installation of the system.

4.11.8 Installation

4.11.8.1 Tekton Building Wrap - Timber Frame

Tekton® Building Wrap shall be installed in accordance with the Marshall Weatherization System requirements and relevant BRANZ Appraisals. The wrap shall be applied with the branded face oriented outward, fixed to the exterior face of the wall framing, and installed horizontally starting from the base of the wall and progressing upward. Installation shall extend from the upper face of the top plate to the underside of bearers or wall plates supporting the ground floor, or below the bottom plate where installed over concrete slabs.

Laps shall be formed to ensure water is directed to the exterior, with horizontal laps of not less than 150 mm and end laps of at least 150 mm located over framing members. The wrap shall be kept straight and tensioned during installation to avoid sagging.

Fix Tekton® Building Wrap at maximum 300 mm centres using 6 mm to 8 mm zinc-plated staples, hot-dip galvanised large-head clouts, tek screws, or approved proprietary wrap fixings. Care shall be taken during installation in windy conditions due to the potential sail effect of the material.

Position the wrap by aligning printed guide marks with framing members prior to fixing. Unroll across the framing and secure to all members at the specified fixing centres.

Tekton® Building Wrap may be installed as a secondary layer over head flashings in accordance with NZBC E2/AS1, or head flashings may be sealed directly to the wrap using an approved flashing tape system.

4.11.9 Warranty

4.11.9.1 Warranty

15 years: For Marshall Weatherization & Underlay Systems products

Commence the warranty from the date of practical completion of the contract works.

4.11.10 Completion

Check that all components of the Marshall Weatherization System have been installed correctly.

Check that the wall underlay is properly supported with all lap joins sealed with the specified jointing tape, and that window and door openings and penetrating pipes are correctly flashed prior to installing joinery and cladding.

Check the underlay for tears and punctures and other damage - repair or replace, as necessary.

Check sealants for compatibility when applying them over the top of any of the Trade-Seals.

Leave this work complete in accordance with the manufacturer's installation requirements.

Remove work-related rubbish and debris and unused material from the site.

Issue to the Owner a copy of the manufacturer's warranty for any warranted product installed as a component of the Marshall Weatherization System.

5 CLADDING & PRECLADDING

5.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

5.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1170.2:2011(AS/NZS)	Structural design actions - Wind actions
2908.2:2000(AS/NZS)	Cellulose-cement products - Flat sheets
3602:2003(NZS)	Timber and wood-based products for use in building
3604:2011(NZS)	Timber-framed buildings
3631:1988(NZS)	New Zealand timber grading rules

5.3 James Hardie Linea™ Weatherboard

5.3.1 Scope

Supply and install Linea Weatherboard 150mm as a fibre-cement weatherboard cladding material to the walls identified on the drawings, complete with all accessories. The Linea Weatherboards are to be finished with a paint system. All aspects of this work shall be in complete accordance with the James Hardie Linea Weatherboard Technical Specification (check www.jameshardie.co.nz, or call 0800 808 868 for the latest edition), Linea BRANZ Appraisals, and other relevant product manufacturers' recommendations.

James Hardie Linea Weatherboard Linea-Weatherboard-Direct-Fix-Technical-Specification.pdf and Linea-Weatherboad-Cavity-Fix-Technical-Specification.pdf Cladding is CodeMark assured with the NZ Building Code: CodeMark Certificate of Conformity No:GM-CM30018 (Rev O), issued by Global-Mark Pty Ltd.

5.3.2 Co-operation

Co-ordinate with other trades to ensure that appropriate clearances are allowed from roofing products and associated flashings etc, that the panels correctly allow for door and window installation, and that services penetrations are correctly handled to maintain full weathertightness and panel integrity.

Ensure that other trades are aware of the James Hardie Safe Working Practices.

5.3.3 Preparation

Check that the timber framing elements are in accordance with NZS 3604, or in accordance with NZS 3603 and AS/NZS 1170 for specific design, and in accordance with James Hardie requirements. Framing shall be plumb and in true alignment, complete and suitable for the weatherboards, and maximum moisture content as per NZS 3602. Ensure that the framing is true in line with no projections due to structural and bracing bracketry etc. Ensure that the bottom plate hold-downs are correctly installed.

Check that the flexible underlay or rigid air barrier has been installed in full accordance with the manufacturer's requirements and the drawings, and completely finished to all penetrations including doors, windows, services, etc. Check junctions to all other building elements and ensure that all necessary works have been completed eg. flashings etc that will enable the weatherboards and all accessories to be installed.

Check that the ground levels are sloping away from the building so that there will be no ponding water against the building, and that the ground will be remain clear of the weatherboards by at least 100mm at all times in accordance with E2/AS1.

5.3.4 Sealants

Flexible silicone sealant to be SIKA Silaflex MS. Use to seal the weatherboards and accessories in accordance with the sealant manufacturer's recommendations and to James Hardie requirements. Ensure sealant compatibility with selected finish.

5.3.5 Workmanship

All installation work shall be carried out by an LBP, or supervised by an LBP, in accordance with Linea Weatherboards Technical Specification and other relevant product manufacturers' recommendations.

5.3.6 Delivery & Handling

Carry all boards on edge. Stack boards flat on a level platform off the ground ie. use the supplied delivery pallet on level ground (if no pallet then evenly spaced bearers on level ground at 600mm crs maximum). Keep boards and accessories dry at all times. Avoid damage to board edges, ends, and surfaces. Keep uPVC flashings etc out of direct sunlight, and store all accessories on flat and avoid damage. All installers to be familiar with and comply with the James Hardie Safe Working Practices in the Installation Manual, to use appropriate safety gear, and in particular to be aware to avoid breathing silica dust. Do not use any damaged or blemished weatherboards or accessories.

5.3.7 Installation

Install the Linea Weatherboards through the flexible underlay or rigid air barrier to the framing in accordance with the Technical Specification and BRANZ Appraisal No.446, complete with all accessories eg. corner mouldings, cant strip, sealant, soakers, etc. Weatherboard end joints are to be formed off framing with a tongue & groove joint and sealant.

Ensure that all cut edges of weatherboards are primed prior to installation with Dulux 1 Step Prep, Resene Quick Dry, or similar. Ensure that the bottom edge of the weatherboard overhangs below the bottom plate by 50mm, and is clear of the ground surface by at least 100mm; the finished ground

clearance shall be in accordance with E2/AS1. Install flexible flashing tape to all junctions and penetrations (including cables etc), with the addition of a pipe bandage for pipes to maintain weathertightness and air pressure resistance, and seal around.

5.3.8 Fixings

Fix weatherboards and accessories with galvanised nails using the concealed nailing method in accordance with James Hardie requirements.

Fix soakers with nails in accordance with James Hardie requirements.

Optional face nail as required in accordance with James Hardie requirements.

Fix corners and vertical edges of openings with galvanised nails using the face nailing method in accordance with James Hardie requirements.

5.3.9 Completion

Ensure that the Linea Weatherboards have been fixed correctly, that all vertical joints and accessories have been completed correctly, and that all penetrations have been taped correctly. Check that no damage has occurred to any installed weatherboard element or associated component, replace as necessary. Check that no dirt has been mounded up within 175mm of the weatherboards, and maintain the clearance. Ensure that the weatherboards are painted within 90 days of the sheet installation, complete with all accessories and flashings. Hand over a copy of the latest edition of the Linea Weatherboard Product Warranty to the client. Hand over a copy of the latest Linea Weatherboard Care and Maintenance Schedule to the client.

6 EXTERNAL WINDOW & DOOR JOINERY

6.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

6.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1170.2:2011(AS/NZS)	Structural design actions - Wind actions
1734:1997(AS/NZS)	Aluminium and aluminium alloys - Flat sheets, coiled sheet and plate
1866:1997(AS/NZS)	Aluminium and aluminium alloys - Extruded rod, bar, solid and hollow shapes
3604:2011(NZS)	Timber-framed buildings
4211:2008(NZS)	Specification for performance of windows
4223.3:2016(NZS)	Glazing in buildings - Part 3: Human impact safety requirements
4303:1990(NZS)	Ventilation for acceptable indoor air quality
4680:2006(AS/NZS)	Hot-dip galvanized (zinc) coatings on fabricated ferrous articles
NZBC B1	Guidance on Barrier Design
NZBC B1/VM1	Structure
NZBC B2/AS1	Durability
NZBC E2/VM1	External Moisture
NZBC F2	Hazardous Building Materials
NZBC F4	Safety from Falling
NZBC G4/AS1	Ventilation
NZBC H1	Energy Efficiency

6.3 APL Residential Aluminium Windows & Doors

6.3.1 Scope

6.3.1.1 APL Aluminium Window & Door Systems

APL Aluminium Window & Door Systems

Supply and install the specified Aluminium Windows and Doors from APL- Window Solutions to the locations and details shown on the drawings; complete with all components (flashings, support mechanisms, brackets, etc) where required, for proper installation and operation; and commissioned to the required performance and functionality. All aspects of this work shall be in strict accordance with the manufacturer's technical literature and installation requirements (check www.aplnz.co.nz,

call 07 849 8888, or email techinfo@aplnz.co.nz for the latest editions), other relevant product manufacturers' recommendations, and as shown on the drawings.

No substitutions are permitted for the specified Aluminium Windows and Doors from APL - Window Solutions

6.3.2 Warranty

Warranty APL - Window Solutions Materials & Workmanship Warranty:
- 12 Years Warranty on Materials – AGP® Insulated glass units (Warrant glass under normal environmental and use conditions against failure of materials).
- 5 Years Warranty on Materials and Workmanship - for all APL window and door products.
- 2 Years Warranty on Materials and Workmanship – for all mirror glass and hardware.
- Provide the Materials & Workmanship Warranty on the Manufacturer's Standard Warranty Form.
- Commence the warranty from the date of practical completion of the contract works.

View the "Care and Maintenance for Windows and Doors". Terms and Conditions are here www.AGPL.co.nz

6.3.3 Requirements

Safety
Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

Shop Drawings
Prepare and submit to the Main Contractor for verification and approval prior to the commencement of works, Shop Drawings describing the general arrangement and connection to the building envelope of the specified window & door systems.

These shall include, but not be limited to:
- Design calculations - where required;
- Dimensioned elevations of all aluminium joinery elements (typical scale = 1:50; minimum scale = 1:100);
- Complete details of the installation construction, connections and all support systems (typical scale = 1:2; minimum scale = 1:5);
- Sealant types and backing rods, etc;
- Provision for movement, thermal, wind load and/or seismic - where required;
- Coordination requirements/issues with other works and trades - where applicable;
- A schedule of materials, finishes, componentry, fittings, fixings and fastenings - where required.

Producer Statement PS1
If required, as a component of the consent process APL can provide a "Letter of Intended Design" outlining the evidence used in the selection of the specified window and door systems. Upon request, the successful tenderer/manufacturer shall furnish a completed Producer Statement PS1 (Design) as confirmation that the specified window and door systems complies with the relevant

clauses of the New Zealand Building Code. To ensure accuracy, the PS1 Producer Statement will be prepared as a part of the shop drawing process but will not serve as a product warranty or guarantee of compliance.

6.3.4 Performance Criteria - Wind Zone - Durability

General Performance - Wind Zone: High
The specified APL Aluminium Window and Door Systems shall comply with the requirements of NZS 4211 for all relevant clauses.

Wind Load - Non-Specific Design Wind Zone Classification. The specified APL Aluminium Window and Door Systems joinery installation is located in a NZS 3604 Wind Zone: H - High; with a maximum pressure of 0.97kPa SLS and 1.36kPa ULS.

6.3.5 APL Aluminium Joinery Range

Residential Series ThermalHEART
'Residential Series ThermalHEART' Windows and Doors, fully glazed, finished, and complete with hardware and other specified components - all as specified in the following clauses. Manufactured and installed in accordance with the manufacturer's requirements to the locations, configurations and details shown on the drawings and schedules.

6.3.6 Hardware Range

Urbo™ Hardware
APL aluminium window and door hardware and furniture shall be selected from the Urbo™ Hardware range. Manufactured from die-cast zinc and powder coated to the specified colour. Supplied and installed by the APL aluminium joinery manufacturer to the windows and doors as indicated on the drawings and schedules.
Powder coat colour:

6.3.7 Co-operation Workmanship & Delivery

Co-operation
Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades to establish exact sizes for all aluminium window and door frames; and to ensure that each element correctly allows for the installation and finishing of exterior claddings and interior linings and any specific detailing shown on the drawings; and generally, to install all APL aluminium windows, doors and accessories as required.

Workmanship
Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

Aluminium window and door joinery fabrication, assembly and installation work shall be carried out by experienced and competent tradespersons, authorised to manufacture and install APL - Window

Solutions aluminium windows and doors, under controlled supervision and procedures, to fully comply with all warranty requirements and in accordance with the manufacturer's requirements.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

All fabrication and assembly processes and techniques, materials and accessories shall be exactly as recommended by the manufacturer and shall be carried out using suitable machinery, tools and equipment, in a factory workshop.

All work shall be such as to leave a neat, efficient, robust and weathertight installation.

Leave aluminium joinery and glazing clean and free from damage and defects of any kind.

Delivery & Handling
Aluminium joinery frames shall be braced and restrained as necessary for transportation and delivery to site. All surfaces, including glass, shall be appropriately protected from marking and damage during manufacture, delivery and installation.

Inspect all aluminium joinery units upon delivery and reject any damaged or defective items. Contact the manufacturer for replacement of rejected items at time of delivery to site. Do not use or install damaged or defective materials, products and joinery elements.

Store aluminium windows, doors and accessories undercover, off the floor, on a flat, even and level surface as recommended by the manufacturer and in a manner that prevents any frame distortion and surface damage and deterioration. Keep stored aluminium joinery dry and protected from damage, moisture and contamination at all times.

Handle aluminium joinery units and accessories in accordance with the manufacturer's requirements and in a manner that prevents distortion to joinery frames and any damage to the elements - including surface marking. Retain manufacturer's protective coverings for as long as possible, and remove them upon completion.

Installers shall be familiar with and comply with the manufacturer's safe handling requirements and precautions for use, and shall use appropriate safety gear and equipment during all stages of manufacture and installation.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including the Best practice guidelines for working at height in NZ, and the OSH Guidelines For the Provision of Facilities and General Safety in the Construction Industry.

6.3.8 Preparation

General
Prior to installation, carry out all necessary inspections and preparatory work required, and ensure that all preliminary works by other trades has been completed to specification and as shown on the

drawings.
Do not commence installation until all necessary preliminary works by others is complete and to the required standard. The commencement of work shall be deemed to indicate full acceptance by the installer that all preliminary works by other trades is complete.
Check that all window openings and door openings are correctly sized for fitting tolerances, are square and correctly aligned, with all sides plumb, level and true to line and plane.
Check window and door openings adjoining other building elements to ensure that all necessary works have been completed that will enable the windows and/or doors to be installed correctly and as shown on the drawings.
Supporting concrete structures shall be within the scope of NZBC E2/AS3, and comply with NZS 3109. New concrete must have aged for a minimum of 28 days prior to installation.
Supporting concrete masonry structures shall be within the scope of NZBC E2/AS3, and shall comply with NZS 4229, or with NZS 4230 and AS/NZS 1170 for specific design, and NZS 4210.
Supporting timber structures shall comply with NZS 3604, or with NZS 3603 and AS/NZS 1170 for specific design, and have a maximum moisture content in accordance with the requirements of NZS 3602 at the time of installation.
Supporting lightweight steel framed structures shall comply with NZ NASH 3405, or the NZBC for specific design.
Supporting steel structures shall comply with NZS 3404.

Concrete Slab Rebates
Concrete Slab Rebates: check that concrete slabs have been correctly rebated to accommodate door sills and floor-mounted window frames as detailed on the drawings, and that any required waterproofing membrane has been applied to the rebates.

Timber Framed Walls - Flexible Underlay
Timber Framed Walls (within the scope of NZBC E2/AS1) - check all aspects of preparatory works to window and door openings, including but not limited to:
- Check that the timber framing is complete at window and door openings, and is in accordance with NZS 3604, or with NZS 3603 and AS/NZS 1170 for specific design.
- Check that timber framing has a maximum moisture content of 20% at the time of joinery installation.
- Check that flexible wall underlay has been correctly finished around framed window and door openings in accordance with E2/AS1 and the underlay manufacturer’s requirements.
- Check that flexible flashing tape has been correctly applied and finished to window and door openings in accordance with E2/AS1 and the manufacturer's requirements.

6.3.9 Fabrication

Fabrication
Do not commence production and fabrication of the joinery elements until the 'For Fabrication and Installation' shop drawings have been verified and approved by the Architect/Designer.
Fabricate and install aluminium window and door joinery in accordance with the approved shop drawings, design calculations, and the project documentation.

Unless noted otherwise on the approved shop drawings, joinery fabrication shall include the installation of all glazing, hinges, stays, running gear, and other hardware items scheduled on the approved shop drawings.

Glass shall be cut true and square, sized to provide correct edge clearances, blocked into place as required. All glazed joinery units shall be delivered either pressure fit, pocket glaze, or beaded/wedged, unless site glazing is required. Glazing gaskets shall be compatible with all adjacent materials, and cut 1% over-length to absolutely avoid stretching during installation.

Window and door hardware shall be fixed true to line and position, and adjusted and oiled as required for correct operation. The aluminium joinery manufacturer shall notify the Architect/Designer if any scheduled hardware item or fixing position appears incorrect. Account for all keys and deliver separately to the site manager.

Factory-fit safety stays as scheduled to all opening windows, and to opening windows where safety stays are required to comply with the requirements of NZBC F4/AS1.
Factory-fit all required and scheduled passive ventilation systems to NZBC G4/AS1, 1.3.9 - Trickle ventilators, NZS 4303, and the manufacturer's requirements.

As necessary, provide protection and temporary bracing required for the transportation and general handling of the joinery elements. Ensure that all opening doors and windows are temporarily secured for transportation and general handling.

6.3.10 Installation

Flashings - Framed Openings
Install metal flashings to window and door openings, accurately level and plumb, and to the required tolerances as detailed - with the head flashing weathering jamb flashings, jamb flashings weathering sill flashing, and sill flashings open (draining) to the exterior.
Overlap and the top edge of head flashings with flexible flashing tape, or a section of additional flexible wall underlay, along the top edge to ensure water drains to the exterior.
Except where windows and doors are recessed, and where detailed otherwise, all head flashings shall extend minimum 30mm beyond the edge of the window/door frame.

Aluminium Joinery
Installation of aluminium window and door joinery shall be to the requirements of the approved shop drawings and installation details, including fixings and fasteners, flashings, bedding compounds, pointing sealants, weathering sealants, and other components and accessories required for proper installation.
Use only fasteners compatible with the materials involved, as recommended by the window manufacturer and to comply with durability and performance requirements. Fixings and fasteners exposed to weather shall be aluminium or Grade 316 stainless steel. Fixings and fasteners not exposed to weather may be galvanised in accordance with AS/NZS 4680.
Set proprietary plastic packers, sized to the required installation tolerances, to the formed opening at the appropriate fixing spacings for secure installation and allowance for wind loading for windows.
Install aluminium windows and doors exactly square, true to line, plumb and level for proper operation of opening sashes and door leaves, and with fixings fastened through jamb liners and

packers.
Door installation shall allow for a minimum clearance gap of 5mm above the specified floor covering in the space that the door opens into.
Form a continuous air-tight seal between the window/door frames and the adjacent structure with a proprietary expanding foam, or appropriate sealant, to a depth of 15mm - 20mm over PEF backing rod at head, jambs and sill.
Commission opening windows and doors, sliding carriage assemblies, and all moving components to the required operation, performance and tolerances, and ensure that all hardware is in full working order.

Weather Sealing
Weather-seal frame jambs etc. to adjacent surfaces (or to each other) as detailed or as required by the window manufacturer, to achieve a fully weathertight installation.
Sealants shall be BRANZ approved for the application and be compatible with all surfaces and any applied finish.
Insert closed cell PEF backing rods or a polyethylene bond breaker tape slip where required and as shown on the drawings.
Ensure substrates are clean and dry; mask off adjacent surfaces; prime substrates and apply sealant in accordance with the sealant manufacturer's requirements and tool finish to a smooth, even surface.
Where required and as shown on the drawings, install aluminium wind deflection or pressure relief angles, over the head and jambs of frames installed within a recessed opening, prior to weather-sealing frames.

Temporary Safety Indicators
As necessary, provide temporary safety indicators to clear glass until completion of adjacent work.
Do not use masking tape or materials incompatible with the glass for this purpose.

6.3.11 Completion

Defective Materials & Work
Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected APL Aluminium Windows & Doors work shall be repaired and/or replaced to the satisfaction of the Contract Administrator, without delay and at no additional cost to the Principal.

Completion
Check that APL aluminium window and door joinery and accessories have been installed, glazed and finished correctly and fully tested for weathertightness.
Check that all opening window sashes, doors, sliding carriage assemblies and all moving components have been commissioned to the required operating performance and functionality.
Check that all hardware, locks, latches and handles are firmly fixed in place without restricting the operation of their moving parts, and that latches and locks fully engage with strikes and keepers and are free of slack when engaged.
Check all aluminium joinery elements for damage, defects, faults and weathertightness - carry out repairs and/or replace elements as necessary in accordance with the manufacturer's instructions to the required standard.
Remove applied safety indicators and protective coverings, and clean all joinery surfaces inside and

out and leave perfectly clean.
Leave this work complete, weathertight and leak-free, and in full working order to the required operating performance and functionality in accordance with the manufacturer's warranty requirements. Leave all locking keys with the Contractor.
Leave the surrounding work area clean and free of rubbish. Remove rubbish and waste material from the site.

Complete the manufacturer's warranty and maintenance requirements, online process **FOUND HERE**.
APL Product and Installation Warranty for the installed aluminium windows and doors can be **FOUND HERE**.

Provide all necessary Producer Statements.

7 INSULATION

7.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

7.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

4218:2009(NZS)	Thermal insulation - Housing and small buildings
4220:1982(NZS)	Code of practice for energy conservation in non-residential buildings
4243.1:2007(NZS)	Energy efficiency - Large buildings - Building thermal envelope
4246:2016(NZS)	Energy efficiency - Installing bulk thermal insulation in residential buildings
4859.1:2018(AS|NZS)	Thermal insulation materials for buildings - Part 1: General criteria and technical provisions

7.3 Pink Batts Insulation

7.3.1 Scope

Supply and install Pink® Batts® Insulation, as specified herein, to the locations identified on the drawings, complete with all accessories required for proper installation and performance. No substitutions are permitted for Pink® Batts® Insulation. All aspects of this work shall be in complete accordance with Pink® Batts® technical information and installation requirements and as shown on the drawings:
https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

The following is a list and/or general description of the extent of the Pink® Batts® Insulation works, which are more specifically defined in the contract documents, required for the completion of the contract works:

7.3.2 Requirements

7.3.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

7.3.2.2 Warranty - applies to BRANZ Appraised Pink® Batts® Ceiling & Wall products

Pink® Batts® Lifetime Product Warranty:

- 50 Years Warranty for BRANZ Appraised Pink® Batts® ceiling and wall products installed according to the warranty conditions.
- Provide the Pink® Batts® Lifetime Product Warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of permanent installation.

7.3.2.3 Substitutions

Pink® Batts® Insulation shall be as specified herein and as indicated on the approved drawings. The substitution of Pink® Batts® branded products for alternative brands is not permitted under any circumstances.

The substitution of a specified Pink® Batts® product for an alternative Pink® Batts® branded product by the Installer (PinkFit® or other) shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Pink® Batts® branded products to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Installer.

7.3.3 Wall Thermal Insulation

7.3.3.1 Pink® Batts® Ultra® R2.8 Wall

Pink® Batts® Ultra® R2.8 Wall - product code 7127128. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. R-value R-2.8. 90mm thick x 560mm wide x 1140mm long segments.

BRANZ Appraised for use as a thermal insulating material for framed or part-framed walls, ceilings and roofs of domestic and commercial buildings according to the conditions and limitations of BRANZ Appraisal No.238. Refer to product data - https://www.pinkbatts.co.nz/assets/Products/April-2022-changes-/Wall-Product-Sheet_April22_1075-RevF.pdf

Pink® Batts® Ultra® R2.8 Wall is licenced with Environmental Choice New Zealand: Thermal Building Insulants Licence No.2504017.

Installed as wall cavity thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location:

7.3.4 Ceiling Thermal Insulation

7.3.4.1 Pink® Batts® Superbatts® R5.0 Ceiling

Pink® Batts® Superbatts® R5.0 Ceiling - product code 7113150. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. R-value R-5.0 - 225mm thick x 460mm wide x 1220mm long segments.

Pink® Batts® ceiling insulation is a lightweight flexible glasswool insulation product designed to:

- thermally insulate ceilings in new homes, be retrofitted into existing homes without insulation, or over existing insulation for better performance;
- fit easily into standard ceiling constructions, or be easily cut to fit non-standard constructions;
- meet the requirements of the New Zealand Building Code for different designs and environments.

Pink® Batts® Ultra® R5.0 Ceiling is BRANZ Appraised - refer to BRANZ Appraisal No.238.

Pink® Batts® Ultra® R5.0 Ceiling is licenced with Environmental Choice New Zealand: Thermal

Building Insulants Licence No.2504017. Refer to data - https://www.pinkbatts.co.nz/assets/Uploads/Downloads/Roof-and-RTA-Data-Sheet-February-2023.pdf

Installed as ceiling thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location:

7.3.4.2 Pink® Batts® Skillion Roof R3.2

Pink® Batts® Skillion Roof R3.2 - product code 7110232. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. R-value R-3.2. 115mm Max. thickness x 432mm wide x 1220mm long segments.

Pink® Batts® Skillion Roof insulation products are specifically designed for skiillion roofs, and provide high levels of thermal performance while ensuring the maximum thickness the segments can achieve.

Pink® Batts® Skillion Roof insulation has been BRANZ Appraised for use as a thermal insulating material for timber framed skillion roofs of domestic and commercial buildings - refer to BRANZ Appraisal No.767.

Pink® Batts® Skillion Roof R3.6 is licenced with Environmental Choice New Zealand: Thermal Building Insulants Licence No.2504017.

Installed as ceiling thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location:

7.3.4.3 Pink® Batts® Skillion Roof R3.6

Pink® Batts® Skillion Roof R3.6 - product code 7110236. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. R-value R-3.6. 165mm Max. thickness x 432mm wide x 1220mm long segments.

Pink® Batts® Skillion Roof insulation products are specifically designed for skiillion roofs, and provide high levels of thermal performance while ensuring the maximum thickness the segments can achieve.

Pink® Batts® Skillion Roof insulation has been BRANZ Appraised for use as a thermal insulating material for timber framed skillion roofs of domestic and commercial buildings - refer to BRANZ Appraisal No.767.

Pink® Batts® Skillion Roof R3.6 is licenced with Environmental Choice New Zealand: Thermal Building Insulants Licence No.2504017.

Installed as ceiling thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location:

7.3.5 Acoustic Insulation

7.3.5.1 Wall - Pink® Batts® Silencer® 100mm

Pink® Batts® Silencer® 100mm - product code 7317001. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. STC 43 (*with 10mm GIB® Standard plasterboard each side*), R-value R-2.4 (estimate only). 100mm thick x 560mm wide x 1140mm long segments. Suits 90mm thick framed internal walls.

Pink® Batts® Silencer® wall insulation is designed for use in internal walls only where both acoustic and thermal properties are desired. Do not use Pink® Batts® Silencer® insulation for external wall applications.

Refer to product data - https://www.pinkbatts.co.nz/assets/Acoustic-Silencer-Product-Sheet-FEB20-RevD.pdf

Installed as internal wall cavity acoustic insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location:

7.3.6 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with trades to install Pink® Batts® Insulation as required.

7.3.7 Workmanship

All installation work shall be carried out by registered PinkFit® installers; the preferred Pink® Batts® installers, or by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer’s requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to: https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

7.3.8 Delivery & Handling

Store the Pink® Batts® Insulation materials undercover, in a weatherproof environment, off the floor, on a flat, even surface in accordance with the manufacturer's requirements. Keep materials dry and protected from damage, moisture and contamination at all times.

For best practice, refer to Pink Batts Product and Installation Guides.
Further assistance contact 0800 746 522

Store the Pink® Batts® Insulation materials undercover, in a weatherproof environment, off the floor, on a flat, even surface in accordance with the manufacturer's requirements. Keep materials dry and protected from damage, moisture and contamination at all times.

Conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including the Workplace and facilities requirements

7.3.9 Installation

7.3.9.1 General

Install Pink® Batts® Insulation in accordance with NZS 4246.
All installation work shall be carried out by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to:
https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

7.3.9.2 Pink® Batts® Wall

Install Pink® Batts® Wall Insulation in accordance with NZS 4246.

All installation work shall be carried out by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to:

https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

7.3.9.3 Pink® Batts® Skillion Roof

Install Pink® Batts® Skillion Roof in accordance with NZS 4246.

All installation work shall be carried out by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to:

https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

7.3.10 Completion

Check that all specified Pink® Batts® Insulation products have been installed correctly in accordance with the manufacturer's requirements.

Check for damage and defects - replace damaged and defective insulation as necessary to the required standard.

Ensure the installed insulation will be adequately protected for durability and performance in accordance with the manufacturer's warranty requirements.

Leave all of this work complete, and in the condition required for proper performance, including for the installation of subsequent linings, in accordance with the manufacturer's warranty requirements.

Leave adjacent surfaces and finished work clean and free of damage. Remove all associated rubbish and waste material from site.

Issue to the Owner a copy of the Pink® Batts® Lifetime Product Warranty for all Pink® Batts® Insulation products installed.

8 ROOFING

8.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

8.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1397:2011(AS)	Continuous hot-dip metallic coated steel sheet and strip - Coatings of zinc and zinc alloyed with aluminium and magnesium
2295:2006(NZS)	Pliable, permeable building underlays
3604:2011(NZS)	Timber-framed buildings
NZMRM Code of Practice	NZ Metal Roof and Wall Cladding Code of Practice - Version 3.0

8.3 COLORSTEEL® - Roofing Specification

8.3.1 Scope

Inland - Moderate (ISO C2)
Supply the selected COLORSTEEL® roofing and install on the areas identified on the Roof Plan. All aspects of the work shall be in complete accordance with NZ Steel 'Installers Guide' (check colorsteel.co.nz for the latest edition) and any other relevant Product Manufacturers Recommendations.

8.3.2 Products™

COLORSTEEL MAXAM
Colour:

8.3.3 Installation

Set-out the roofing sheets square to building axis and maintain this accurate set out throughout the works.

Install the underlay, keeping it taut and evenly lapped, with a minimum lap of 150mm.

All handling and fixing techniques, and all jointing and sealing materials and techniques, shall be exactly as recommended by New Zealand Steel.

Upon delivery, store on even bearers, and keep dry until installed. Handle roofing without scratching, distortion or other damage. Ensure that each section of roof is waterproofed as soon as possible after preparatory work is complete; allow to carry out the works in several operations if necessary to comply with this condition.

Install fasteners in straight lines, setting them to the correct depth to avoid either a loose seal or distorted sealing washer. Cut sheets by shear only, do not use grinders or friction blades. Do not use graphite pencils for marking. At the end of each day, sweep any loose debris/swarf from the roof surface. The top ends of all sheets are to be turned up to form a stop-end. The bottom of all sheets that have pitches below 8degrees must be drip formed into the gutter.

8.3.4 Maintenance

After completion of the roof, the roof must be maintained in accordance with the COLORSTEEL® Maintenance Recommendations Brochure.

9 TILING

9.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

9.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

2358:1990(AS)	Adhesives - For fixing ceramic tiles
3103:1991(NZS)	Specification for sands for mortars and plasters
3122:2009(NZS)	Specification for Portland and blended cements (General and special purpose)
3661.2:1994(AS/NZS)	Slip resistance of pedestrian surfaces - Part 2: Guide to the reduction of slip hazards
3740:2010(AS)	Waterproofing of domestic wet areas
4586:2004(AS/NZS)	Slip resistance classification of new pedestrian surface materials
4858:2004(AS/NZS)	Wet area membranes
BRANZ Good Practice Guide	Tiling
NZBC B2/AS1	Durability
NZBC D1/AS1	Access Routes
NZBC E3/AS1	Internal Moisture

9.3 Tiling

9.3.1 Scope

Supply, install and finish all Tiling works, complete with all necessary components and accessories required for proper installation and performance, as specified herein and to the locations, layouts and details shown on the approved drawings. All aspects of this work shall be carried out to comply with the New Zealand Building Code and relevant standards, and in accordance with the approved project design documentation, and with any relevant product manufacturers' technical literature.

The following is a list and a general description of the extent of Tiling work, which are more specifically defined in the contract documents, required for the completion of the contract works:

9.3.2 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades to install tiling as required, and to ensure that:
- appropriate tolerances and clearances allow for adjacent finishes, fixtures and fittings, etc; and
- penetrations for piped and cabled services are correctly located to maintain tile integrity and tiling performance.

9.3.3 Workmanship

Where required by the NZ Building Act 2004, it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All Tiling work shall be carried out to best trade practice by qualified and experienced tradespersons, familiar with the specified materials and installation and finishing techniques, in accordance with AS 3958.1 and relevant product manufacturers' technical literature, to the layout and details shown on the approved drawings, and to fully comply with all warranty requirements.

Submit evidence of experience on request, e.g. National Certificate in Floor and Wall Tiling, or certified member of Master Plasterers and Tilers Association.

All substrate preparation, tile laying and tiling accessories application and finishing techniques shall be exactly as recommended by the specified product manufacturer. All work shall be such as to leave a neat, efficient and robust installation.

Interior wet-area tiling shall be waterproof and installed over a waterproof membrane as shown on the drawings.
Exterior floor tiling shall be waterproof and weathertight, and where necessary installed over a waterproof membrane as shown on the drawings.

As recommended by the tile manufacturer, use only an approved adhesive that is compatible with the specified tile, its substrate and its application/use.

Where necessary, delay tiling to allow maximum curing and settling and initial creep of the substrates, particularly to load bearing structural elements.

Do not cover or bridge movement control joints with tiles and tile underlay.

Tiling shall not be undertaken when the ambient and surface temperatures are outside the specified product manufacturer's permissible temperature range.

Where necessary, mask off and protect from contamination adjacent surfaces, joinery, fixtures and finished work before commencing.

Exterior tiling shall not be undertaken during inclement weather. As necessary and in accordance with the manufacturer's requirements, protect exterior tiling from rain, hot dry winds and direct sunlight to aid proper drying and curing.

Leave all tiled surfaces clean, sound, and free from blemishes of any kind.

9.3.4 Delivery & Handling

Upon delivery to site, inspect the tile packs and reject those items that are found to be damaged, defective or contaminated. Contact the supplier for replacement of rejected items at time of delivery to site.

Do not use damaged, defective or contaminated materials, or products that are beyond their designated shelf life.

Store all tiling materials undercover, in a weatherproof environment, off the floor, on a flat, even and level surface in accordance with the manufacturer's requirements. Keep products and materials dry, out of direct sunlight and protected from damage, moisture and contamination at all times.

Handle tiling materials in accordance with the manufacturer's requirements and in a manner that prevents damage to and contamination of the materials and works.

Installers shall be familiar with and comply with all associated product Safety Data Sheet precautions for use, and use appropriate safety gear when handling materials.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including General risk and workplace management - part 1.

9.3.5 Completion

Check that all Tiling work has been correctly installed to the required layout, and that all tile joints, edge-trimming and other detailing is correctly finished, grouted and sealed.

Check all Tiling installations for damage, marks and defects - repair or replace as necessary. Carry out any repairs to the required standard.

Thoroughly clean tiled surfaces in accordance with the manufacturer's recommended procedures and techniques. Lightly buff where appropriate.

Leave this work complete and to the required standard, and in accordance with the associated warranty requirements.

Clean up thoroughly, and leave adjacent surfaces and finished work clean and free of damage and contamination. Remove all associated rubbish from site.

Protect the completed installation from damage, trafficable dirt and grime, and stains as necessary until hand-over as scheduled or directed.

Issue to the Owner a copy of all relevant product manufacturers' maintenance requirements, and a copy of relevant manufacturer Product Warranties and the installer/applicator Installation Warranty for the installed products and completed works.

10 PAINTING & DECORATING

10.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

10.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

2310:2002(AS/NZS)	Glossary of paint and painting terms
2311:2017(AS/NZS)	Guide to the painting of buildings
3750.0:2008(AS/NZS)	Paints for steel structures - Introduction and list of Standards

10.3 General

10.3.1 Alternatives

The materials specified in this section or on the drawings indicate the required standards for these works. Alternatives which are considered equal to or superior to these may be tendered for approval (in writing, and they must NOT be used unless they are approved in writing).

10.3.2 Co-operation

Co-operate with all trades and attend upon Concretor, Joiner, Carpenter, etc. to ensure that the surfaces provided by these trades are completely suitable for the Painter works that are required.

10.3.3 Preparation

No painting or varnishing or other surface coating work shall be undertaken unless the surfaces to be coated are in a correct and proper condition to ensure first class results.

Inspect the works of other trades on which Painter work is scheduled and report to the Main Contractor and the Architect/Designer any defects or irregularities that would affect the permanency or finish of the painting work, and do not proceed until the defects or irregularities have been completely rectified. Failure to examine and report will be construed as an acceptance that all preparatory works are completely satisfactory.

This clause does not relieve the Painter of any of the usual preparatory work to surfaces customarily performed by this trade.

Clean down all surfaces with sugar soap, strippers, mould killers, etching agents, etc. as required. Sand or rub all sharp edges off exterior timbers and other materials as appropriate before painting. Finish rub down ALL surfaces. Ensure that the moisture content of all substrates is appropriate. Remove locks, fastenings, and similar hardware before painting and refix on completion. Remove all

electrical switch and power plates before painting and refix them on completion. Mask adjacent surfaces as required to a true line and remove the masking on completion. Dust and wipe down all surfaces for Painter work and completely remove all dust, rubbish, dirt etc. from areas involved immediately prior to commencement. To each area of the works complete all surface preparation before applying paint to any surface.

10.3.4 Protection

Take adequate precautions to prevent paint spots falling on prefinished or similar surfaces, and extreme care to keep absorbent materials (e.g. cedar, sawn framing, decking, paving) completely clean during all adjacent painting work. Correction of any such disfigurement shall be to the Architect/Designer's approval.

10.3.5 Workmanship

Strictly adhere to all Manufacturers' instructions.

Strictly observe Manufacturers' requirements with regard to surface and air temperatures for painting. No work shall be carried out on surfaces that are not completely dry, and no external work shall be carried out during damp or wet conditions.

In all finishes any irregularities or brushmarks or dust etc. in each preceding coat shall be rubbed down to provide a smooth clean surface for the following coat. Each coat shall be finished over all surfaces before a further coat is applied, and each coat shall be completely dry before subsequent coats. Finish broad areas before painting trim, paint ceilings before walls and walls before joinery, trim and other items.

Each coat and the full completed system shall be of uniform finish, colour, texture and sheen, shall have proper covering of thin edges, corners, end grain etc. and shall be free of blemishes such as runs, sags, fat edges, entrained hairs, brush marks, starved patches etc.

10.3.6 General

The schedules indicate the general extent of the works to be carried out but are in no way exhaustive in their description of the actual items for painter work. Complete all work necessary for the proper and entire completion of the works. All items and portions of items reasonably inferable but not specifically mentioned are deemed included, i.e. cupboard interiors, the top and bottom of doors, unseen cabinetry tops, etc. All doors shall have equal painter work on ALL surfaces.

Where timber work is specified for priming before fixing the priming shall be thoroughly brushed in to all surfaces, and all exterior timber work for paint finishing shall be fully primed within one week of fixing. Should more than one month elapse between priming and undercoating the timber shall be fully reprimed.

Stopping up work shall be carried out immediately the priming or sealing coat is dry, and shall be solidly placed to finish clean and dry. Stopping tinted to match the timber for clear finished work.

Paint putties within one month of glazing timber frames; paint to impinge on glass to assist sealing.

10.3.7 Materials

All Painter materials shall be ready mixed and delivered in unopened containers. Materials shall be used only for the purpose and in the manner intended by the manufacturer; any apparent scheduled discrepancy in this respect shall be referred to the Architect/Designer immediately for clarification.

Where surfaces are specified to be finished in a particular manner or material, all preparatory work, priming, or undercoating, that is necessary to ensure a proper finish shall be provided, irrespective of any apparent omission herein.

Thinning shall only be to manufacturer's specification. Thoroughly stir as required to lift any settled pigment and ensure the paint is homogeneous. Paints shall be factory or shop tinted to the colour required. Undercoats shall be fully tinted to match the final colour scheduled. All paints shall have the finished film thickness that is specified by the manufacturer (checked by monitoring the coverage per litre).

10.3.8 Completion

Allow to touch up to approval any Painter work which is damaged during the finishing works of other trades. Replace all hardware, remove all masking, covers, containers etc., thoroughly clean all affected surfaces, and leave all spaces ready for immediate occupation. Avoid scratching or abrading glass or hardware during any cleaning.

11 PLUMBING

11.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

11.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1221:1997(AS/NZS)	Fire hose reels
1254:2010(AS/NZS)	PVC-U pipes and fittings for stormwater and surface water applications
1260:2017(AS|NZS)	PVC-U pipes and fittings for drain, waste and vent applications
1477:2017(AS|NZS)	PVC pipes and fittings for pressure applications
1546.1:2008(AS/NZS)	On-site domestic wastewater treatment units - Septic tanks
1596:2014(AS/NZS)	The storage and handling of LP Gas
2032:2006(AS/NZS)	Installation of PVC pipe systems
2033:2008(AS/NZS)	Installation of polyethylene pipe systems
2492:2007(AS/NZS)	Cross-linked polyethylene (PE-X) pipes for pressure applications
2537.1:2011(AS/NZS)	Mechanical jointing fittings for use with crosslinked polyethylene (PE-X) for pressure applications - Part 1: Plastics piping systems for hot and cold water installations - Crosslinked polyethylene (PE-X) - General
2642.2:2008(AS/NZS)	Polybutylene pipe systems - Polybutylene (PB) pipe for hot and cold water applications
2712:2007(AS/NZS)	Solar and heat pump water heaters - Design and construction
3500.1:2015(AS|NZS)	Plumbing and drainage - Part 1: Water services
3500.1:2018(AS|NZS)	Plumbing and drainage Part 1: Water services
3500.1:2021(AS/NZS)	Plumbing and drainage, Part 1: Water services
3500.2:2015(AS|NZS)	Plumbing and drainage - Part 2: Sanitary plumbing and drainage
3500.2:2018(AS|NZS)	Plumbing and drainage Part 2: Sanitary plumbing and drainage
3500.2:2021 (AS|NZS)	Plumbing and drainage Part 2: Sanitary plumbing and drainage
3500.2:2021(AS|NZS)	Plumbing and drainage, Part 2: Sanitary plumbing and drainage
3500.3:2018(AS|NZS)	Plumbing and drainage Part 3: Stormwater drainage
3500.3:2021(AS|NZS)	Plumbing and drainage, Part 3: Stormwater drainage
3500.4:2015(AS|NZS)	Plumbing and drainage - Part 4: Heated water services
3500.4:2018(AS|NZS)	Plumbing and drainage Part 4: Heated water services
3500.4:2021(AS|NZS)	Plumbing and drainage, Part 4: Heated water services

3500.5:2012(AS/NZS)	Plumbing and drainage - Part 5: Housing Installations
3501:1976(NZS)	Specification for copper tubes for water, gas, and sanitation
4020:2018(AS|NZS)	Testing of products for use in contact with drinking water
4121:2001(NZS)	Design for access and mobility: Buildings and associated facilities
4517:2010(NZS)	Fire sprinkler systems for houses
4602:1988(NZS)	Low pressure copper thermal storage electric water heaters
4603:1985(NZS)	Installation of low pressure thermal storage electric water heaters with copper cylinders (open-vented systems)
4606.1:1989(NZS)	Storage water heaters - General requirements
4607:1989(NZS)	Installation of thermal storage electric water heaters: valve-vented systems
4613:1986(NZS)	Domestic solar water heaters
4614:1986(NZS)	Installation of domestic solar water heating systems
4617:1989(NZS)	Tempering (3-port mixing) valves
4692.1:2005(AS/NZS)	Electric water heaters - Energy consumption, performance and general requirements
5601.1:2013(AS|NZS)	Gas installations - Part 1: General installations
7602:1977(NZS)	Specification for polyethylene pipe (Type 5) for cold water services
7643:1979(NZS)	Code of practice for the installation of unplasticized PVC pipe systems
7646:1978(NZS)	Specification for polyethylene pipes and fittings for gas reticulation
AS/NZS 3500.5:2012	Plumbing and drainage - Part 5: Housing installations
NZBC B2/AS1	Durability
NZBC G11	Gas as an Energy Source
NZBC G12	Water Supplies
NZBC G13/AS1	Sanitary Plumbing

11.3 General

Carry out all works necessary to leave the water, waste, vent and soil systems serving the sanitary fittings and the plumbing hardware shown on the drawings or specified below in correct working order complete with all ancillary systems (safetrays, floor drains, overflows, relief valves, etc.) required, and with all normal incidentals customarily installed by this trade.

Comply with the Building Code, Territorial Authority By-laws and statutory authority Regulations as appropriate. Obtain all necessary permits and consents, serve all necessary notices, arrange for all tests and pay all fees and customary charges in connection with the required works.

11.4 Aquatherm Flexi Pipe System

11.4.1 Scope

Supply and install aquatherm Flexi Pipe System, complete with pipes, system components, fittings and accessories, as piped hot and cold potable water systems to the layout shown on the drawings. All

aspects of this work shall be in strict accordance with aquatherm Flexi Pipe System technical literature and installation requirements and recommendations (check www.aquatherm.co.nz, or call 09 570 7204 for the latest editions), BRANZ Appraisal No.708, other relevant product manufacturers' recommendations, and with all relevant Standards, Regulations and Acts.

No substitutions are permitted for aquatherm Flexi Pipe System products.

11.4.2 Pipe

20mm diameter aquatherm Flexi Pipe polyethylene - raised temperature (PE-RT) type 2, black coloured pipe. For Hot & Cold potable water pipework. To the layout shown on the drawings. Supported at maximum 700mm spacings with aquatherm Flexi proprietary pipe clips. Includes aquatherm Flexi 20mm brass couplings, adaptors, junctions and bends, plastic pipe clips, H & C pipe indicators and other associated system accessories.

11.4.3 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings prior to installation.

Coordinate with all trades to install aquatherm Flexi Pipe System hot and cold water system components and accessories to the required locations, routes and clearances shown on the drawings.

11.4.4 Workmanship

All aquatherm Flexi Pipe System installation shall be carried out by aquatherm certified trained installers, familiar with the specified products and installation techniques, under the direct supervision of a NZ certified Registered Plumber, in accordance with the requirements of NZBC G12/AS1 - in particular Section 7.

Store aquatherm Flexi components and accessories under cover on a flat surface in accordance with the manufacturer's recommendations. Keep products clean and dry, and protect from damage and contamination, and out of direct sunlight. Do not use damaged or defective products.
Handle aquatherm Flexi components and accessories in accordance with the manufacturer's recommendations.

Adequately protect all surrounding work surfaces during installation. Any damage to fittings or finished surfaces shall be made good by the appropriate trade at the Plumber's expense.

11.4.5 Installation

All aquatherm Flexi RT Type 2 hot & cold water pipework and accessories and other necessary fittings and fixtures shall be sized and installed in strict accordance with the manufacturer's requirements and relevant Standards and Acts, to the layout, details and schedules shown on the drawings.

All pipework installation requirements and techniques, including but not limited to; cutting, joining and support, shall be in accordance with aquatherm Flexi Pipe technical manual and as detailed or noted on the drawings. In-ground pipes shall be installed to AS/NZS 3500 requirements. All cutting, checking and boring of timber framing for pipework shall be in accordance with NZS 3604, holes shall

be correctly sized to allow pipework to expand and contract. Pipework shall be installed and supported in such a manner as to eliminate hammer and flow noise.

Set-out pipework neatly, and firmly support with proprietary pipe clamps at the required spacings. Make allowance for all probable thermal movement and linear expansion to the pipework as necessary.
Pipework shall be run straight and true to line, parallel with and at right angles to structural elements, and with a minimum number of bends - avoid diagonal piping. Neatly align support brackets, fittings and components to multiple pipe runs.
Protect aquatherm Flexi pipework with aquatherm Corrugated pipe, correctly sized, for UV and mechanical protection in accordance aquatherm requirements.
Install exterior sleeved pipes on stand-off brackets. Fixings to the exterior or damp locations shall be hot dip galvanized unless otherwise noted.
Sleeves for pipes penetrating concrete or masonry shall be uPVC, 20mm minimum larger internal diameter than the external diameter of the pipe, set at right angles to the surface, finished flush, packed and mastic sealed.
Install all other necessary system components, fittings and fixtures to complete the hot and cold water system as shown on the drawings.

Weather-seal wherever pipes and fastenings penetrate an external surface; seal with gaskets, flashings (and over-flashings if necessary) or mastic as appropriate.
Fire-protect all pipework that penetrate fire-rated floors and walls with intumescent foaming sealant for joints up to 10mm, and with intumescent stopping putty for gaps over 10mm. Where required fit approved intumescent type fire collars to pipes located such that the fire rating of the wall or ceiling is maintained.
Pipework insulation: preformed hollow sections to the pipe diameters with a minimum wall thickness as recommended by aquatherm Flex Pipe, and installed to the insulation manufacturer's recommendations.

Connect pipework to the main supply and to all hot & cold water fittings & outlets as necessary in preparation for system testing.

11.4.6 Completion

Check that all aquatherm Flexi pipework has been installed correctly in accordance with the manufacturer's recommendations and as shown on the drawings.
Check for damage and faults and repair as necessary. Charge the system and flush out pipework free of trapped air and foreign matter with clean, fresh water, and leave filters clean and free of contaminants.
Fully pressure test the completed system to aquatherm Flex Pipe requirements and leave leak-free.
Leave the works area clean and free of rubbish, remove rubbish and waste material from the site.

Issue to the Owner a copy of the aquatherm Flex Pipe maintenance requirements and a copy of the aquatherm Flex Pipe Warranty for the installed system.

Issue all As-Built Documentation required to the relevant parties.

11.5 Materials

11.6 Plumbing Elements

11.7 Systems

11.8 Workmanship

12 DRAINAGE

12.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

12.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1254:2010(AS/NZS)	PVC-U pipes and fittings for stormwater and surface water applications
1260:2017(AS|NZS)	PVC-U pipes and fittings for drain, waste and vent applications
1546.1:2008(AS/NZS)	On-site domestic wastewater treatment units - Septic tanks
1547:2012(AS/NZS)	On-site domestic wastewater management
2032:2006(AS/NZS)	Installation of PVC pipe systems
3500.0:2003(AS/NZS)	Plumbing and drainage - Glossary of terms
3500.2:2018(AS|NZS)	Plumbing and drainage Part 2: Sanitary plumbing and drainage
3500.3:2018(AS|NZS)	Plumbing and drainage Part 3: Stormwater drainage
7643:1979(NZS)	Code of practice for the installation of unplasticized PVC pipe systems

12.3 General

Carry out all required works to leave the sewer and stormwater systems shown on the drawings in correct working order complete with all normal incidentals.

Comply with Local Authority By-laws and Health Department Regulations as appropriate. Obtain all necessary permits and consents, serve all necessary notices, arrange all tests and pay all fees and customary charges in connection with the works.

12.4 Workmanship

12.4.1 General

Carry out all required works to leave the sewer and stormwater systems shown on the drawings in correct working order complete with all normal incidentals. Comply with Local Authority By-laws and Health Department Regulations as appropriate. Obtain all necessary permits and consents, serve all necessary notices, arrange all tests and pay all fees and customary charges in connection with the works.

12.4.2 Co-operation

Cooperate with all trades and attend upon the Concretor and Plumber to set out exact pipe runs before any adjacent work is put in hand and ensure that all sleeves etc. are correctly incorporated as work proceeds.

12.4.3 Materials

All pipes and other materials shall comply with the appropriate Standards, and shall be protected from damage of any kind until installation is complete. All incidentals appropriate for the applications involved. Concrete shall be 17.5MPa and as specified under Concretor, Mortar shall be as specified in Blocklayer.

12.4.4 Workmanship

All drainlaying shall be carried out by, or under direct control of, properly qualified tradesmen, and shall be to recognised high standards. Ensure cast-in items are installed when required so that no delay is caused by this trade. Adequately protect all adjacent surfaces - clean down to remove dirt etc., and any damage shall be made good by the appropriate trade at the Drainlayer's expense.

On completion of drainlaying clean up full area affected by this trade to the condition it was in before drainlaying commenced.

Site is to be returned as close as possible to its present condition on completion of the contract.

12.4.5 Excavation

As required for sewer and stormwater. Check for other service lines before excavation - the Drainlayer is responsible for making good any damage. Trenches true to line and with even gradients between gullies, soil stack terminations or downpipes, etc.

Keep the bottom of trenches clear of loose material. All pipes shall be laid in appropriate bedding material, compacted as required. Shore trenches if required to suit ground conditions. Backfilling shall be by this trade, to the standards required in Siteworks.

12.5 Elements

12.5.1 Drainlaying

Commence drainlaying at the low end of even fall sections of drains and proceed in a continuous sequence to the fittings connections.

Sumps, gullies, etc. solidly bedded. Lay 110mm uPVC drains to connect gullies, sumps, stacks, and downpipes through to the street edge connections.

Every junction and bend shall be an inspection position. Temporarily seal the open ends of incomplete drains to prevent entry of foreign matter. Make appropriate provision for any anticipated differential settlement. Place signal strip above all drains.

Ensure that stormwater drains are very accurately positioned so that downpipes can drop directly into them, without offsets.

12.5.2 Testing

The sewer and stormwater systems shall both be fully tested to the approval of the Territorial Authority Inspector before being covered in. If any defects show rectify and then fully retest.

12.5.3 As Built Drawings

During drainlaying plot the location of all bends and changes in direction and all cleaning access positions. Locate each item by two diagonal measures from structure corners, etc. and record on a blank plan copy (supplied by Architect/Designer when requested).

Note that Practical Completion of the contract will not be certified until this as-built drawing has been produced (made available to the Contractor in time for the Code Compliance Certificate application.

12.6 Stormwater Drainage

12.6.1 Scope

Supply, install, test and commission new, gravity-flow stormwater drains on the site, to the locations, layout and details shown on the drawings, complete with all necessary components and accessories required for the satisfactory completion and performance of the stormwater system. All aspects of this works shall comply with the requirements of the NZ Building Code, related compliance Standards, Regulations and Acts, and to the requirements of the Territorial Authority, and as specified herein and on the design drawings and schedules. Ancillary work and/or services not specifically mentioned but necessary to complete the installation shall be deemed included.

Install stormwater drains in natural ground, beneath and/or external to the building, for the distances indicated on the drawings. Allow for all inspection openings, bends, branches, manholes, inspection chambers, etc., as required and indicated on the drawings. Unless shown otherwise on the drawings, the stormwater drains shall be connected to the roof and surface stormwater installations, and discharge to the stormwater network.

The stormwater drainage plans are diagrammatic only. Allow for all necessary inspection fittings, cleaning eyes, and traps in accordance with AS/NZS 3500.3 and to comply with the New Zealand Building Code, and as required by the Territorial Authority. Refer to the drawings for the dimensioned locations of roof drainage system rainwater pipes and outlets, and surface drainage outlets, etc.

The following is a list and a general description of the extent of Stormwater Drainage works, which are more specifically defined in the contract documents, required for the completion of the contract works:

12.6.2 Requirements

12.6.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, including WorkSafe's General Risk and Workplace Management - Part 1 and Workplace and Facilities Requirements guidance.

Carry out all construction operations in accordance with the Contractor's project-specific Health and Safety Plan.

12.6.2.2 Compliance

Obtain all necessary permits and consents, serve all necessary notices, arrange all tests and pay all fees and customary charges in connection with the stormwater drainage works.

The Drain Layer shall be deemed to have allowed for all work associated with the safe and orderly execution of the stormwater drainage work, including complying with all Territorial Authority requirements, Building Consent, Building Act, Health and Safety requirements, and all other acts, laws, by-laws and regulations that may affect the execution of the work.

12.6.2.3 Work on Public Property

Excavation and reinstatement of public property shall comply with the requirements of the relevant controlling authorities.

Obtain all necessary approvals and permits from the controlling authorities before commencing work on public property.

Arrange and pay for any excavation and reinstatement inspections of public property required by the controlling authorities.

Before commencing any excavation in or reinstatement work to public footpaths, driveway crossings, roads or other public property, make all necessary enquiries to the relevant controlling authority for their standards for excavation and reinstatement.

Provide at all times, adequate safeguards to the public in respect of temporary fences, signals, signs and lights. Where traffic signs are necessary, these shall be provided and operated in accordance with the Regulatory Authority or NZ Transport Agency (NZTA) guidelines, as applicable, but erected only with the prior written approval of the Regulatory Authority or NZTA and the Contract Administrator.

Where a Traffic Management Plan (TMP) is required, prepare, operate and update this plan as necessary throughout the duration of the works. The TMP shall conform to the requirements of the Regulatory Authority or NZTA, as applicable. Obtain TMP prior-approvals, and maintain the TMP for the entire construction duration.

Remove dirt and contamination deposited on public property to the satisfaction of the controlling authorities.

12.6.2.4 Inspections

Inspections of stormwater drainage works shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Obtain and pay all fees for any required inspections which are additional to the Building Consent.

12.6.2.5 Testing

Carry out all necessary testing of the stormwater drainage installations, and demonstrate to the Contract Administrator and the Territorial Authority that the installations are watertight and comply with the requirements of the New Zealand Building Code, related compliance Standards, and the design documents.

12.6.2.6 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades as necessary to install stormwater drains to the required locations and layout.

12.6.2.7 Workmanship

Stormwater drainage work shall be carried out by qualified and experienced tradespersons, familiar with all required installation requirements, under the direct supervision of a NZ certified Registered Drain Layer, in accordance with AS/NZS 3500.3 and to comply with the New Zealand Building Code, and all local codes and regulatory authority requirements, and the conditions of the Building Consent.

All pipe cutting, jointing, and supporting techniques shall be exactly as recommended by the pipe manufacturer. Pipes, fittings and accessories shall be handled and installed in such a manner that prevents any damage to the component.

All work shall be such as to leave a neat, efficient, robust and watertight installation.

Carry out all necessary inspections and tests during installation to ensure compliance with the design specifications and regulatory requirements. Provide test result sheets to the Contract Administrator to show compliance has been achieved.

Take all necessary precautions during installation to protect the stormwater drainage system from damage, and to prevent the entry of:
- soil, sand, or rock;
- sewage, including the contents of any septic tank, or trade waste; or
- any other substance that could damage or impede the operation of the stormwater drainage network.

Ensure that any installed drain is adequately protected from any damage and excessive loading during the remaining construction period.

Protect adjacent finished work and surfaces from damage and contamination during installation. Any damage to fittings or finished surfaces shall be made good by the appropriate trade at the Drain Layer's expense.

Any associated electrical wiring and prescribed electrical work (by others) shall be carried out by a qualified electrician in accordance with the electrical standards and regulations and the Electrical specification.

12.6.2.8 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. All rejected stormwater drainage materials and work shall be repaired and/or replaced to the satisfaction of the Contract Administrator, without delay and at no additional expense to the Principal.

12.6.2.9 Delivery & Handling

Store stormwater drain pipes and accessories undercover, out of direct sunlight, clear of the ground, on an even surface, and protected from damage and contamination in accordance with the manufacturer's requirements. Keep pipes and accessories out of direct sunlight and protected from damage and contamination at all times.

Store loose PVC-U pipes on evenly spaced bearers at maximum 1.0m centres, with pipe sockets alternated so the the sockets do not bear on each other, and with side supports if pipes are stacked more than two layers high. When loose PVC-U pipes are stacked in a pyramid, the maximum stack height shall be 1.0m and the bottom pipes shall be chocked.

Do not used damaged or faulty materials or products, or products that are beyond their designated shelf life. Do not use PVC-U materials that have been exposed to or stored in direct sunlight longer than the period specified by the manufacturer.

Handle all products and materials in accordance with the manufacturer's requirements, and in a manner that prevents damage or deterioration of the material/product.

Installers shall be familiar with and comply with manufacturer's Material Safety Data Sheet precautions for use, and use appropriate safety gear when handling materials.

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, including WorkSafe's General Risk and Workplace Management - Part 1 and Workplace and Facilities Requirements guidance.

12.6.2.10 As-Built Drawings

On completion and before application for Code Compliance Certificate, prepare As-Built Drawings of the stormwater drainage system, that accurately record the new and/or modified stormwater drainage installation.

Information shall include, but not limited to, type, class and size of all pipes, the location, grade and direction of flow of all pipes, the location of all bends, changes in direction, cleaning access positions, manholes, and all dimensions, levels, inverts, etc.

Submit prepared as-built drawings to the Contract Administrator for review. Issue as-built drawings in accordance with the Contract Administrator's instruction, and in the required format.

12.6.2.11 Warranties

On completion and before Practical Completion, provide all relevant manufacturer/supplier warranties in favour of the Principal, covering materials, equipment, proprietary products, etc., supplied and installed.

12.6.3 Materials

12.6.3.1 General

Supply and deliver to the site all pipes, junctions, precast manholes, granular bedding material and other materials required for the satisfactory completion of the stormwater drainage works. All drainlaying materials shall be fit for purpose, new and free from damage and defects.

12.6.3.2 PVC-U Pipes & Fittings

PVC-U stormwater drain pipes and fittings for non-pressure applications shall comply with AS/NZS 1254: 'PVC-U pipes and fittings for stormwater and surface water applications'. Installed in accordance with AS/NZS 3500.3 and AS/NZS 2032 or AS/NZS 2566.2

Pipe Classification:
Class SN4-SN6 - Rubber Ring Joint or Solvent Welded Joint. For domestic and residential applications, and low load areas.
Class SN8-SN10 - Rubber Ring Joint or Solvent Welded Joint. For commercial and industrial applications, and medium load areas.
Class SN16 - Rubber Ring Joint or Solvent Welded Joint. For heavy traffic load areas.

12.6.3.3 Bedding & Surround Material

Except where specified otherwise, bedding (underlay, side support, overlay) material for PVC-U pipes shall be GAP 7 - General All Passing 7mm - clean, granular, non-cohesive crushed rock or gravel screenings, that is free from organic material and clay, with a moisture content appropriate to the degree of compaction required. If the bedding material is contaminated or an excessive amount of oversized particles are present, the bedding material shall be rejected and not used.

12.6.3.4 Backfill Material

Except where specified otherwise, backfill material above the pipe embedment layer (150mm above the top of pipe) shall be selected ordinary excavated material that is free from any builder's waste,

any organic material, any rocks or hard matter larger than 20mm, and any soil lumps larger than 75mm.

Except where specified otherwise, pipes beneath private roadways and where subject to vehicular traffic - all backfill from the top of the embedment layer (150mm above top of pipe) to the underside of the pavement layer shall be GAP 65 - General All Passing 65mm.

Mechanically compact backfill material in layers not exceeding 300mm to a relative compaction no less than 95% of the NZ Standard Compaction.

Trenches in public footpaths and roads shall be backfilled in accordance with the requirements of the controlling authority.

12.6.4 Trench Excavation

12.6.4.1 Clearing of Surfaces

Where trenches are to be excavated in a grassed area, garden or a berm, the topsoil shall be stripped from the area of the excavation and stockpiled separately adjacent to the trench for use in reinstating the surface.

Where trenches are to be excavated in existing concrete or asphalt paved areas, the paving shall be cut to neat, straight lines, parallel to the trench prior to excavation, with a nominal 100mm trimming allowance either side of the excavation width. The excavation shall be carried out with minimal damage to the existing paved surface.

Where trenches are to be excavated in existing segmental paved areas, the pavers shall be removed by hand, cleaned and set aside for later reinstatement.

Subsequent trench backfill shall be adequately compacted to avoid subsidence of reinstated surfaces.

12.6.4.2 Excavation

Locate all existing buried services before commencing excavation work in any area.

Excavations for trenches and pits shall be properly executed and supported in accordance with the requirements of AS/NZS 3500.3.

Carry out excavation work to comply with all relevant health and safety regulations and guidelines, including the 'Excavation Safety - Good Practice Guidelines'.

Unless specified otherwise, the excavation of trenches shall be taken out by open cut to the levels and grades shown or implied on the drawings. Excavate trenches to the depths which will provide for the appropriate type of bedding.

Trench excavations shall be of sufficient width to allow all operations necessary for the jointing of pipes and placing of the specified backfill. The bottom width of the trenches shall at least the combined measurement of the outside diameter of the pipe plus 200mm - with a minimum clearance of 100mm on each side of the drain barrel. The trench width at the top of the pipe shall not exceed

the outside diameter of the pipe plus 600mm unless the pipe in the trench is covered with concrete. The trench above the top of the pipe may be cut wider, either by excavating a wider bench or by battering the trench wall.

Where a trench has been excavated deeper than required without authorisation, the excess depth shall be filled either with bedding material compacted to achieve a density as near to the original soil density as possible, or with concrete.

12.6.4.3 Dewatering

Take all necessary precautions to keep trenches and pits free from water. Provide all necessary pumps, drainage pipes and other equipments required for dewatering. Install all necessary filtering and detention measures required by the Territorial Authority.

If the bottom of the trench is likely to be adversely affected by rain, remove the final 80mm of excavation as a separate operation immediately before placing the bedding material.

12.6.5 Pipe Laying

12.6.5.1 Bedding Pipes

Provide a minimum 75mm thick underlay layer of well compacted bedding material for all pipes. A chase shall be excavated in the bedding to accommodate any jointing socket or fitting in the drain. The pipe embedment material shall be laid and compacted so that the pipe is evenly and continuously supported along its length on either side of the pipe, and with an overlay layer minimum 150mm thick.

When trench support systems are used, the bedding material shall be placed and compacted in a manner so that no loss of compaction results from removal of the trench side support systems. The trench support shall be removed in such a way as to ensure that the placing and compaction of the bedding material occurs below the trench supports and directly against the undisturbed ground of the trench walls.

After completion of the jointing and inspection of drain pipes, place and compact the bedding surround material around the pipe to the required depth over the pipe. The material shall be carefully placed around and over the pipe using hand tamping and in a manner that ensures the pipe is uniformly supported all round its perimeter and without voids. Take care during placement and compaction to ensure the pipe is not displaced or damaged.

12.6.5.2 Laying Pipes

Install stormwater drains in accordance with AS/NZS 3500.3 to the layout, levels and grades shown on the drawings. Drain pipes shall be laid to provide maximum falls, in straight lines and at an even grade, without obstruction to flow, and with full allowance for bedding.

Before installing the pipes, check the bore of each pipe is free from foreign matter and that the pipe exterior and the socket have not been damaged in handling or storage. All pipelines shall be kept clean and free of dirt and debris at all times during installation, testing and commissioning.

PVC-U stormwater drain pipes shall be properly jointed (rubber ring joint or solvent welded joint) to produce a watertight seal in accordance with the manufacturer's instructions.

Start laying main drains at the point of outfall and insert junctions for branch drains as the work proceeds. Pipes shall be laid with the least number of bends, in the centre of the trench, in straight lines between bends, and to the grades and locations shown on the drawings.

Install all necessary fittings, including inspection openings, bends and junctions, to the locations shown on the drawings and in accordance with the manufacturer's instructions. Where not specified on the drawings or schedules, fittings for inspection openings, bends, and junctions shall be selected from the PVC-U pipe system range of products and installed in accordance with the manufacturer's instructions.

Other than precautions against damage by displacement or floating pipes, no bedding surround material or backfill shall be placed until the laying of the drain has been inspected by the Territorial Authority.

12.6.5.3 Pipe Cover

Unless specified otherwise on the drawings, the minimum pipe cover (finished surface to top of pipe) shall be:

- where not subject to vehicular loading: 300mm.
- where subject to vehicular loading - not in roadways: 450mm.
- where subject to vehicular loading - in sealed roadways: 600mm.
- where subject to vehicular loading - in unsealed roadways: 750mm.
- pipes in embankment conditions or subject to loading from heavy construction equipment: 750mm.

12.6.6 Connection

12.6.6.1 Onsite - to Existing Stormwater Drain

Connect to discharge the new stormwater drainage line to the existing, operational stormwater drainage line on-site in accordance with the requirements of the Territorial Authority and as shown on the drawings.

12.6.7 Testing

12.6.7.1 Stormwater Drains

Test the stormwater installation, including all drains, connections and system components, for water tightness in accordance with the requirements of the Territorial Authority (TA).

Where required by the Territorial Authority, the testing shall be undertaken in the presence of the representative of the TA. Demonstrate to the Contract Administrator and the Territorial Authority that the installation complies with the requirements of the contract documents, related standards and regulatory bodies. Lodge all certificates of approval with the Contract Administrator.

Unless specified otherwise by the Territorial Authority, the testing procedure shall be the Water Test procedure as defined in AS/NZS 3500.3: Section 9. Where appropriate, the procedures in NZBC

E1/VM1 may be used as an alternative. The acceptability of other test methods are be subject to the approval of the Territorial Authority and the Contract Administrator.

Provide all necessary plant, equipment and instruments required for the specified testing procedure. All testing and commissioning shall be undertaken by suitably skilled and experienced technicians.

Pressure testing shall be carried out after the pipes have been laid and the bedding material has been placed over the pipes as specified.

Prior to testing ensure that all pipe junctions and inspection eyes are exposed, and pipelines have been flushed and all residual debris cleaned out.

Stormwater manholes shall be free of visible faults, or permeable zones, and jointing or penetration repairs shall be to best trade practice and standards.

Test results shall be recorded clearly on properly formatted test result sheets, and submitted to the Contract Administrator within 48 hours of completion of testing.

Repair or replace any materials or workmanship found to be defective or faulty during testing, and repeat the test until a satisfactory test result is achieved.

Leave the installation watertight and free of defects, and operating to the required performance standard.

The work shall be deemed incomplete unless all required testing and commissioning has been carried out and has passed the requirements of the testing specification and the Territorial Authority.

12.6.8 Backfilling

12.6.8.1 Backfilling

Trenches shall be backfilled as soon as possible after the laying, inspecting and testing of the pipeline.

Where required, lay marker tape along the length of the drain, just above the top of the pipe embedment zone, before backfilling.

Trench backfill materials shall be placed on the pipe embedment, and compacted to restore the trench as near as practicable to the normal surrounding ground surface level and reduce the likelihood of subsidence. Backfill material shall be placed in uncompacted layers not exceed 300mm, then mechanically compacted to the required density.

Temporary trench support systems shall be lifted progressively above each layer of backfill to ensure each layer is compacted against undisturbed ground.

Any deficiencies of trench filling exposed by settlement shall be corrected to the required standard.

12.6.9 Reinstatement of Surfaces

12.6.9.1 Reinstatement of Surfaces

Refer to separate specification section - Siteworks - Reinstatement of Surfaces. Ground and paved surfaces above excavated stormwater drainage trenches shall be reinstated to the standard specified. Reinstatement shall generally achieve a standard equal to or better than the pre-existing situation - in no case will a lower standard be accepted.

Hedges, fences and other features to be retained that have been damaged or removed during the work shall be reinstated to the satisfaction of the Contract Administrator.

12.6.9.2 Public Property

Reinstatement of surfaces to public property shall comply with the requirements of the relevant controlling authorities.

13 ELECTRICAL

13.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

13.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

2053.1:2001(AS/NZS)	Conduits and fittings for electrical installations - General requirements
2201.1:2007(AS/NZS)	Intruder alarm systems - Client's premises - Design, installation, commissioning and maintenance
2293.2:2019(AS|NZS)	Emergency lighting and exit signs for buildings - Part 2: Routine service and maintenance
3000:2018(AS|NZS)	Electrical installations - Known as the Australian/New Zealand Wiring Rules
3100:2009(AS/NZS)	Approval and test specification - General requirements for electrical equipment
3112:2011(AS/NZS)	Approval and test specification - Plugs and socket-outlets
4512:2010(NZS)	Fire detection and alarm systems in buildings
4514:2009(NZS)	Interconnected smoke alarms for houses
5000.1:2005(AS/NZS)	Electric cables - Polymeric insulated - For working voltages up to and including 0.6/1 (1.2) kV
60335.2.30:2015(AS|NZS)	Household and similar electrical appliances - Safety - Part 2.30: Particular requirements for room heaters
60335.2.30:2015(AS|NZS)INCIEC	Household and similar electrical appliances - Safety - Part 2.30: Particular requirements for room heaters
60335.2.35:2013(AS/NZS)	Household and similar electrical appliances - Safety - Part 2.35: Particular requirements for instantaneous water heaters
60598.2.2:2016(AS|NZS)	Luminaires - Part 2.2: Particular requirements - Recessed luminaires
6104:1981(NZS)	Specification for emergency electricity supply in buildings

13.3 Workmanship

13.3.1 General

Supply and install all materials, including all necessary minor and incidental items, for proper completion of all of the electrical services specified or shown on the drawings. The contract will not be deemed to be complete until the Electrician has provided an Electrical Certificate of Compliance (made available to the Contractor in time for the Code Compliance Certificate application).

Obtain all necessary permits and consents, serve all notices and pay all fees in and customary charges connection with the works.

The position of switches, light and power outlets and other fittings, although shown specifically in some instances, are in general only shown diagrammatically. The exact location of each of these items will be as directed on site by the Architect/Designer; the Electrician shall give reasonable notice of when this information is required. Items positioned in contravention of this shall be repositioned if directed, including rewiring if necessary, all at the Electrician's expense.

Unless drawn (on 1:20 wall elevations) or specified otherwise the mounting height to the centreline of the following items above the floor shall be:

-1000mm for lighting switches;
-2000mm for wall mounted lights;
-2100mm for the bayonet of pendant lights;
-300mm for power points, except at benches.

(Notify the Architect/Designer if either the actual fitting or mounting position seem to make the mounting height noted above inappropriate).

Warranty cards and manufacturers guarantees for items supplied and installed by this trade shall be filled in correctly and handed over at Practical Completion. Arrange all circuits to obtain an optimum balance of the system, and check and reconnect where necessary to achieve this on completion. Leave the works clean and tidy and in full operational order.

13.3.2 Co-operation

Co-operate with all other trades and attend upon the Concretor and Carpenter to set out all required penetrations and to ensure that all wiring and fittings are correctly incorporated as work proceeds. The Carpenter will provide and fix all necessary dwangs and timber supports in locations determined by the Electrician.

13.3.3 Workmanship

All electrical work shall be carried out by, or under the direct control of, registered tradesmen, and shall be to recognized high standards. All work shall be such as to leave a neat, efficient and robust installation. Neatly label switchboards to identify each circuit.

The cutting away and checking of timbers shall be limited to such dimensions as will not prejudice the purpose for which the timber is used; observe NZS 3604: 2011 restrictions on the holing and checking of joists and beams. Chasing and checking of other materials shall be only to approval.

Adequately protect all surfaces. Any damage to fittings or surfaces made good by the appropriate trade at the Electrician's expense.

13.3.4 Wiring

Joints within cable runs will not normally be accepted. TPS cable shall be adequately supported, and clipped at regular intervals. At terminations all strands of conductors shall be fully secured in a

terminal block or clamped under a screw head washer; do not cut away any strands. Wiring which terminates in enclosed fittings and/or where subject to heat liable to cause deterioration, shall be high temperature type, with the tails made off with heat resisting sleeves, to protect the permanent wiring.

Wire lights in 1.5mm 3 core - 7.5 amps loading max per circuit (allow for 100w to all light fittings unless identified otherwise).
Wire power outlets in 2.5mm 3 core - 7 maximum GPO singles or doubles per circuit. Assess power outlets for specific equipment and allow accordingly.

Conceal all wiring except as noted on drawings or below. All wiring cast into concrete shall be run in conduit pipes. All cables shall be stranded (single core is unacceptable).

Wire more or less parallel to and at right angles to the structural elements - avoid any diagonal wiring. Layout of the principal distribution wiring shall be to approval. Position all wires to minimise the risk of damage from subsequent nailing of linings etc.

Generally, do not run TPS horizontally within timber walls except in the area up to 300mm above floor. Wire in the ceiling framing and drop vertically to outlets and switches.

Do not run TPS horizontally within partitions except in the area up to 300mm above floor. Wire in the ceiling void and drop vertically to outlets and switches. Principal wiring in the ceiling void shall be supported on adequate catenaries.

Wire exterior lighting in screened cable.

Where cables pass through fire rated walls or floors use a fire barrier or fire rated sealing compound to seal the space after installation of the cables.

13.4 Elements

13.4.1 Appliances

All appliances are exactly identified on the drawings notes. Main Contractor will establish, in consultation with the Plumber and Electrician, which of them will be supplied by each of these trades.

The Electrician shall supply appliances that are their responsibility, install them exactly in accordance with their manufacturer’s instructions, and protect them until completion.

13.4.2 Light Fittings

All light fittings are identified as to type on the drawing, and will be supplied by the Principal. Take delivery, install in accordance with any directions supplied and protect until Practical Completion.

13.4.3 Tele Communications

Workmanship shall be recognised best trade practice, and in accordance with the manufacturers' recommendations. All work shall be by competent and experienced operatives.

13.4.4 Other Wired Services

Co-operate with all other trades to ensure that the following services - where relevant to the project and as indicated on the plans - are installed complete and in accordance with their manufacturer's recommendations with all normal or necessary incidentals and with all wiring concealed.

-SKY TV.
-Stereo Unit.
-Central Vacuum System.
-Garage door operating mechanisms.
-Gas hot water supply unit installed complete by the Plumber - supply electrical feed and connect.
-Wall mounted fan heaters.
-Front door bell as noted - supply and install.
-Kitchen, laundry and wet areas air exhaust fans and ducting as noted - supply and install.
-Cupboard heaters - supply and install.
-Infrared / movement / daylight sensor switches as noted.
-Under-tile electric heating to the bathroom and shower room complete with thermostat control installed where shown. Supply and install (immediately prior to tiles installation) exactly to the suppliers recommendations.
-Heated towel rails to bathroom and shower room.
-Spa pool equipment will be installed complete by the Plumber. Supply power through weather proof connection, with an isolating switch.
-Hot water cylinders installed complete by the Plumber. Supply and connect.
-The lap pool electrical equipment will be installed complete and wired from the splitter box (by a Registered Electrician) by the Pool Installer. Main contract Electrician shall verify that all aspects of this work comply with all relevant main contract requirements.
-Septic tank pumps feed in conduit from an isolating switch.
-Heat pump
-Supply a Heavy Duty TV Aerial (suitable for TV1, 2, and 3, Sky, and all local and community TV stations) and install on the roof ridges where directed, stayed against wind, and with all connections compatible with the roofing and waterproof. Feed to the outlets shown with the complete system exactly to aerial suppliers recommendations.
-Heating.
-Install ceiling fans with variable speed controllers supplied by owner.

13.5 Interconnected Smoke Alarms

13.5.1 Scope

Supply, install, and commission Interconnected Smoke Alarms to the locations and layout shown on the drawings, complete with accessories. All aspects of this work shall be in accordance with the smoke alarm manufacturer's product specification and installation requirements, other product manufacturers' recommendations, the electrical specification, and as shown on the drawings.

13.5.2 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.
Co-ordinate with other trades to install Interconnected Smoke Alarms as required.

13.5.3 Workmanship

All work shall be carried out by experienced and competent tradesmen in accordance with the manufacturer's requirements, the electrical specification and drawings, and the related standards, electrical regulations and code requirements.
All work shall be such as to leave a neat, efficient and robust installation.

13.5.4 Power Supply

Interconnected smoke alarms shall be powered from a permanently energised 230 v a.c. mains power supplied from the unswitched side of a commonly used circuit, and shall include either a long-life battery backup or long life (10yr minimum) built-in rechargeable energy storage device.

13.5.5 Heat Alarms & Heat Detectors

In addition to installing interconnected smoke alarms; install heat alarms or heat detectors, interconnected to the smoke alarms, to the locations shown on the drawings.

Manufacturer, brand name & type:

13.5.6 Installation

Install the interconnected smoke alarms on ceilings, or as shown otherwise, to the layout shown on the drawings in strict accordance with the manufacturer's instructions. Do not install smoke alarms in dead air spaces or obstructions where dead air spaces may be created.

Install smoke alarms to sloping ceilings at the high end of the ceiling slope.

Do not install smoke alarms to exposed bulkheads, beams, joists or purlins greater than 300mm deep.

Do not install smoke alarms closer than 400mm to any forced-air supply opening or to any blade of a ceiling fan.

13.5.7 Completion

Check that the smoke alarms have been correctly installed and wired.
Commission smoke alarms to the required operation in accordance with the manufacturer's instructions. Test alarms to ensure that the warning signal is heard in all bedrooms when all doors between the alarm and bedrooms are closed.
Check for faults and damage, repair/replace as necessary.

Issue to the Owner a copy of the manufacturer's testing and maintenance requirements and product warranty.

13.6 Systems

13.6.1 Earth

Provide a driven main earth suitable for the full installation, close to the meterboard, complying fully with all appropriate regulations and to the complete approval of a certified inspector. Bond all exposed metals, including light fittings and piped services and provide earth conductors for the entire system. Sheathing to any neutral screened cables may be used for earthing.

13.6.2 Mains

Install a neutral screened 16mm main cable underground (depth, cover/protection, backfilling, signal strip etc. to comply with all relevant regulations) from the grid connection position noted on the Site Plan along the route indicated to the meterboard, positioned where shown on the Floor Plan, and make appropriate arrangements for the grid connection. Install pilot as required. The meterboard shall be metalclad with a meter reading window, recessed maximum depth into the wall and at 2m to the top of the board, with the meters and water heater controllers by the supply company nominated by the Principal. Install all switches and fuses that are necessary. From the meterboard run (route to approval) a neutral screened 16mm main plus controllers etc. to the switchboard.

13.7 Materials & Control

13.7.1 Materials

All materials delivered with packaging and labeling intact. All required incidentals (insulating tape, seals, fixings, etc.) shall be completely appropriate for the application involved. The use of items damaged in any way is subject to approval in each instance.

13.7.2 Switchboard

The main switchboard and the subboard(s) shall be appropriate sized standard PDL DBF series boards installed fully recessed where shown and at 2m to the top of the boards. Install appropriate sized MCB's for all circuits, including a minimum of two power and one lighting RCDs as required to cover all outlets to each board. Submain(s) from the main switchboard to the subboard(s) shall be neutral screened 16mm or 2 x 16mm as appropriate, run along the routes indicated / as approved. Pay particular attention to spreading the distribution of the various probable loadings evenly across the phases to obtain an optimum balance of the system.

1 4 H V A C

14.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

14.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

14.3 Panasonic Heat Pumps

14.3.1 Scope

14.3.1.1 Scope

Supply, install, and commission the selected Panasonic Heat Pumps to the locations and layout shown on the drawings, complete with accessories. All aspects of this work shall be in accordance with Panasonic New Zealands's installation requirements, other product manufacturers' recommendations, the electrical specification, and as shown on the drawings.

No substitutions are permitted for the selected Panasonic Heat Pumps.

14.3.2 Co-operation

14.3.2.1 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.
Co-ordinate with other trades to install the selected Panasonic Heat Pumps as required.

14.3.3 Workmanship

14.3.3.1 Workmanship

All installation work shall be carried out by an experienced tradesmen, familiar with the specified products and installation techniques, to fully comply with Panasonic New Zealand warranty requirements in accordance with the manufacturer's installation requirements, the electrical specification and drawings, related standards, regulations and code requirements, and as noted and detailed on the drawings.

14.3.4 Delivery & Handling

14.3.4.1 Delivery & Handling

Store and handle materials and products in accordance with the manufacturer's recommendations, keep materials dry and protect from damage at all times. Do not use damaged or faulty materials and products.

14.3.5 Completion

14.3.5.1 Completion

Check that the Panasonic Heat Pumps have been installed correctly.

Carry out all necessary testing, check for faults and damage and repair and/or replace as necessary. Commission the heating panels to the required operation and performance functionality.

Issue to the Owner a copy of the heated floor system maintenance requirements, and a copy of the Product and Installation Warranties for the completed works.

14.3.5.2 Healthy Homes Standard

If this home is to be tenanted under the *Residential Tenancies Act 1986*, adequate heating will be installed, compliant with the *Residential Tenancies (Healthy Home Standards) Regulations 2019.*

More information can be found at https://www.tenancy.govt.nz/healthy-homes/heating-standard/