BROUGHAN RESIDENCE

49 KOREKE LOOP, KOREKE RISE, HAWEA

LATITUDE HOMES



ARTISTIC IMPRESSION SUBJECT TO FINAL DESIGN AND COLOUR SELECTION



PLAN INDEX

	GENERAL NOTES
A101	SITE PLAN
A201	FLOOR PLAN
A202	FOUNDATION PLAN
A203	DRAINAGE PLAN
A204	ROOF FRAMING PLAN
A205	ROOF PLAN
A206	BRACING PLAN
A207	ELECTRICAL PLAN
A301	ELEVATIONS
A401	CROSS SECTION
A402	CROSS SECTION
A501	DETAILS
A502	DETAILS
A503	DETAILS
A504	DETAILS
A505	DETAILS
A506	DETAILS
A507	DETAILS
A508	DETAILS
A509	DETAILS
A510	DETAILS
A511	DETAILS
A512	DETAILS
A513	DETAILS
A514	DETAILS
A515	DETAILS
A516	DETAILS
A517	DETAILS
A518	WET AREA DETAILS
A519	HWC DETAILS
A520	APPENDIX 01 (BRACING)
A521	APPENDIX 02 (FIXINGS)
A522	APPENDIX 03 (JACK STUD FIXINGS)
A523	APPENDIX 04 (ROOF BRACING)
A524	APPENDIX 05 (PIPE PENETRATIONS)
A525	APPENDIX 06 (DRAINAGE)
A526	APPENDIX 07 (H1)
A601	JOINERY SCHEDULE

REVISIONS

CN-A 20 MAY 2026
- Concept plan

CN-B 10 JUNE 2026
- Concept plan revisions

CN-C 19 JUNE 2026
- Concept plan revisions

CN-D 27 JUNE 2026
- Concept plan changes

CN-E 29 JUNE 2026
- Concept plan changes

CN-F 14 JULY 2026
- Concept plan change

CN-G 22 JULY 2026
- Landscaping added

CN-H 11 AUGUST 2026
- Shower changed

NEW HOME CONSULTANT:
JEREMY PILE

FRANCHISE:
Latitude Homes Southern Lakes

JOB NUMBER:
CTL309

Garner Architecture

Plans prepared by Garner Architecture Ltd
P: 027 358 3498
E: office@garnerarchitecture.nz

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
CHECKED: CG
PROJECT #:
CTL309

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

GENERAL NOTES


SCALE 1:1, 1:1.2668 @ A3

STATUS: **WD-A** WORKING DRAWING

SHEET:

CLIENT:
BROUGHAN RESIDENCE

ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA



Legend:

- Site boundary line
- Easement line
- Boundary setback line
- Contour line
- Sediment control fence
- Selected driveway with 1:100 min fall to sumps

General Notes:

1 All setout dimensions are to the face of the foundations

2 Location and orientation of proposed building to be confirmed on site with owner before commencing construction

3 Patio and paving to front door to comply with NZBC D1 2.1 slip resistance table 2.

4 Location of services to be located by building contractor before commencing construction

Sediment Control Notes:

1 All erosion and sediment control measures to be installed prior to any major earth works on site

2 All earthworks shall be kept to a minimum as required to complete building and landscaping work and shall only commence immediately prior to building

3 All excavated material not required for sill shall be removed from the site

4 All erosion and sediment control structures shall be inspected each day and maintained

5 Downpipes shall be temporarily connected to the srormwater drainage system as soon as the roof is installed and ahall be left in place until the permanent downpipes are fitted

Hazard Management Temporary Fencing:

If a work site is not completely enclosed and unauthorised entry by children is likely, it is acceptable for specific hazards to be fenced only when workers are absent from the immediate vicinity where a potential hazard as a work site makes a safety barrier necessary, a barrier complying with table 1, NZBC F5/ AS1 is an acceptable solution

Surrounding Ground Fall:

Fall finished ground away from building at 1:25 min. For at least 1.0m. Finished ground levels to the site are to allow for un-obstructed overland flow paths to street channel or other council designated stormwater paths

Legal Description

Lot: 74 DP: 604070
Site area: 654m²

Site Details:

Wind zone:	HIGH
Earthquake zone:	3
Exposure zone:	B
Snow loading:	N5

Site Coverage:

Building footprint:	165.76 m²
Additional areas:	6.04 m²
Total area:	171.08 m²

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | *DRAWN:* SG
PROJECT #: CTL309 | *CHECKED:* CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

SITE PLAN


SCALE 1:100, 1:150 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE

ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A101**



General Notes:

1. Building contractor to check all dimensions before commencing construction
2. Offset joinery is dimensioned otherwise considered centred in wall space
3. **All** joinery double glazed
   All glazing shall comply with NZS 4223 part.3:2016 'human impact safety requirements' note that irrespective of glazing dimensions safety glazing must be installed to any door or window in a room containing a bath or a shower or a spa and to all shower doors and screens.
4. **All** downlights to be IC-F rated
   To comply with NZBC G8/AS1. Minimum illuminance of 20 lux per m^3 of floor area required. External lighting to be provided at access routes.
5. Kitchen bench surface to comply with NZBC G3 clause 1.1.3
6. Walls in internal wet areas to be GIB Aqualine with washable 3 coat system using a satin enamel top coat unless specified otherwise
7. Door locking mechanism shall comply with C/AS1 3.2.4.2 key operation shall not be in the direction of the fire escape route

External Wall Framing:

90x45 studs up to 2.4m - at 600mm crs
90x90 studs up to 3.6m - at 600mm crs

Interior Wall Framing:

90x45 studs up to 2.4m - at 600mm crs

Flooring Legend / Notes:

Indicates vinyl plank flooring:
Installed to manufactures specification

Patio and paving to front door to comply with NZBC D1 2.1 slip resistance table 2. Maximum step height to common / main private stairways to be 190mm.

Total Area Over Frame:

Living area (House):	106.75 m²
Garage area:	24.98 m²
Living area (Unit):	34.07 m²
Total area (over frame):	**165.76 m²**
Roof plan area:	206.60 m²
Covered area(s):	6.04 m²

N

ELEVATION KEY

1 2 3 4

Legend:

- Interconnected smoke detector installed in accordance with NZS4514:2021
- Heated towel rail

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

FLOOR PLAN


SCALE 1:100, 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE

ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A201**



General Notes:

1 Diagonal dimensions are for setout and checking purposes only

Foundation Type:

Engineered Maxslab Base Foundation

HWC
20mm copper pipe to discharge outside the foundation envelope in a visable location
Safe tray installed to HWC with overflow pipe to discharge outside the foundation envelope

Legend:

- Joinery / garage door rebate
- Wanz bar location at slab
- Load bearing walls, refer to floor plan for position

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
PROJECT #: **CTL309**
DRAWN: SG
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

FOUNDATION PLAN


SCALE 1:100 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE

ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A202**



Plumbing and Drainage AS3500:

* = discharge pipe discharges to un-vented 65Ø branch drain at floor level

Sanitary sewer plumbing and drainage to AS/NZS 3500.2. Stormwater drainage to nzbc E1/AS1.

Sanitary sewer and stormwater drains to be tested by way of air test in accordance with either clause 12.3.2 of AS/NZS 3500.2.2 or paragraph 8.3 of E1/VM1

Pipe sizes, grades, and layout, to be confirmed by a registered plumber/drainlayer.

Fixtures discharging to gullies:	**Pipe size**	**+ Gradient**
Bath	40Ø	1:40
Basin	40Ø	1:40
Shower	40Ø	1:40
Laundry Tub + WM	40Ø	1:40
Kitchen Sink	40Ø	1:40

Fixtures discharging to un-vented branch drain:	**Pipe size**	**+ Gradient**
Bath	40Ø*	1:40
Basin	40Ø*	1:40
Shower	40Ø*	1:40
Laundry Tub + WM	50Ø*	1:40
Kitchen Sink	50Ø*	1:40
Water Closet	100Ø	1:60

Vent Sizes:	**Pipe size**
Drain Vent	50Ø

Sanitary Drainage:	**Pipe size**	**+ Gradient**
Main Drain	100Ø	1:60
Branch Drain	100Ø	1:60

Stormwater Drainage:	**Pipe size**	**+ Gradient**
Stormwater lines	100Ø	1:120
Downpipes	80Ø	

Ledend:

	Stormwater
	Sewer main
	Sewer drain Under slab
	65Ø branch drain
ORG	Overflow refief gully
GT	Gully trap
IP	Inspection Point
FWG	Floor outlet
AAV	Air Admittance Valve

HWC
20mm Copper overflow and 40mm UPVC safe tray drain outside of external envelope

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | *DRAWN:* SG | *CHECKED:* CG

PROJECT #: **CTL309**

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DRAINAGE PLAN


SCALE 1:100 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE

ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A203**



General Notes:

1 Gangnail H1.2 roof trusses at 900crs to roof manufacturer's design

2 All wall framing / studs calculated to NZS3604:2011 unless otherwise stated

3 Refer to roof manufacturer's truss framing plan. The truss design provided with these drawings takes precedence over all members indicated on the architectural plans. Any discrepancy please contact the architectural practice.

4 Beams and lintels including fixings designed by truss designer unless otherwise stated.

5 All beams, lintels or rafters by designer are calculated from either NZS3604:2011 or DesignIT.

6 Mechnical ventilation to achieve exhaust rates in accordance with AS 1668.2
Bathroom / WC shall achieve 25L/s
Laundry shall achieve 20L/s
Kitchen rangehood shall achieve 50L/s

Top Plate Fixings:

All load bearing walls, stud to top plate fixing with type B (2/90x3.15mm end nails and 2 wire dogs)

Soffit Construction:

4.5mm James Hardie hardiesoffit lining with PVC jointers

Bearer Construction:

(max very high wind zone)
450mm Eave shall have 900mm bearer crs
600mm Eave shall have 600mm bearer crs
1200mm Eave shall have 600mm bearer crs

Install in accordance with the manufacturers documentation for soffit lining

Gable Ends:

90x45 SG8 fly rafter as per NZS3604:2011 and mitek gable end raking verge overhang options 2017

90x45 SG8 outriggers @ 1200 crs max. As per NZS3604:2011 and mitek gable end raking verge overhang options 2017 fix to gable end truss with 1xwiredog & 2/90x3.15ø skew driven nails and fix to next truss back with 3/90mm nails

Beam Schedule:


Beam	Beam sizee
Beam 01	150x90LVL11

Legend:

- 2/ 90x45 LVL8 / L1 — Lintel size / type, Lintel fixing type
- L2 — Lintel Beam fixing
- Stud to top plate internal load bearing wall fixing type B (to hatched area)
- Ranghood ducting venting out soffit
- Extractor fan ducting venting out soffit

Pink® Batts® Perimeter

With the reduction of the R value requirement for ceilings to a construction R value of R2.6 under the H1 6th Edition, we have released an R2.7 Pink® Batts® Perimeter product at 100mm thickness. Supplied at 560mm wide, our Pink® Batts® Perimeter is designed to cover over at least half of the top plate and extend up to 500mm into the ceiling space at the perimeter. Combined with the 460mm wide Superbatts® ceiling insulation solutions this ensures you can meet the requirements of the H1 6th Edition, while avoiding the need for a raise heel or an insulation guard.



EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: CTL309
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

ROOF FRAMING PLAN

SCALE 1:100 @ A3


STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE


ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA


SHEET: **A204**

8.5.1B Ridge-hip Intersection



8.5.1A Ridge-Hip Junction





General Notes:

1 The maximum plan area discharding into the downpipes shall be 50m²

2 The truss design provided with these drawings takes precedence over all members indicated on the architectural plans. Any discrepancy please contact the architectural practice.

3 Valley boards shall be min 19mm H1.2

4 Snow straps as per manufacturer's requirements

Roof Bracing:
Designed to NZS3604:2011 section 10.3 and 10.4


Material Selections:

Roof Cladding 1:
Trim Rib 0.4 BMT Colorcote Zinacore metal profiled roofing on self supporting roofing underlay on SG8 timber purlins on structural roof framing

Fascia & Gutter(s):
Selected 180mm Fascia and Gutter profile
Cross sectional area of gutter 5550m² can collect up to 50m² of roof area

External gutter to have a 10mm offset in accordance with E1/AS2:NZS3500 figure F1

Downpipe(s):
Selected 80Ø downpipe



Legend:

27mm x 0.6 strip brace installed diagonally opposing pair of roof plane bracing with tensioners

Dwelling line below

Fall direction

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | DRAWN: SG
PROJECT #: CTL309 | CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

ROOF PLAN
SCALE 1:100 @ A3


STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A205**



Wall brace legend:



Wall bracing to be read in conjunction with wall bracing calculations

Bracing done in accordance with GIB Ezybrace system table 1: 10mm GIB plasterboard ratings

Bracing Legend:

GS1/GS2
GIB Standard bracing element

BL1
GIB Braceline bracing element

BLP
GIB Braceline + plywood

EP1/EPBS
Plywood bracing element

A — Bracing line in accordace with GIB Ezybrace system

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: CTL309
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

BRACING PLAN

SCALE 1:100 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE

ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A206**

88.78 m² total H1 dwelling area
4.76 m²
6.70 m²
1.90 m²



25.96 m² total unit H1 area
5.49 m²

Legend:

- Recessed ca rated led downlight
- Pendant led downlight
- Recessed exterior soffit downlight
- Mechanical vent ducting
- Switch
- Smoke detector
- Heated towel rail

All recessed lights to be LED or CA rated

Minimum 20 lux of natural or artificial light required at floor level at all times when the room is inhabited as per NZBC G8, *artificial light*.

Note:
All electrical work to be confirmed with a walk through with a qualified electrician

H1 Calculations:

(yellow fill indicative of thermal envelope)

Compressed insulation area
500mm perimeter allowed for as compressed insulation R value based on worst case (15° @ 500mm wide)
R-values calculated
(design navigator, see H1 calculations for complience with calculation method)
- Ceiling 1 R7.2
- Ceiling 2 R4.38
- Wall Axon R1.66
- Wall Graphex R2.34
- Foundation R2.0
- Glazing R0.50

Note:
For simplisity calculations have taken the lower wall value

Product	1.6	1.8	2	2.2	2.4	2.6	2.8	3	< A/P Ratio
MAXSlab Base 300	1.5	1.6	1.8	1.9	2	2.15	2.3	2.4	< R-value
MAXSlab Base 300 Brick	1.9	2.1	2.3	2.4	2.6	2.7	2.9	3	< R-value

Foundation A/P ratio 2.48

Smoke Detector
Interconnected smoke detector in accordance with NZS4514:2021
(Hardwired unless otherwise specified)

(*Where wirless detectors are used*
Smoke alarms must be either 10-year long-life battery-operated (non-removable/sealed), DC low voltage or 240v mains-powered and interconnected.)

To be installed to ALL bedrooms, living areas, hallways and landings.

Where installed within kitchens seperated by doors shall be a heat detector

Detectors shall be installed to the ceiling lining unless specified otherwise and shall:
- Flat ceilings or slops less than 1 in 10 shall be installed 200mm min from the wall
- Ceilings where slopes are greater than 1 in 10 (5° pitch) on the high side of the ceiling between 200 - 500mm from apex

- Not be installed within 300mm from a light fixture
- greater than 1m from a cooktop (where possible greater than 3m)
- Not be installed within 400mm from an opening of air conditioning or ventilation.

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz


ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

ELECTRICAL PLAN


SCALE 1:100 @ A3

STATUS: **WD-A** WORKING DRAWING
SHEET: **A207**
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA



ELEVATION 1 (SOUTH)

SCALE 1:100





ELEVATION 2 (WEST)

SCALE 1:100

ELEVATION 4 (EAST)

SCALE 1:100



ELEVATION 3 (NORTH)

SCALE 1:100

Material Selections:

Roof Cladding:
Trim Rib 0.4 BMT Colorcote Zinacore metal profiled roofing on self supporting roofing underlay on SG8 timber purlins on structural roof framing

Wall Cladding 1:
Rockcote Graphex 50mm plaster cladding system on 20mm cavity

Wall Cladding 2:
James Hardie Axon 133mm cladding system over CLD 20mm cavity battens with Danban over flexible wall underlay

Allow dwangs to be installed as per the cladding manufacturers requirments

Joinery (External):
Powder coated thermally broken double glazed aluminium joinery Argon with low E glass

Joinery (Internal):
Hollow core internal door (refer to plan for leaf size)

Hung Doors
1980mm (trim size 2040mm high, door width + 55mm)
Cavity Slider
2070mm high (2x door width +30mm)
Robe sliders
2040mm high
2 door (2x door width + 30mm)
3 door (3x door width + 10mm)

Safety Glazing:
'SG' safety glazing in accordance with NZS 4223 part 3:2016

'RS' Restrictor stay

BUILDING ENVELOPE RISK MATRIX		
ALL ELEVATIONS		
Risk Factor	**Risk Severity**	**Risk Score**
Wind zone (per NZS 3604)	High risk	1
Number of storeys	Low risk	0
Roof/wall intersection design	Very high risk	5
Eaves width	High risk	2
Envelope complexity	Medium risk	1
Deck design	Low risk	0
Total Risk Score:		**9**

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

ELEVATIONS


SCALE 1:100 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE


ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A301**



CROSS SECTION A-A

SCALE 1:50



CROSS SECTION B-B

SCALE 1:50

General Notes:

1 All framing to be SG8 unless specified otherwise. Refer to floor plan for spacings

Material Selections:

Roof cladding:
Trim Rib 0.4 BMT Colorcote Zinacore metal profiled roofing on self supporting roofing underlay on SG8 timber purlins on structural roof framing

Fascia + Gutter:
Selected 180mm Fascia and Gutter profile

Purlins:
70x45 SG8 H1.2 timber purlins @ 900mm crs with top and bottom spans at 600mm spacing. Fixing with 1/10g self-drilling screw 80mm long

Soffit lining:
4.5mm James Hardie hardiesoffit lining with PVC jointers

Wall cladding 1:
Rockcote Graphex 50mm plaster cladding system on 20mm cavity

Wall cladding 2:
James Hardie Axon 133mm cladding system over CLD 20mm cavity battens with Danban over flexible wall underlay

Underlay(s):
- Thermakraft Covertek 215 roofing underlay
- Mason Uniplus flexible underlay

Joinery:
Powder coated thermally broken double glazed aluminium joinery Argon with low E glass

Insulation:
R2.8 wall batts
R7.0 ceiling batts

Wall linings:
10mm gib standard plaster board
10mm gib aqualine to bathroom / ensuite

Ceiling linings:
13mm gib standard plaster board
13mm gib aqualine to bathroom / ensuite

Ceiling battens:
35mm metal battens at 600crs generally

Safety glazing:

'SG' safety glazing in accordance with NZS 4223 part 3:2016

'RS' Restrictor stay

Framing size and treatment:

90x45 H1.2 single top plate
140x35 H1.2 fixing plate

Note:
Engineers drawings take precedence over all engineered members indicated on the architectural plans. Any discrepency please contact the architect.

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz


ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

CROSS SECTION
SCALE 1:50 @ A3


STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A401**



CROSS SECTION C-C

SCALE 1:50



CROSS SECTION D-D

SCALE 1:50

General Notes:

1 All framing to be SG8 unless specified otherwise. Refer to floor plan for spacings

Material Selections:

Roof cladding:
Trim Rib 0.4 BMT Colorcote Zinacore metal profiled roofing on self supporting roofing underlay on SG8 timber purlins on structural roof framing

Fascia + Gutter:
Selected 180mm Fascia and Gutter profile

Purlins:
70x45 SG8 H1.2 timber purlins @ 900mm crs with top and bottom spans at 600mm spacing. Fixing with 1/10g self-drilling screw 80mm long

Soffit lining:
4.5mm James Hardie hardiesoffit lining with PVC jointers

Wall cladding 1:
Rockcote Graphex 50mm plaster cladding system on 20mm cavity

Wall cladding 2:
James Hardie Axon 133mm cladding system over CLD 20mm cavity battens with Danban over flexible wall underlay

Underlay(s):
- Thermakraft Covertek 215 roofing underlay
- Mason Uniplus flexible underlay

Joinery:
Powder coated thermally broken double glazed aluminium joinery Argon with low E glass

Insulation:
R2.8 wall batts
R7.0 ceiling batts

Wall linings:
10mm gib standard plaster board
10mm gib aqualine to bathroom / ensuite

Ceiling linings:
13mm gib standard plaster board
13mm gib aqualine to bathroom / ensuite

Ceiling battens:
35mm metal battens at 600crs generally

Safety glazing:
'SG' safety glazing in accordance with NZS 4223 part 3:2016
'RS' Restrictor stay

Framing size and treatment:
90x45 H1.2 single top plate
140x35 H1.2 fixing plate

Note:
Engineers drawings take precedence over all engineered members indicated on the architectural plans. Any discrepency please contact the architect.

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

CROSS SECTION
SCALE 1:50 @ A3


STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A402**


CLEARANCES (mm)

MASONRY VENEER		OTHER CLADDINGS	
A	125	A	150
B	200	B	225
C	25	C	100
D	100	D	175
E	100	E	50




D01 CLADDING CLEARANCES

Scale NTS




D02 JOINERY SILL DETAIL

Scale 1:5



D03 REBATED JOINERY SILL DETAIL

Scale 1:5



Note:
Refer to engineers documentation for ground works requirments

D04 ENGINEERED FOOTING DETAIL (NO REBATE)

Scale 1:5 *Note: refer to engineers design and documentation*

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz


ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
CHECKED: CG
PROJECT #: **CTL309**

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:5 @ A3


STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A501**




D01 EAVE DETAIL

Scale 1:10



D02 BARGE DETAIL

Scale 1:10



Soaker flashing for Pipe penetrations

**suitable for pipes from 86mm to 500mm dia.*
Suitable only for roof pitches of 10° or more

'x' 130mm wind zones up to and incl high wind zone
200mm very and extra high wind zone


Small Pipe Note:
1. Max. Roof pitch for this flashing 45°, minimum pitch 10°
If base of flange covers one or more complete troughs

2. For pipes up to 85mm dia.

Flashing for small pipes


D03 PIPE PENETRATIONS DETAIL

Scale 1:10




D04 POST / BEAM DETAIL

Scale 1:10



D05 POST / BEAM CONNECTION DETAIL

Scale 1:10



D06 POST FOOTING DETAIL

Scale 1:10

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | *DRAWN:* SG | *CHECKED:* CG

PROJECT #: **CTL309**

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission


DETAILS
SCALE 1:10 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE


ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A502**




D01 JOINERY HEAD TO SOFFIT DETAIL

Scale 1:5




D03 RIDGE PROFILE DETAIL

Scale 1:5



D02 PARALLEL APRON FLASHING DETAIL

Scale 1:5



Note: all dimensions stated are minimum sizes

D04 VALLEY PROFILE DETAIL

Scale 1:5

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | *DRAWN:* SG

PROJECT #: **CTL309** | *CHECKED:* CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission


DETAILS
SCALE 1:5 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A503**





Refer TradeSpec™ Document 1.2 for information on Ground Clearances

TradeSpec™ and RenderSpec™ are Registered Trademarks, both Documents are available on the Resene Construction Systems

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Scale: 1 : 2 @ A4
Substrate: Graphex Panel 50mm (20mm Cavity)
Date:
Drawing Name: Batten Layout (600mm Centres)
Sheet: 71.01.00

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Scale: 1 : 2 @ A4
Substrate: Graphex Panel 50mm (20mm Cavity)
Date: 1 November 2017
Drawing Name: Foundation
Sheet: 71.02.00

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES


Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz


ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
CHECKED: CG
PROJECT #: **CTL309**

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING
SHEET: **A504**
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA





Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System
Insulated Facade System

Scale
1 : 2 @ A4

Substrate
Graphex Panel 50mm (20mm Cavity)

Date
1 November 2017

Drawing Name
External Corner

Sheet
71.03.00

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System
Insulated Facade System

Scale
1 : 2 @ A4

Substrate
Graphex Panel 50mm (20mm Cavity)

Date
1 November 2017

Drawing Name
Internal Corner

Sheet
71.04.00

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission


DETAILS
SCALE 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET:
A505





Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Scale: 1 : 2 @ A4
Substrate: Graphex Panel 50mm (20mm Cavity)
Date: 1 November 2017
Drawing Name: Soffit
Sheet: 71.08.00

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Scale: 1 : 2 @ A4
Substrate: Graphex Panel 50mm (20mm Cavity)
Date: 1 November 2017
Drawing Name: Internal Corner with Fibre Cement Sheet - Option 1
Sheet: 71.04.30

EVERY HOME BEGINS WITH YOU


LATITUDE HOMES


Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A506**





Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Scale: 1 : 2 @ A4
Substrate: Graphex Panel 50mm (20mm Cavity)
Date: 4 November 2020
Drawing Name: Window Jamb
Sheet: 71.06.00

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Scale: 1 : 2 @ A4
Substrate: Graphex Panel 50mm (20mm Cavity)
Date: 4 November 2020
Drawing Name: Window Head - Option 1
Sheet: 71.07.00

EVERY HOME BEGINS WITH YOU


LATITUDE HOMES


Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
CHECKED: CG
PROJECT #: **CTL309**

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A507**





Allow a 25mm Gap between the back of the joinery and external facing timber framing to allow the sill flashing to fit.

The responsibility for the penetration is the responsibility of the main contractor, where possible and practical use a flange.

It is important that there is adequate support for the penetration in the form of timber packing. The penetration should be angled slightly away from the cladding so any moisture is diverted away from the cladding.

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Substrate: Graphex Panel 50mm (20mm Cavity)
Drawing Name: Window Sill
Scale: 1 : 2 @ A4
Date: 4 November 2020
Sheet: 71.05.00

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: Insulated Facade System
Substrate: Graphex Panel 50mm (20mm Cavity)
Drawing Name: Pipe Penetration
Scale: 1 : 2 @ A4
Date: 1 November 2017
Sheet: 71.12.20

EVERY HOME BEGINS WITH YOU


LATITUDE HOMES


Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
PROJECT #: CTL309
DRAWN: SG
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: A508





Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System
Insulated Facade System

Scale
1 : 2 @ A4

Substrate
Graphex Panel 50mm (20mm Cavity)

Date
1 November 2017

Drawing Name
Garage Door Head - Option 1

Sheet
71.07.50

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System
Insulated Facade System

Scale
1 : 2 @ A4

Substrate
Graphex Panel 50mm (20mm Cavity)

Date
1 November 2017

Drawing Name
Garage Door Jamb - Option 1

Sheet
71.06.50

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
PROJECT #: **CTL309**
DRAWN: SG
CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET:
A509



jhl_axon24_c_001

jhl_axon24_c_ktaltd.rvt


JamesHardie™
www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay

March 2024
Scale: 1 : 25

FRAMING SETOUT

Figure 1



jhl_axon24_c_004

jhl_axon24_c_ktaltd.rvt

JamesHardie™
www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay

March 2024
Scale: 1 : 2

INSULATED FOUNDATION DETAIL

Figure 4

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1.1002, 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A510**



jhl_axon24_c_030 jhl_axon24_c_ktaltd.rvt


JamesHardie™ www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay

HORIZONTAL JOINT IN TALL WALL

March 2024
Scale: 1 : 2

Figure 30



Note: Site cut edges to be primed.
Ensure cavity does not vent into roof space. Refer to E2/AS1 clause 9.1.8.2.

jhl_axon24_c_020 jhl_axon24_c_ktaltd.rvt

JamesHardie™ www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay

SOFFIT DETAIL

March 2024
Scale: 1 : 2

Figure 20

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
CHECKED: CG
PROJECT #: **CTL309**


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A511**



jhl_axon24_c_010

jhl_axon24_c_ktaltd.rvt


JamesHardie™
www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay

March 2024
Scale: 1 : 2

EXTERNAL CORNER - BOX

Figure 10



jhl_axon24_c_009

jhl_axon24_c_ktaltd.rvt

JamesHardie™
www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay

March 2024
Scale: 1 : 2

HARDIE™ 9mm ALUMINIUM INTERNAL CORNER

Figure 9

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: CTL309
CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3


STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET:
A512



Note: When HomeRAB™ Pre-Cladding/RAB™ Board is used flashing tape to be applied to the entire window opening.



General notes for materials selection

* Flexible underlay must comply with acceptable solution E2/AS1.
* Flashing tape must have proven compatibility with the selected flexible underlay and other materials with which it comes into contact.

Refer to the manufacturer or supplier for technical information for these materials.

jhl_axon24_c_024 | jhl_axon24_c_ktaltd.rvt

JamesHardie™ www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay
WINDOW JAMB
March 2024
Scale: 1 : 2
Figure 24

jhl_axon24_c_023 | jhl_axon24_c_ktaltd.rvt

JamesHardie™ www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay
WINDOW SILL
March 2024
Scale: 1 : 2
Figure 23

EVERY HOME BEGINS WITH YOU


LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | *DRAWN:* SG
PROJECT #: **CTL309** | *CHECKED:* CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A513**




Note:

* When HomeRAB™ Pre-Cladding/RAB™ Board is used flashing tape to be applied to the entire window opening.
* Also refer to Figure 116 NZBC clause E2/AS1 for head and jamb details
* Sealant must be applied between head flashing and window flange VH and EH wind zones and SED wind pressures

jhl_axon24_c_022 jhl_axon24_c_ktaltd.rvt

JamesHardie™ www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay
WINDOW HEAD
March 2024
Scale: 1 : 2
Figure 22



Note: When 50 year durability for flashing is required refer to Table 20 NZBC E2/AS1 document

jhl_axon24_c_046 jhl_axon24_c_ktaltd.rvt

JamesHardie™ www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay
ONE PIECE APRON FLASHING JOINT
March 2024
Scale: 1 : 2
Figure 46

EVERY HOME BEGINS WITH YOU


LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 *DRAWN:* SG
PROJECT #: CTL309 *CHECKED:* CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A514**



Note: Site cut edges to be primed

jhl_axon24_c_040 jhl_axon24_c_ktaltd.rvt

JamesHardie™
www.jameshardie.co.nz

Axon™ Panel
Hardie™ CLD™ Batten With Flexible Underlay

CAVITY PIPE PENETRATION

March 2024
Scale:

Figure 40

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 *DRAWN:* SG
PROJECT #: **CTL309** *CHECKED:* CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

DETAILS
SCALE 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A515**



- Plaster Systems AAC Adhesive to be used to mortar all Integra Panel Joins
- Cavity size to be 20-40mm wide
- Studs to be located at a maximum of 600 centre and dwangs/nogs at 800mm centres.Where there is a need for fire-stopping, mineral wool or ceramic fibre cavity insulation must be used, the wool/insulation should have a minimum density of 40kg/m³, or as specified by a fire engineer
- Where fire separations meet other fire separations or fire rated parts of external walls, they shall have the junction fire stopped over its full length
- The Integra Intertenancy System shall terminate as close as possible to the external roof cladding and primary elements providing roof support, with any gaps fully fire stopped
- Acoustic Sealant to be applied to the perimeter of the Intertenancy wall to which the plasterboard linings have been fastened. The acoustic sealant should also be used to seal around any penetrations to ensure no gaps are left.

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: INTEGRA Lightweight Concrete Intertenancy System


Substrate: Terraced Housing - Timber Frame

Drawing Name: Wall Plan

Scale: NTS

Date: 1 December 2018

Sheet: 34.19.06



- Plaster Systems AAC Adhesive to be used to mortar all Integra Panel Joins
- Cavity size to be 20-40mm wide
- Studs to be located at a maximum of 600 centre and dwangs/nogs at 800mm centres.Where there is a need for fire-stopping, mineral wool or ceramic fibre cavity insulation must be used, the wool/insulation should have a minimum density of 40kg/m³, or as specified by a fire engineer
- Where fire separations meet other fire separations or fire rated parts of external walls, they shall have the junction fire stopped over its full length
- The Integra Intertenancy System shall terminate as close as possible to the external roof cladding and primary elements providing roof support, with any gaps fully fire stopped
- Acoustic Sealant to be applied to the perimeter of the Intertenancy wall to which the plasterboard linings have been fastened. The acoustic sealant should also be used to seal around any penetrations to ensure no gaps are left.

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: INTEGRA Lightweight Concrete Intertenancy System

Substrate: Terraced Housing - Timber Frame

Drawing Name: Foundation or Intermediate Floor Slab

Scale: 1 : 5 @ A4

Date: 1 December 2018

Sheet: 34.19.10

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
PROJECT #: **CTL309**
DRAWN: SG
CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission


DETAILS
SCALE 1:1, 1:1.0322 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A516**





- Plaster Systems AAC Adhesive to be used to mortar all Integra Panel Joins
- Cavity size to be 20-40mm wide
- Studs to be located at a maximum of 600 centre and dwangs/nogs at 800mm centres.Where there is a need for fire-stopping, mineral wool or ceramic fibre cavity insulation must be used, the wool/insulation should have a minimum density of 40kg/m³, or as specified by a fire engineer
- Where fire separations meet other fire separations or fire rated parts of external walls, they shall have the junction fire stopped over its full length
- The Integra Intertenancy System shall terminate as close as possible to the external roof cladding and primary elements providing roof support, with any gaps fully fire stopped
- Acoustic Sealant to be applied to the perimeter of the Intertenancy wall to which the plasterboard linings have been fastened. The acoustic sealant should also be used to seal around any penetrations to ensure no gaps are left.

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: INTEGRA Lightweight Concrete Intertenancy System
Scale: 1 : 5 @ A4
Substrate: Terraced Housing - Timber Frame
Date: 15 March 2021
Drawing Name: T-Junction with External Wall - Option 1
Sheet: 34.19.61

- Plaster Systems AAC Adhesive to be used to mortar all Integra Panel Joins
- Cavity size to be 20-40mm wide
- Studs to be located at a maximum of 600 centre and dwangs/nogs at 800mm centres.Where there is a need for fire-stopping, mineral wool or ceramic fibre cavity insulation must be used, the wool/insulation should have a minimum density of 40kg/m³, or as specified by a fire engineer
- Where fire separations meet other fire separations or fire rated parts of external walls, they shall have the junction fire stopped over its full length
- The Integra Intertenancy System shall terminate as close as possible to the external roof cladding and primary elements providing roof support, with any gaps fully fire stopped
- Acoustic Sealant to be applied to the perimeter of the Intertenancy wall to which the plasterboard linings have been fastened. The acoustic sealant should also be used to seal around any penetrations to ensure no gaps are left.

Resene Construction Systems

CONFIDENTIALITY: No part of this publication may be reproduced or transmitted other than the intended use by Resene Construction Systems without written consent from the author.

System: INTEGRA Lightweight Concrete Intertenancy System
Scale: 1 : 5 @ A4
Substrate: Terraced Housing - Timber Frame
Date: 1 December 2018
Drawing Name: Roof Truss Section
Sheet: 34.19.90

EVERY HOME BEGINS WITH YOU


LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: CTL309
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission


DETAILS
SCALE 1:1.0309, 1:1, 1:1.0249 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A517**



Note:
Where impact noise from pipes is an issue, fix all pipes on resilient brackets


D01 ARCYLIC SHOWER

Scale 1:10



D02 TYPICAL WATER -SPLASH AREA JUNCTIONS

Scale 1:10



D03 VINYL FLOOR TO WALL JUNCTIONS

Scale 1:10

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

WET AREA DETAILS
SCALE 1:10 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE
ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A518**




Placement option 1 **Placement option 2**

Table 4 NZBC G12/AS1
tempering valve and nominal pipe diameters

	low pressure (i.e header tank supply or low pressure)	low and medium pressure unvented (valve vented) and and open vented	mains pressure
pressure of water at tempering valve (kpa)	20-30	30-120	over 300
metres head (m)	2-3	>3-12	over 30
minimum tempering valve size	25mm	20mm	15mm
pipes to tempering valve	25mm (see note 3)	20mm	20mm (15mm optional) (see note 1)
pipes to shower	20mm	20mm (see note 4)	20mm (see note 5) (15mm optional) (see note 1)
pipes to sink/laundry (see note 2)	20mm	20mm	15mm
pipes to bath (see note 2)	20mm	20mm	15mm
pipes to basins (see note 2)	15mm	15mm	10mm

notes:
1. If supplied by seperate pipe from storage water heater to a single outlet.
2. This table is based on maximum pipe lengths of 20 metres.
3. 2m maximum length from water heater outlet to tempering valve.
4. 15mm if dedicated line to shower.
5. 10mm if dedicated line to shower.

Figure 8 NZBC G12/AS1
mains pressure storage water heater system (unvented)



HWC NOTES
Electric storage hot water heaters shall have a minimum insulation material thickness of 25mm. The insulation material shall have a thermal conductivity of less than 24mW/M°C when tested to ASTM C518-76.
COMPLIANCE
Electric storage heater complies with NZS 4606; parts 1, 2 and 3, AS 1056:Part 1
See plans for location and installation details

NZBC G12/AS1
6.14.3 Legionella bacteria
Irrespective of whether a mixing device is installed, the storage water heater control thermostat shall be set at a temperature of not less than 60°C to prevent the growth of Legionella bacteria.

7.2 Protection from freezing
7.2.1 Where there is the likelyhood of freezing, hot and cold water supply systems shall be protected in the following manner:

a) Piping outside the building thermal envelope shall be insulated,

b) Piping buried in the ground shall be insulated or insulated below a level affected by freezing, and

c) Storage water heater vent pipes shall be insulated (see Figure 17).

7.2.2 In climates where freezing temperatures are likely for a period of greater than 24 hours an expansion control valve is required in addition to vent pipe insulation (see Figure 17)

Notes:
1. An additional centre strap is required where a storage water heater is located more than 12 m above finished ground level.
2. Additional timber framing may be required in retrofit situations to ensure adequate strap fixing is available.
3. Straps shall not be installed where they clash with water heater inlets, outlets or controls.
4. Where the 100 mm maximum strap distance from the top or bottom of the storage water heater cannot be achieved, straps may be placed within the top and bottom 25% with one additional strap placed centrally for water heaters < 200 litres, and two additional evenly spaced straps for water heaters 200 - 360 litres.
5. A maximum total of four straps are required when complying with both Note 1 and Note 4

D01 MAINS PRESSURE HWC AND SEISMIC RESTRAINT
Scale 1:10 *NZBC G12 / AS1*

EVERY HOME BEGINS WITH YOU
LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | *DRAWN:* SG
PROJECT #: **CTL309** | *CHECKED:* CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission


HWC DETAILS
SCALE 1:10 @ A3


STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA


SHEET: **A519**

TOP PLATE CONNECTIONS		
WALL TYPE	**BRACING IN WALL**	**TOP PLATE CONNECTION CAPACITY**
ALL WALLS	NO BRACING	3kN
IN-LINE WALLS	BRACING CAPACITY NOT EXCEEDING 100BU's	3kN
	BRACING CAPACITY EXCEEDING 100BU's	6kN
WALL CONNECTING TO EXTERNAL WALL AT RIGHT ANGLES	TOTAL BRACING CAPACITY NOT EXCEEDING 125BU's	6kN TO 1 EXTERNAL WALL
	BRACING CAPACITY NOT EXCEEDING 250BU's	6kN TO 2 EXTERNAL WALLS
	BRACING CAPACITY EXCEEDING 250BU's	2.4kN PER 100BU's TO 2 EXTERNAL WALLS

Note:
For up to 12kn connections use 2x6kN strap or 12/90x2.15 nails for nail fix option.
For up to 18kn connections use 3x6kn strap







15kN BRACING HOLDDOWN DETAIL GIB HANDIBRAC


All fixings in accordance with GIB manufacturers documentation SCALE 1:10

Panel hold down for GIB Braceline panels concrete floor external / internal wall

Note:
GIB GS1-N and GS2-N and James Hardie HPn do not require specific connections at brace ends


FASTENER LAYOUT

GS1-N/BL1-H (10 & 13mm) - SINGLE SIDE
GS2-N/BLG-H (10 & 13mm) - 2 SIDED. BOTH SIDES FIXED AS SHOWN



SYSTEM	LINING ONE SIDE (1)		LINING OPPOSITE SIDE (2)		PANEL HOLD DOWN (3)	FASTNER SPACING
	LINING	FASTNERS	LINING	FASTNERS		
GS1-N	Any 10mm Or 13mm GIB Plasterboard	30mm GIB nails, Or minimum 32mm x 6g GIB Grabber Drywall screws	Not required	Not required	Not required	Gib plasterboard: Corner fastening pattern as illustrated below Fastners at 150mm to bracing element perimeter and: - at 300mm centres to intermediate sheet joints for vertical fixing, or - at stud/sheet junction for horizontally fixed elements, and - gibfix adhesive daubs at 300mm centres to intermediate framing Plywood: Fastners at 150mm centres around the perimeter of every sheet and at 300mm centres To intermediate studs. Place fastners no closer than 7mm from sheet edges. Plasterboard corner fastner pattern does not apply to plywood
GS2-N			Any 10mm Or 13mm GIB Plasterboard	30mm GIB nails, Or minimum 32mm x 6g GIB Grabber Drywall screws		
GSP-H			Minimum 7mm Ecoply plywood Manufactured To as/nzs 2269	50mm fh Galvanised or Stainless steel Nails	YES	
BL1-H	10mm or 13mm Braceline	32mm x 6g GIB Grabber Drywall screws GIB braceline Nails may be Used for 10mm Braceline only	NOT REQUIRED	NOT REQUIRED		
BLG-H			Any 10mm Or 13mm GIB Plasterboard	30mm GIBnails, Or minimum 32mm x 6g GIB Grabber Drywall screws		
BLP-H			Minimum 7mm Ecoply plywood Manufactured To AS/NZS 2269	50mm fh Galvanised or Stainless steel Nails		

CORNER FASTENER PATTERN



EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | DRAWN: SG
PROJECT #: CTL309 | CHECKED: CG


COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

APPENDIX 01 (BRACING)

SCALE 1:10 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A520**

LUMBERLOK STUD TO TOP PLATE FIXING TYPES

TYPE A
0.7kN




2 x 90mm x 3.15 dia. plain steel wire nails driven vertically into stud.

TYPE B
4.7kN


CHOOSE ANY OF THE 3 OPTIONS

2 x 90mm x 3.15 dia. plain steel wire nails driven vertically into stud.




Plus LUMBERLOK 6kN Stud Anchor (CPC80)

2 x 90mm x 3.15 dia. plain steel wire nails driven vertically into stud.




Plus 2 x LUMBERLOK CPC40

2 x 90mm x 3.15 dia. plain steel wire nails driven vertically into stud.




Plus LUMBERLOK Stud Strap (ONE FACE ONLY)

ACCEPTABLE SOLUTIONS IN CONJUNCTION WITH TABLES 8:14 & FIG 8:12 OF NZS3604:2011



1. For trimming stud thickness refer to Table 8.5 NZS 3604:2011. Additional studs to that shown to have a minimum stud to stud fixing of 11/90*3.15 nails.
2. Where a double stud which provides support for a lintel is shorter by 400mm or more than the full stud height, its thickness shall not be included as contributing to the thickness of trimming studs.
3. Studs & jacks to be fixed to top plate in accordance with the Top Plate to Stud Fixing Guide on pg. 39. Same fixing is required for jack stud to lintel.

Alternative solution for L3 & L4 SBS use



EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | DRAWN: SG
PROJECT #: **CTL309** | CHECKED: CG


COPYRIGHT: This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

APPENDIX 02 (FIXINGS)
SCALE 1:10, 1:1 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A521**

JACK STUD TO TOP PLATE & LINTEL FIXING

PROVIDES A SOLUTION FOR ALL JACK STUD LENGTH FIXING OPTIONS

- Covers the requirements for LUMBERLOK® Stud to Top Plate fixing "Type b -4.7kN" as require by LUMBERLOK® Lintel Fixing Schedule
- Wall framing and connection details under girder trusses are not covered by this fixing soultion and are subject to specific engineering design
- All timber selections are as per NZS 3604:2011



AVAILABLE FROM LEADING BUILDERS SUPPLY MERCHANTS THROUGHOUT NEW ZEALAND

MiTek®
LUMBERLOK®
Timber Connectors


www.miteknz.co.nz

© Copyright 2020 MiTek Holdings, Inc. All rights reserved. Mar 2020

JACK STUD TO TOP PLATE & LINTEL FIXING

FRAMING ARRANGEMENTS

Jack Stud Dimension Definition (JSD)




* Note: It is preferable for the top fixing to be located on the uppermost top plate packer to provide better options for the truss connections

FIXING 1
Jack Stud Dimension (JSD) up to a maximum of 100mm. Includes top plate fixed directly onto lintel i.e. no jack stud used.

FIXING 2
Jack Stud Dimension (JSD) from a minimum of 100mm to a maximumof 430mm.

FIXING 3
Jack Stud Dimension (JSD) from a minimum of 270mm. No maximum dimension.



LUMBERLOK® Sheet Brace Strap
on one face

Note:
Fix jack stud with 2/ 90mm x 3.15 dia. nails from top plate and 2/ 90mm x 3.15 dia. skew nails to lintel (typical)

LUMBERLOK® Sheet Brace Strap
on one face. Fill 6 holes in shaded area with LUMBERLOK® Product Nails 30mm x 3.15 dia.

Note:
- JSD up to 230mm use Sheet Brace Strap 400mm.
- JSD from 230mm to 430mm use Sheet Brace Strap 600mm.

LUMBERLOK® Sheet Brace Strap
200mm on one face. Fill 6 holes in both shaded areas of Jack Stud and Lintel with LUMBERLOK Product Nails 30mm x 3.15 dia

MiTek®

www.miteknz.co.nz

© Copyright 2020 MiTek Holdings, Inc. All rights reserved Mar 2020

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
PROJECT #: **CTL309**
CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

APPENDIX 03 (JACK STUD FIXINGS)
SCALE @ A3

STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET: **A522**

Roof Bracing Options


i) ROOF PLANE BRACE

Each roof plane brace can be:

- A hip or valley rafter running continuously from ridge to the top plate in accordance with NZS 3604:2011 Clauses 10.2.1.3.2 or 10.2.1.3.3

OR

- A pair of tensioned and crossed LUMBERLOK Strip Brace running continuously from ridge to top plate installed as detailed below.



OVERHANG OPTIONS

- **All gable end loading parameters are based on the design considerations used in NZS 3604:2011 and cover heavy roof weight, extra high wind load and snow load Sg of up to 1.0kPa.**
- **All live load considerations as per AS/NZS 1170.**
- **All timber to be minimum grade SG8 as defined in NZS 3604:2011.**

CANTILEVER PURLIN OPTION





TABLE 1


PURLIN SIZE & ORIENTATION	MAX. CANTILEVER LENGTH (mm)	PURLIN CENTRES (mm)
45x45 ⊠	200	400
70x45 ⊠	300	900
90x45 ⊠	450	900

CONSTRUCTION DETAILS FOR CANTILEVER OUTRIGGER OPTION

(SPANS & CENTRES AS PER TABLE 2)



CROSS SECTION



LAYOUT

© Copyright 2017 MiTek Holdings, Inc. All rights reserved.

EVERY HOME BEGINS WITH YOU


LATITUDE HOMES


Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | DRAWN: SG
PROJECT #: CTL309 | CHECKED: CG


COPYRIGHT: This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

APPENDIX 04 (ROOF BRACING)
SCALE 1:10 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A523**





Code: TPS
Material: 1.55mm G300 Z275 Galvanised Steel
Packed: 8 x Top Plate Stiffeners per Carton
100 x Type 17-14g x 75mm Hex Head Galvanised Screws






Figure 2: Notches and holes in top plates. See Figure 3 if notches or holes are larger than shown.




Figure 3: Strengthening for large checks and holes in wall plates.




Figure 1: Notches and holes in studs. Space notches in studs at least 600 mm apart.

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | DRAWN: SG
PROJECT #: CTL309 | CHECKED: CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

APPENDIX 05 (PIPE PENETRATIONS)
SCALE 1:1 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A524**

Figure 14: Relationship of Pipe Trench to Building Foundation
Paragraph 3.9.7





Figure 8: Type-one Surface Water Sump
Paragraph 3.6.2








Figure 2 Gully trap dimensions and requirements.


Figure 13: Bedding and backfilling
Paragraphs 3.9.2, 3.9.4 and 3.9.5



(a) Cover greater than 500mm



(b) Cover greater than 375mm



(c) Cover greater than 125mm

NOTE:
1. Fill shall be:
-Ordinary fill where drains are located below gardens and open country.
-Compacted selected fill where the drains are located below residential driveways and similar areas subjected to light traffic.

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026
DRAWN: SG
CHECKED: CG
PROJECT #: **CTL309**

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

APPENDIX 06 (DRAINAGE)
SCALE 1:100 @ A3
STATUS: **WD-A** WORKING DRAWING
CLIENT: BROUGHAN RESIDENCE
ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA
SHEET: **A525**

Details: Rooftype 1 Ceiling Perimeter ☐ heated ☐ 7.20 m²°C/W

Type: Roof: Timber framed truss Roof, flat Ceiling

Timber framed truss Roof, flat Ceiling [view detail]

external surface 0.03

Roofing : generic - Metal Tiles with building paper

R-value: 0.01

Insulation :

Timber Frame & Cavity :

90mm rafters or joists @ 900mm, battens covered with insulation

Roof Frame Area: 5.0%	*Cavity Area: 95.0%*
Roof space (still air) 0.11	Roof space (still air) 0.11
Framing : *R-value: 0.75*	Pink(c)Batts(c) Superbatts R7.0 Ceiling - 460mm wide 7
	Insulation covering bottom chord ☑
	When using this option make sure that the insulation product is suitable - typically manufactured at 460mm width

Ceiling Lining : generic - gypsum Plasterboard 13mm

R-value: 0.06

internal surface 0.09

Non-IC-rated recessed downlights

Ceiling Area [m²]: Number of downlights: Clearance from lamp holder side [m]:

Details: Rooftype 1 Ceiling Perimeter ☑ heated ☐ 4.38 m²°C/W

Type: Roof: Timber framed truss Roof, flat Ceiling Perimeter (compressed Insulation)

Timber framed truss Roof, flat Ceiling Perimeter (compressed Insulation)

external surface 0.03

Roofing : generic - Metal trapezoidal Iron with building paper

R-value: 0.01

Timber Frame & Cavity :

90mm rafters or joists @ 900mm, battens covered with insulation

Roof Frame Area: 5.0%	*Cavity Area: 95.0%*
Framing : *R-value: 0.75*	Pink(c)Batts(c) Superbatts R7.0 Ceiling - 460mm wide 7
	Compressed Insulation Details
	Roof Slope 25 ° Perimeter Width 500 mm
	Wall Stud Width 90 mm Offset 0 mm
	Top Chord Lift 0 mm Top Chord Depth 90 mm
	Compression Constant 0.83
	Is a ventilation gap present? ☑ Is insulation inside chord base? ☐

Ceiling Lining : generic - gypsum Plasterboard 13mm

R-value: 0.06

internal surface 0.09

Details: Glazingtype 1 Opaque Door ☐ 0.50 m²°C/W

Type: generic Windows and Skylights

generic Windows and Skylights

Joinery: Thermally Broken Aluminium Frame

Glass: Double Pane: Low E4/Clear - Argon - Thermally improved Spacer (Ug 1.10)

R-value: 0.50

Solar Heat Gain Coefficient (SHGC): 0.56

Details: Walltype 1 Solid: C ◉ T ○ H ○ heated ☐ 1.66 m²°C/W

Type: Wall: Timber Frame with vented Cavity

Timber Frame with vented Cavity [view detail]

external surface 0.03

Cladding : James Hardie Axon Cladding 9mm

R-value: 0.04

Air Barrier : generic - Building paper

R-value: 0.01

Timber Frame & Cavity :

90mm deep, 45mm studs @ 600mm, dwangs @ 800mm

Wall Frame Area: 38.0% (default value)	*Cavity Area: 62.0%*
15-90mm vented cavity (all R-values on ext. side of cavity will be halved), R: 0.08	15-90mm vented cavity (all R-values on ext. side of cavity will be halved), R: 0.08
Framing : *R-value: 0.75*	Pink(c)Batts(c) Ultra R2.8 90mm Wall 2.8
	still Airgap: none *R-value: 0.00*

Wall Lining : generic - gypsum Plasterboard 10mm

R-value: 0.04

internal surface 0.09

Details: Walltype 1 Solid: C ◉ T ○ H ○ heated ☐ 2.34 m²°C/W

Type: Wall: Timber Frame with vented Cavity

Timber Frame with vented Cavity [view detail]

external surface 0.03

Cladding : Resene Construction Systems Graphex 50mm

R-value: 1.57

Air Barrier : generic - Vapour Membrane

R-value: 0.01

Timber Frame & Cavity :

90mm deep, 45mm studs @ 600mm, dwangs @ 800mm

Wall Frame Area: 38.0% (default value)	*Cavity Area: 62.0%*
15-90mm vented cavity (all R-values on ext. side of cavity will be halved), R: 0.08	15-90mm vented cavity (all R-values on ext. side of cavity will be halved), R: 0.08
Framing : *R-value: 0.75*	Pink(c)Batts(c) Ultra R2.8 90mm Wall 2.8
	still Airgap: none *R-value: 0.00*

Wall Lining : generic - gypsum Plasterboard 10mm

R-value: 0.04

internal surface 0.09

H1 R values: Design Navigator AS1 Edition 6

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 *DRAWN:* SG

PROJECT #: **CTL309** *CHECKED:* CG

COPYRIGHT: This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

APPENDIX 07 (H1)


SCALE @ A3

STATUS: **WD-A** WORKING DRAWING


CLIENT: BROUGHAN RESIDENCE

ADDRESS: 49 KOREKE LOOP, KOREKE RISE, HAWEA


SHEET: **A526**




D 01




D 02




D 03




D 04




D 05




D 06




W01




W02




W03




W04




W05




W06




W07




W08



W09



W10



W11

General Notes:

1. All windows are viewed from the exterior
2. External window and door dimensions are taken over reveal.
3. All joinery subject to site measure and confirmed onsite prior to fabrication
4. Safety glazing shall be in compliance with NZS 4223 Part 2016
5. All windows to have 19mm finished pine liners unless specified or requested otherwise
6. Internal door handles to be 1000mm above floor level unless specified or requested otherwise

EVERY HOME BEGINS WITH YOU

LATITUDE HOMES

Phone: 0800 776 777
Email: Jeremy@latitudehomes.co.nz
www.latitudehomes.co.nz

ISSUE DATE: 22 - 10 - 2026 | *DRAWN:* SG
PROJECT #: **CTL309** | *CHECKED:* CG

COPYRIGHT:
This plan remains the property of Latitude Homes and is provided for the use as described above and may not be used or reproduced in whole or in part without written permission

JOINERY SCHEDULE

SCALE 1:50, 1:1 @ A3

STATUS: **WD-A** WORKING DRAWING

CLIENT:
BROUGHAN RESIDENCE

ADDRESS:
49 KOREKE LOOP, KOREKE RISE, HAWEA

SHEET:
A601