Figure & Ground

P R O J E C T S P E C I F I C A T I O N

1 Jessies Crescent

Issued for Consent

PROJECT OVERVIEW

Scope

8 x Town house delevopment.

Address

Site Conditions

Wind Zone	L - Low Wind Speed
Earthquake Zone	Zone 3
Exposure Zone	Zone B - Low
Snow Loading Zone	Zone N5

© Productspec 2026

TABLE OF CONTENTS

Preliminaries & General....4
Project Overview - NBC General....4
Siteworks....11
Site & Scope....11
Excavation & Siteworks....12
Concrete....14
Thermakraft Underlay, DPM, DPC & Tapes....14
Waterproofing....18
Interior Wet Area Waterproofing Membrane Systems....18
Carpentry....21
Timber Framing....22
Workmanship & Materials....26
Hermpac Weatherboard Cladding Systems....35
GIB® Plasterboard Linings....40
Cladding....52
Schistwork....52
External Window & Door Joinery....54
Aluminium Windows & Doors....54
Glazing....58
Non-Structural Glazing....58
Insulation....61
Pink Batts Insulation....61
Roofing....67
Roofing Systems - Profiled Steel....67
Tiling....69
Tiling....69
Plumbing....78
Workmanship....79
Systems....81
Drainage....83
Workmanship....83
Drainlaying Elements....84
Electrical....86
Workmanship....86
Systems....88
Materials & Control....89

© Productspec 2026

1 PRELIMINARIES & GENERAL

1.1 Project Overview - NBC General

1.1.1 Contract Documents

The Contract Documents are complementary and comprise this Specification, the accompanying drawings, the NBC (National Building Contract) together with Schedules as specified below, any written documentation clarifications issued during tendering/estimating, any manufacturer/supplier information issued with this Specification, any list of agreed Subcontractors, the contract establishment letter and any other relevant correspondence, and any Site Instructions or additional details or instructions issued as Variations. (The National Building Contract will be emailed upon request).

If the Architect/Designer has not been engaged to administer the Contract or observe the works, then the term Architect/Designer, where referred to in this specification, means Contract Administrator.

These Project Specific Conditions supersede the Standard Conditions where they are in conflict. Refer any ambiguity or apparent discrepancy within or between any Contract Documents to the Architect/Designer, whose interpretation shall be binding on all parties.

Ensure that all Trades are aware of all Conditions and that subcontract prices are accepted on this basis, and in a form acceptable to the Registered Master Builders Federation or the Certified Builders Association. Ensure that all persons engaged on the works are aware of all items in this specification and on the drawings that may in any way affect their section of the works.

1.1.2 Site

Relevant site conditions are believed to be correctly represented in the Contract Documents, however the Contractor (and Subcontractors where appropriate) are requested to inspect the site to ascertain for themselves the nature and extent of the works and the rights and interests that may be interfered with in the execution of the works, as no claims for additional payment will be recognised on the grounds of insufficient description.

1.1.3 Adjacent Owners

Carry out whatever actions or precautions are required to avoid or to absolutely minimise noise, dirt, dust, access, etc. inconvenience or disruption of any nature to the adjacent owners or tenants. Indemnify the Principal against any claims arising from this source.

1.1.4 Protection

Take all appropriate precautions to protect all third party property, services, etc., and indemnify the Principal against any claims arising from the construction operations. Any damage to third party property caused by construction activities or failure to protect shall be rectified as soon as possible by the person causing the damage, or by appropriately qualified trades-persons employed by the person responsible for the damage if necessary.
Suspend operations during weather which would affect the quality of work in progress. Secure the

works as soon as possible against adverse weather, dust and vandals. Avoid structural damage that is caused by overloading.
Adequately protect all finished work and maintain until the date of Practical Completion. Each trade shall protect the work of all other trades, and each trade is responsible for making good any damage they cause to finished works. Arrange special protection as required for windows and doors, finished timber work, plumbing fittings and hardware, cabinets and other joinery, and similar items.

1.1.5 Responsibility

The Contractor will be held responsible for the full period of their legal responsibility in connection with this Contract for ensuring that all work execution, materials, and fittings, are completely in accordance with Contract requirements.
The Contractor is responsible to the Principal for the appropriateness and fitness, in relation to a reasonable expectation or requirement, of all of the materials and workmanship incorporated into the works by themselves or their subcontractors; for this reason few specific guarantees are required in these contract documents. The terms and conditions of any warranty or guarantee required or provided shall not in any way negate the minimum remedies available under common law as if no warranty or guarantee had been furnished.
No apparent expression of the Architect's/Designer's reasonable satisfaction shall be deemed to be acceptance of defective materials or workmanship within the terms of the Contract or to be an authority for any Variation except where such Variation is authorised as provided for in the Contract. Instructions that are given verbally are deemed to be instructions for proper execution of the works and do not involve extra charges.

Workmanship in all trades is required to be equal to or better than recognised good trade practice. The Contractor shall provide all necessary setting out information and component dimensions for subcontractors and shall check and be responsible for the accuracy of their work.

Should any tradesperson consider that the surface finish or general conditions of previous work are unsatisfactory to ensure a proper finish for their own work thereon, that tradesperson shall give immediate notice to the Contractor or Architect/Designer as appropriate and shall not proceed until all necessary improvements have been made. Failing such notice the trade concerned will not be relieved of responsibility for a poor finish due to such unsatisfactory condition.
Specialist Finishes Subcontractors are responsible for ensuring that substrates are completely appropriate for them to achieve first class results, and to this end shall, in sufficient time, instruct the Contractor with regard any fixings, primings, sealings or whatever for the substrate that vary in any way from the substrate manufacturer's standard recommendations. The Contractor shall advise the Architect/Designer with regard these variances, and not proceed until the Architect/Designer has agreed to them.

The Contractor and all Subcontractors affected shall be jointly and severally responsible for completion of the whole of the works in a completely watertight condition and shall therefore examine all details to be satisfied that this condition can be achieved. If any detail is considered unsatisfactory the Architect/Designer shall be notified immediately and he/she will then either interpret the detail to the Contractor's satisfaction, or accept responsibility for watertightness at the points in question, always assuming reasonable workmanship.

Ensure that all materials or items incorporated into any particular construction or finish are compatible and that their individual use is approved by the manufacturers and/or suppliers of the other parts of the system.
For all electronic/electrical/mechanical operating systems all work and all necessary materials and items incidental to the primary item specified, that are incorporated into the works, shall be such as to leave a neat, efficient, easily maintained and robust installation, completely in accordance with all of the recommendations of the primary items' manufacturers. Where appropriate, source all parts of a system from a single supplier or manufacturer.

The Contractor shall make provision for all temporary works and services required for the satisfactory completion of the contract works. The Contractor shall pay all associated costs and fees; carry out all necessary maintenance, alterations and servicing requirements; and remove temporary works and services on completion of the contract works. Temporary works and services shall comply with the requirements New Zealand Building Code.

1.1.6 Specification

This Specification covers contract administration, standards, materials quality, workmanship and the scope of works only: the exact nature of the works and all specialist items, descriptions, etc., are contained on the drawings, which also take full precedence.
All clauses in all specification sections apply to their full extent and meaning to the entire Contract.
Trade sections and paragraphs have been introduced into this specification for reference only and it shall not be construed that each trade section is a complete segregation of the materials and labour of that trade. The onus is on all trades to be conversant with any and all clauses which in any way affect their work.
(Be aware that the ‘scope’ noted in the ‘Project Overview’, and scope and general extent clauses within this specification, are included to provide a general indication only and must NOT be interpreted as schedules of quantities - the exact nature and extent of all aspects of the works are shown on the drawings).

1.1.7 Standards

New Zealand Standards (NZS), Australian Standards (AS), Joint Standards (AS/NZS), British Standards (BS), Acts of Parliament, Regulations made thereunder, Codes of Practice, and any specific Manufacturer's Instructions or Manufacturer's Recommendations that are referred to in these Contract Documents shall all be deemed to be the latest published edition thereof at the time of drawings issue, and shall be followed by the Contractor and all Subcontractors to the full extent applicable consistent with the intent of this Contract. Documents cited within other cited publications are deemed to form part of this specification.
Where Standards have a number of Divisions, e.g. AS/NZS 3500.1, AS/NZS 3500.2, etc., each of the Divisions relevant to this project is deemed to form part of this specification.
Retain current copies of significant cited documents and manufacturer's technical literature on the site.

1.1.8 Authorities and Charges

Comply with all relevant provisions of the NZ Building Code, and with all relevant territorial or statutory authority regulations, by-laws, obligations, etc. Give all required notices.

The Principal has obtained a Land Use Consent. The Principal has applied for and paid for the Project Information Memoranda, the Building Consent and other approvals required for the works to start. The PIM and Building Consent will be forwarded to the Contractor as quickly as possible after they are issued by the Territorial Authority. Note: It is an offence under the Building Act to carry out work not in accordance with a Building Consent.
Should the Building Consent be subject to any conditions which modify the requirements of the Contract Documents in any way, the Architect/Designer reserves the right to negotiate any or all of these modifying conditions with the Building Consent Authority. If after these negotiations additional work is required, it will be handled as a Variation to the Contract.

1.1.9 Code Compliance Certificate

The Principal will apply for the Code Compliance Certificate (CCC) and any other licenses or approvals for the building to be used. The Contractor is to obtains all required certificates, guarantees, Producer Statements, as-built drawings, etc., required for the CCC application as work proceeds, to facilitate application for the CCC as soon as the works are completed. For their part, the Principal hereby undertakes to apply for the CCC within one day of all required material being in hand. Likewise, the Contractor should have capacity available to attend as quickly as possible to any items identified by the Building Consent Authority as being required prior to the issue of the CCC.

1.1.10 Coordination of the Works

Coordinate the works of all trades to ensure efficient progress of the works. Ensure that all holes, sleeves, penetrations, supports, etc., that are required for services are correctly incorporated as work proceeds. Identify and sufficiently forward-notify the appropriate persons of all deadlines for the supply of fittings, components, information, etc.

1.1.11 Documents Interpretation

Except where they are clearly to the contrary, all dimensions are deemed to be to the bare surface of concrete, masonry, timber framing or other basic construction material. All figured dimensions take precedence over scaled sizes. Where any detail is included in more than one drawing the larger scale detail takes precedence. Where any ambiguity exists refer to the Architect/Designer for interpretation.
The word ‘provide' and the word ‘fix' used separately in the Documents shall be taken to mean ‘provide and fix' unless otherwise stated.
When the term ‘allow' occurs in the Documents, except with reference to Monetary Allowances, the cost of the item shall be at the risk of the Contractor.
The terms ‘approved', ‘directed', and ‘selected' when used in the Documents refers to the approval, direction or selection of or by the Architect/Designer. Please give adequate notice of when these decisions are required. ‘Architect/Designer' shall mean the Architect or Designer, their representative or any Consulting Engineer engaged by the Architect/Designer.

1.1.12 Work Shown and Mentioned

1.1.12.1 Work Shown and Mentioned

The Contract Documents show the extent and nature of the works but there is no warranty expressed or implied that they show each and every minor detail or item required to be included by the

Contractor. Should any material, structural member, fixing, or item or work appear to be inadequately described, yet obviously necessary for the neat, strong and satisfactory completion of the work, it shall be incorporated into the Contract Works.

1.1.13 Site Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance. Comply with the relevant provisions of the New Zealand Building Code, in particular Clause F5.

So far as is reasonably practicable and according to a PCBU's (person conducting a business or undertaking) primary duty of care, take all necessary steps required to make the site and the contract works safe, and to provide and maintain a safe working environment. Ensure that all those working on or visiting the site are aware of the site safety rules and are not unnecessarily exposed to hazards.

Each PCBU, so far as is reasonably practicable, must ensure the health and safety of workers, and that other people are not put at risk by its work. If more than one PCBU has a duty in relation to the same matter, each PCBU with the duty must, so far as is reasonably practicable, consult, co-operate with, and co-ordinate activities with all other PCBUs who have a duty in relation to the same matter. PCBUs can enter reasonable agreements with other PCBUs to meet their duties, but cannot contract out of their duties.

Notify WorkSafe as soon as possible when a notifiable event occurs. Take all reasonable steps to preserve the site of the notifiable event in accordance with WorkSafe requirements. Ensure that the site of the event is not disturbed until authorised otherwise by WorkSafe. Keep records of all notifiable events.

Scaffolding shall comply with all Statutory and Local Authority Regulations, with the WorkSafe 'Best Practice Guidelines for Scaffolding', AS/NZS 1576 (Scaffolding equipment), AS/NZS 4576 (Guidelines for Scaffolding), and AS/NZS 4994 (Roof edge scaffolding), and shall be maintained for the duration and removed on completion.

The use of ballistic fixings must absolutely comply with all relevant safety recommendations at all times. No rubbish fires are allowed on site. Portable/personal disc/tape players, radios and iPods must not be used anywhere on the site. No smoking on site, except in the designated location in accordance with the Smoke Free Environments Act 1990, the location of which will be determined by the Contractor, with the approval of the Principal.

A PCBU's primary duty of care includes, but is not limited to, so far as is reasonably practicable:
- providing and maintaining a work environment that is without risks to health and safety;
- providing and maintaining safe plant and structures;
- providing and maintaining safe systems of work;
- ensuring the safe use, handling and storage of plant, structures and substances;
- providing adequate facilities for the welfare at work of workers in carrying out work for the business or undertaking, including ensuring access to those facilities;

- providing any information, training, instruction, or supervision that is necessary to protect all persons from risks to their health and safety arising from work carried out as part of the conduct of the business or undertaking;
- monitoring the health of workers and the conditions at the workplace for the purpose of preventing injury or illness of workers arising from the conduct of the business or undertaking.

Before commencing work on the site, the Contractor shall prepare and submit to the contract administrator a health and safety plan. The health and safety plan shall include, but not be limited to:
- the health and safety of all people on the site and on other properties, and the general public;
- identification of existing and potential construction hazards and risks;
- safety procedures to eliminate, isolate or minimise construction hazards;
- the equipment to be used to minimise the hazards;
- the maintenance of a register of hazards for the site;
- the name and qualifications of the site safety person;
- emergency procedures;
- first aid facilities and safety equipment;
- the methodology for notifying, recording and investigating accidents and injuries.

Carry out all construction operations in accordance with the submitted health and safety plan.

1.1.14 Variations

The Architect/Designer will issue Site Instructions (SI) to amend or clarify the works. Upon receipt of a SI the Contractor shall immediately notify the Architect/Designer if they believes there are price or timing adjustment implications. The Architect/Designer will then issue a Variation Price Request (VPR) for pricing of the possible Variation by the Contractor, within the time stipulated, or within 10 days if no time is stipulated. If the Contractor does not return the VPR within the time stipulated the Architect/Designer will assess it at reasonable rates. Once agreement is reached on price and/or timing a Variation Order (VO) for the item will be issued. Note that works covered by a SI or a VPR must NOT be actioned until the VO is issued.

When a Variation is contemplated and timing does not allow SI and VPR action the Contractor is to advise, and record in the site diary, an estimate of price and timing implications. If accepted by the Architect/Designer, a VO will be issued immediately. The Contractor shall then co-operate with the Architect/Designer to establish agreed pricing.
Claims for Variations neither priced nor estimated prior to being put in hand (but considered valid) will be incorporated into Progress Payment Certificates or the Draft Final Accounts as claimed and accepted but with a proviso allowing 5 (five) days for written objections by either the Principal or the Contractor, to any aspect of them, for further consideration.

The Main Contractor's Variations Margin agreed pre-contract will be the maximum accepted for any trade unless higher rates are nominated pre-contract and are accepted. The Main Contractor's agreed Variations Margin shown shall be deemed to include all preliminary and general costs, overheads, variation processing costs, and profit. If no margin is given, a 5% overall margin will be applied.
Note that ‘loss of anticipated profit' claims consequent upon reduction of works extent will NOT be recognised, and that the cost of processing Variations is deemed to be included in the P & G

Allowance.
Also note that for Variations pricing all materials shall be charged at the actual net invoiced cost plus margin; i.e. recognised 'Trade Price', volume discounted where appropriate.

1.1.15 Cleaning and Completion

Clear construction debris and rubbish from the works at regular intervals, and additionally if so instructed by the Architect/Designer. Clean each space thoroughly before commencing any finishing works.

In preparation for the Practical Completion inspection carry out the following:
- Clean the works thoroughly, removing all debris, surplus materials, splashes, marks, temporary markings, etc. (All cleaning methods and materials shall be as recommended by the manufacturer of the item being cleaned).
- Remove protective wrappings and coverings unless otherwise directed.
- Touch up minor painting faults, carefully matching colour, and brushing out edges. Repaint any badly marked surfaces back to suitable break-lines.
- Adjust, ease and/or lubricate as required all doors, drawers, controls and other moving parts to ensure their efficient operation.
- Any other works required to leave all spaces ready for immediate occupation and all electronic/electrical/mechanical systems fully operational.
- Clean out all spoutings, gutters, downpipes, and gullies and flush out all drains.
- Clean all sanitary appliances and check all aspects of the water services.
- Thoroughly re-inspect all aspects of the works (and have any defects fully rectified) to be certain that the works are completely ready for the Practical Completion inspection - if an unreasonable number of items are noted by the Architect/Designer during the inspection it will be terminated and then rescheduled for at least a week forward to allow proper completion to be achieved.

(Note that a Code Compliance Certificate must be obtained before Practical Completion will be certified. Obtain all required certificates, guarantees, as-built drawings, etc., as work proceeds to enable the CCC application to be submitted as soon as construction is completed).

2 SITEWORKS

2.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

2.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

2.3 Site & Scope

2.3.1 Site

Note that no claims will be recognised on the grounds of insufficient description of existing site conditions in the Contract Documents.

Take great care to excavate exactly for the wall foundations to avoid any damage to adjacent property.

2.3.2 Scope

This section covers:

Demolition work

Removal of vegetation

Excavation of topsoil and stockpiling and final distribution

Excavation as required for foundations, slabs, carpark and drive

Supply, placing and compaction of hardfill basecourse and sand blinding
Supply and placing of any site concrete required

Preparation for, and installation of asphalt driveway paving
Supply and installation of asphaltic concrete

Preparation for paving works, and sandstone and asphalt paving
Preparation for, and installation of exposed aggregate paving

2.3.3 Waahi Tapu

During excavation, should a waahi tapu or other cultural site be unearthed, cease excavation operations immediately, and inform the Contract Administrator. Inform the local Iwi, and inform Heritage New Zealand Pouhere Taonga and apply for an appropriate authority if required. Take

appropriate action, following discussions with Heritage NZ Pouhere Taonga and Territorial Authority, and runanga/runaka/iwi if Maori, to remedy any damage and/or to restore the site.

Note; in accordance with the Heritage New Zealand Pouhere Taonga Act 2014, where an archaeological site is present (or uncovered), an authority from Heritage New Zealand is required if the site is to be modified in any way. An archaeological site is defined in the Heritage New Zealand Pouhere Taonga Act 2014 as any place in New Zealand (including buildings, structures or shipwrecks) that was associated with pre-1900 human activity, where there is evidence relating to the history of New Zealand that can be investigated using archaeological methods.

2.4 Excavation & Siteworks

2.4.1 Excavation

Excavation work shall be carried out in accordance with the WorkSafe NZ Excavation Code of Practice. Co-ordinate with other trades as to set-out and timing to ensure that all cut faces are covered or finished etc. as soon as possible after the excavation is complete.

From the excavated material select the most appropriate material for compacted filling and stockpile it in appropriate positions sufficient for filling and backfilling (but NOT for hardfilling).

Remove all surplus material from the site as soon as it is excavated, taking care to avoid damaging the footpath or streets or spilling material on to them.

Remove individual boulders from the excavated material and stockpile them where noted for future landscaping use by others.

Report for instruction when any unexpected voids, made-up ground or similar are encountered.

Report the finding of antiquities or other items of value, and leave them undisturbed until approval (and instruction) is given for their removal - they remain the property of the Principal.

Plan the excavation carefully to ensure that stockpiles will not interfere with concrete construction, to stockpile just sufficient material for the filling, backfilling and reshaping required later, and to avoid overlaying areas outside the works area with material.

Cease machine excavation above final levels and trim to the finish profiles by hand where appropriate. Any over excavation in critical foundation, etc. areas made up with 10MPa concrete unless otherwise approved. Trim slab benches exactly to the required level to allow for hardfill and blinding.

Noisy excavation equipment shall be used only during hours which will avoid undue nuisance to the occupants of adjacent properties.

Excavate accurately in position and true to line and minimum sizes and to levels and grades required for all slabs, footings and foundations, and over the rest of the areas shown for levels adjustment.

Excavations down to firm undisturbed ground, and footings and foundations 200mm minimum into solid, except where shown otherwise.

Below slabs on ground the general intent is to excavate to a stable undisturbed subgrade (of 300 kPa ultimate bearing capacity).

2.4.2 Excavation Completion

As soon as excavation and filling is complete and before any concrete is placed or other work proceeded with the foundation material will be inspected by the Engineer, and any necessary changes to foundation widths or details will be directed.

2.4.3 Backfilling

Backfill as soon as possible after retaining walls are in place and sealing, field drains and FormFlow are in place, and fully checked. Remove any timber offcuts and any/all other rubbish prior to backfilling.

3 CONCRETE

3.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

3.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

2295:2006(NZS)	Pliable, permeable building underlays
2904:1995(AS/NZS)	Damp-proof courses and flashings
3604:2011(NZS)	Timber-framed buildings
4200.1:2017(AS|NZS)	Pliable building membranes and underlays - Part 1: Materials
4200.2:1994(AS/NZS)	Pliable building membranes and underlays - Installation requirements
4389:2015(AS/NZS)	Roof safety mesh
SNZ HB 3604:2011	Timber-framed buildings - Selected extracts from NZS 3604:2011

3.3 Thermakraft Underlay, DPM, DPC & Tapes

3.3.1 Scope

Supply and install Thermakraft Underlays and Membranes, as specified herein, to the locations identified on the drawings, complete with all accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with Thermakraft Ltd technical information and installation requirements (check www.thermakraft.co.nz, or call 0800 806 595 for the latest editions), other relevant product manufacturers' recommendations, and as shown on the design drawings.

No substitutions are permitted for the specified products from Thermakraft Ltd.

The following is a list and a general description of the extent of the Thermakraft Underlays and Membranes works, which are more specifically defined in the contract documents, required for the completion of the contract works:

3.3.2 Requirements

3.3.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

3.3.2.2 Warranty

Kingspan Thermakraft Product Warranty Statement:

- 15 Years Warranty - for all Thermakraft warranted products installed, according to the warranty conditions.
- Provide the Thermakraft Ltd Product Warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of permanent installation.

3.3.2.3 Substitutions

Thermakraft Ltd products shall be as specified herein and as indicated on the approved drawings. The substitution of Thermakraft branded products for alternative brands is not permitted under any circumstances.

The substitution of a specified Thermakraft product for an alternative Thermakraft branded product by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Thermakraft branded products to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

3.3.3 Damp-Proof Membrane

Thermathene Black (250µm). A 250 micron thick (0.25mm), tear resistant, recycled polyethylene film sheet concrete underlay. Coloured black.

Installed over nominal 10mm (max. 25mm) thick compacted sand blinding layer, over a properly prepared base course, as a moisture vapour barrier under concrete slabs on-ground (prior to concreting), in accordance with the manufacturer's requirements and as shown on the drawings (Install Guide).

Thermathene Black must be laid in a continuous manner with all laps minimum 150mm, and penetrations to be taped with Thermakraft White General Purpose Tape. Tape-seal around penetrations. Inspect immediately before pouring concrete and repair any holes or other damage.

Installed Location:

3.3.4 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades to install Thermakraft Underlays, DPMs, and DPCs as required.

3.3.5 Workmanship

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All installation work shall be carried out by experienced and competent tradespersons, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements.

All cutting, joining, and fixing techniques shall be exactly as recommended by the manufacturer, and carried out with the use of suitable tools and equipment appropriate for the application. All work shall be such as to leave a neat, efficient, and weathertight installation.

3.3.6 Delivery & Handling

Store underlay rolls on end, undercover, on a flat, clean and dry surface. Keep stored materials dry, out of direct sunlight, and protected from damage and contamination at all times.

Handle materials in accordance with the manufacturer's requirements and in a manner that prevents damage to or deterioration of the product.

Do not used damaged or defective materials, or products that are beyond their designated shelf life.

Installers shall be familiar with and comply with the manufacturer's safe handling requirements and precautions for use, and shall use appropriate safety gear when handling materials.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including General risk and workplace management - part 1.

3.3.7 Preparation

3.3.7.1 General

Prior to installation, carry out all necessary inspections and preparatory work required, and ensure that all preliminary works by other trades has been completed to specification and as shown on the approved drawings.

Do not commence installation until all necessary preliminary works by others is complete and to the required standard. The commencement of work shall be deemed to indicate full acceptance by the installer that all preliminary works by other trades is complete.

Supporting timber framing shall comply with NZS 3604, or with NZS 3603 and AS/NZS 1170 for specific design, and have a maximum moisture content of 20% at the time of cladding installation. Allow LOSP treated timber to sufficiently flash-off before installing Thermakraft building underlays and foils.

Supporting light structural steel framing shall comply with the requirements of AS/NZS 4600 or the NASH Standard for Residential and Low-rise Steel Framing, Part 1: Design Criteria. Comply with the light structural steel framing fabricator's specifications and requirements for fixing cladding and roofing components.

Supporting heavy steel structures shall comply with NZS 3404.

3.3.7.2 Roof Structure

Roof Structure - prior to roof underlay installation check all aspects of preparatory works, including but not limited to:

- Check that the supporting purlins or battens are set-out to the required set-out and spacings, are straight and true to line and plane, and are securely fixed.

- Check that all barge and fascia boards have been installed to the correct line and plane with all edge blocking complete and secure.
- Check that valley gutter and hidden gutter framing is to the required dimensions with solid backing supports securely fixed, true to line and plane.
- Check that internal gutter membrane linings are complete, and dressed back and adhered to a solid substrate along the roof edge as shown on the approved drawings.
- Check that all trimming for roof penetrations, all roof/wall junction blocking, and all necessary work by other trades is complete.
- Check that solid sarking required for fully-supported roofing is complete and securely fixed in accordance with the approved drawings.
- Check that any required anti-ponding boards for tiled roofs have been correctly installed to a minimum 5° (1:12) fall to the eaves gutter.

3.3.8 Completion

Check that all underlays have been installed correctly and are properly supported, and that all underlay edges, joins and ends are correctly finished prior to closing off with claddings - all in accordance with Thermakraft installation requirements.

Check installed membranes and underlays for defective work and damage - replace and/or repair as necessary to the required standard.

Leave all of this work complete, and free of defects, and to the required standard in accordance with the manufacturer's warranty requirements.

Issue to the Owner a copy of the Thermakraft maintenance requirements and the Thermakraft product warranties for the installed products.

4 WATERPROOFING

4.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

4.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

3740:2010(AS)	Waterproofing of domestic wet areas
4858:2004(AS/NZS)	Wet area membranes
NZBC B2/AS1	Durability
NZBC E3/AS1	Internal Moisture

4.3 Interior Wet Area Waterproofing Membrane Systems

4.3.1 Scope

Supply and install the specified Interior Wet Area Waterproofing System, to the locations shown on the drawings, complete with all accessories. All aspects of this work shall be in strict accordance with the manufacturer's technical guidelines, installation specifications and details, other relevant product manufacturers' recommendations, and as shown on the drawings.

No substitutions are permitted for the specified Interior Wet Area Waterproofing System.

4.3.2 Waterproofing System

Liquid-Applied Waterproofing Membrane System. A liquid applied, modified polyurethane, high-build acrylic, flexible waterproof membrane, suitable for residential and commercial interior wet area floor and wall applications to be subsequently tiled or otherwise covered and protected.

Installed as an interior wet area undertile waterproofing membrane system in accordance with the manufacturer's requirements, NZBC E3/AS1, AS 3740, and as shown on the drawings.

Brand & Product: As per supporting documents.
Number of Coats: As per supporting documents.
Coverage per Coat (l/m²): As per supporting documents.
Location: As per plans.

4.3.3 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades to install the specified Interior Wet Area Waterproofing System as required.

4.3.4 Workmanship

All installation work shall be carried out by experienced contractors, authorised by the manufacturer, familiar with the specified products and installation techniques, to fully comply with all of the manufacturer's warranty requirements in accordance with the manufacturer's installation requirements and as noted and detailed on the drawings.

4.3.5 Delivery & Handling

Store products off the ground on a flat surface undercover, keep materials dry and out of direct sunlight, and protect from damage. Do not use damaged or faulty products, or products beyond the designated shelf life. Handle materials and products in accordance with the manufacturer's recommendations.

4.3.6 Installation

Liquid Applied Waterproofing Membrane System. Install the undertile membrane waterproofing system, including surface priming, membrane application, jointing, flashing and sealing etc., and system-supplied accessories in strict accordance with the manufacturer's installation requirements and details, and as shown on the drawings. Application and workmanship shall be in accordance with AS/NZS 4858:2004 and AS 3740:2004.

Substrates shall be free of dust, grease, wax, oil, dirt, loose plaster, laitance, curing compounds, paint and other contaminants likely to prevent proper bonding, and shall be structurally sound, securely fastened and properly supported to eliminate any movement which may cause cracking. New concrete should be sufficiently aged for a minimum of 4 to 6 weeks. Allow proprietary floor levelling compounds and screeds to cure in accordance with the manufacturer's recommendations prior to application.

Seal substrate corner junctions and substrate joints and fixings and visible cracks, with a suitable sealant. Prepare all substrate floor/wall junctions and sheet joints with a system-approved pressure sensitive bond breaker tape. Prime all surfaces with the specified system primer.

Apply the specified liquid-applied membrane undiluted on to a dry and primed substrate uniformly by brush or roller in accordance with the manufacturer's instructions.
Finish the membrane at control joints, floor wastes and drain outlets to the manufacturer's requirements. Consult the manufacturer regarding any detail where a standard system detail does not exist.

Allow to membrane dry in accordance with the manufacturer's requirements. Where required; carry out a full flood test prior to tiling. Protect the installed membrane as required; avoid puncturing or damaging when exposed - repair as necessary

4.3.7 Completion

Check that the internal wet area waterproofing system has been installed correctly, and that any system accessories are correctly installed and finished. Check for damage, repair or replace as necessary.
Leave the completed waterproofing system leak free and watertight.
Leave the working area clean and tidy ready for tiling, remove rubbish from site.

Advise the Main Contractor to protect the completed works from damage until tiling is completed.

Issue to the Owner a copy of the product and installation warranty for the completed works.

5 CARPENTRY

5.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

5.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1491:1996(AS/NZS)	Finger jointed structural timber
1859.1:2017(AS|NZS)	Reconstituted wood-based panels - Specifications - Part 1: Particleboard
1859.2:2017(AS|NZS)	Reconstituted wood-based panels - Specifications - Part 2: Dry process fibreboard
2270:2006(AS/NZS)	Plywood and blockboard for interior use
2271:2004(AS/NZS)	Plywood and blockboard for exterior use
2295:2006(NZS)	Pliable, permeable building underlays
2588:2018(AS|NZS)	Gypsum plasterboard
2589:2017(AS/NZS)	Gypsum linings - Application and finishing
2904:1995(AS/NZS)	Damp-proof courses and flashings
2908.2:2000(AS/NZS)	Cellulose-cement products - Flat sheets
3601:1973(NZS)	Metric dimensions for timber
3602:2003(NZS)	Timber and wood-based products for use in building
3603:1993(NZS)	Timber Structures Standard
3604:2011(NZS)	Timber-framed buildings
3617:1979(NZS)	Specification for profiles of weatherboards, fascia boards, and flooring
3622:2004(NZS)	Verification of timber properties
3631:1988(NZS)	New Zealand timber grading rules
3640:2003(NZS)	Chemical preservation of round and sawn timber
AS/NZS 1080.1:2012	Timber - Methods of test - Method 1: Moisture content
AS/NZS 2269.0:2012	Plywood - Structural - Part 0: Specifications
NASH Standard	Residential and Low-rise Steel Framing - Part 1: Design Criteria
NZBC B2/AS1	Durability
NZBC C/AS2-AS6	Protection from Fire
NZBC G6	Airborne and Impact Sound

5.3 General

This section includes the receiving, stacking and storage of all Carpenter's materials and the fabrication, erection and fixing of all framing, sheathings and finishing timbers, including all work incidental to neatly finishing in other trades and all temporary work and temporary bracing.

The Carpenter shall attend upon all trades, and shall supply and fix all obviously necessary but not specifically mentioned fixings and materials.

5.4 Timber Framing

5.4.1 Scope

Supply and install timber framing to the floors, walls, roofs, and other timber framed elements, as identified and detailed on the drawings. All aspects of this work shall be in accordance with NZS 3604, product manufacturers' recommendations, and as shown on the drawings and the specification.

5.4.2 Workmanship

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All work shall be carried out to current best trade practise by experienced and competent tradesmen, familiar with the materials and installation techniques, in accordance with NZS 3604 and as shown on the drawings.

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings prior to installing timber framing.
Co-ordinate with other trades to install timber framing as required.

5.4.3 Timber Framing

5.4.3.1 Timber Grade and Quality

Unless otherwise noted or specified on the drawings or specification, all framing timber shall be minimum structural grade SG 8 Radiata pine in accordance with NZS 3622.
Framing timber shall be seasoned or kiln dried, and be straight and true and free from wind, warp and distortion, and in lengths suitable for the members required, and shall have a moisture content of between 12% and 18% before installation.
Do not used damaged, faulty or defective materials.

5.4.3.2 Timber Treatment

All non-durable timber framing shall be appropriately treated against moisture and/or insect decay by treatment plants with recognised quality assurance systems that are administered by the Timber Preservation Council (NZTPC). Treatment of timber and wood-based building products shall be to the requirements of NZS 3602 as an absolute minimum, and all treated timber shall be identified and marked as required.
Carefully manage treated framing during installation to avoid accidental use of timber with a lower performance or durability treatment than that required or specified.

5.4.3.3 Storage & Handling

Check timber framing upon delivery and reject sub-standard or damaged material.
Store timber framing dry under cover, fillet stacked and well clear of the ground, and protect from damage, moisture, and contamination.
Ensure all appropriate personal protection equipment is worn at all times when handling and cutting treated framing.

5.4.3.4 Framing Installation

All timber framing members, including all dwanging, strutting, blocking, bracing etc, shall be sized, setout, fitted and fixed to the requirements of NZS 3604 and as shown on the drawings to accommodate structural loadings, cladding and lining setout and support, and the installation of other building components, fixtures and fittings.

All framing shall be erected without deviation, true to line, level, angle and plumb, and evenly aligned and square, and within the tolerances allowed in NZS 3604 Table 2.1. Framing members accurately cut, lapped, housed, joined, and seated so as to provide full contact over the bearing surfaces.

Temporarily prop, brace, tie, and secure framing members and elements as required until the framing is complete and self supporting. Leave in place for safety purposes as long as required.

Protect timber framing as required during installation against damage and moisture, and against significant variation of moisture content until ready for lining. Avoid ponding of water around floor plates.

5.4.3.5 Concrete Separation

Separate timber framing with an approved continuous damp proof course when in direct contact with concrete or masonry. Ensure that the DPC material is compatible with the timber treatment.
Free draining separations to external vertical faces shall be 12mm minimum and as noted on the drawings.

5.4.3.6 Timber Re-treatment

All cut or drilled surfaces of H4 and H5 treated timber framing shall be flood coat re-treated, with a suitable product recommended by the original treatment plant, before installation.

5.4.3.7 Edge Notching and Centre Holes

The notching, checking, and boring of framing members shall be in strict accordance with the requirements of NZS 3604.
Avoided checking and cutting where possible and keep to such dimensions so as not to prejudice the purpose for which the member is used. Keep edge notching to a minimum and where possible use centrally bored holes instead.
Concealed services pipes and wiring shall not project beyond the framing face and where possible shall be beyond the lining's fixing reach.

5.4.3.8 Framing Protection

Protect timber framing as required during installation against damage and moisture, and against significant variation of moisture content until ready for lining. Avoid ponding of water around floor plates.

5.4.3.9 Built-up Framing Members

Except for jack studs, bottom plates and top plates, framing members may be substituted with built-up members in accordance with the limitations of NZS 3604 2.4.4.7 with the prior approval of the Architect/Designer only.

5.4.4 Steel Fixings

5.4.4.1 Fastenings and Connectors

Unless otherwise noted or specified, timber framing fastenings and connectors shall be as specified in the relevant fixing schedules of NZS 3604 or have an equivalent capacity as specified therein. Timber framing connectors and fixings shall comply with the product information as required in NZS 3604 2.4.6, and shall be used and installed in accordance with the manufacturer's recommendations. Pre-drill nail holes in split-prone framing as necessary.

5.4.4.2 Durability of Fixings & Fastenings

Unless otherwise noted or specified, the minimum durability of timber framing fixings and fastenings, excluding nails and screws, shall comply with the durability requirements of NZS 3604 Table 4.1.
Galvanised steel fixing components, excluding nails and screws, shall have galvanised coating masses in accordance with NZS 3604 Table 4.2.
Unless noted or specified otherwise, the materials for nails and screws shall be as given in NZS 3604 Table 4.3.
Steel fixings and fastenings in contact with timber treated with copper based timber preservatives (H3.2 or higher) shall be in accordance with NZS 3604 4.4.4.
Stainless steel nails shall be minimum Grade 304 unless otherwise specified or noted.

5.4.4.3 Bolts and Coachscrews

Unless specified or shown otherwise, all bolted and coach screwed connections shall be M12 or M16 in accordance with the relevant fixing requirements given in NZS 3604.
Bolted and coach screwed connections shall have either a 50mm x 3mm square, or a 55mm x 3mm round, washer to each head and nut for M12 and M16 fixings. Washers shall be of the same material and durability as the bolt or coach screw.

5.4.5 Wall Framing

5.4.5.1 Plates

Top and bottom plates shall be to the dimensions and layout shown on the drawings. Unless specified or shown otherwise, top and bottom plates shall be fixed in accordance with NZS 3604 7.5.12 and Tables 8.18 and 8.19, true to line and level or angle.
Joints in top plates shall be made over a stud or over blocking between studs, and all top plate connections shall be in accordance with NZS 3604 8.7.3. Form all holes and edge notches in top and bottom plates in accordance with NZS 3604 8.7.5.

5.4.5.2 Studs

Studs shall be to the dimensions and spacings shown on the drawings, and installed true to line and plumb in both directions between top and bottom plates.
Unless noted otherwise, non-load bearing wall studs shall be to the spacings given in NZS 3604 Table 8.4, stud width as shown on the drawings.
Form all holes and edge notches in studs in accordance with NZS 3604 8.5.1.5. Do not notch, check, cut, or bore holes in the middle third of any trimming stud.
Should the need arise, studs shall be straightened in accordance with NZS 3604 8.5.3 with prior approval from the Architect/Designer only.

Unless noted otherwise, studs in loadbearing walls for 3 kPa floor loads shall be in accordance with NZS 3604 Table 14.10.

5.4.5.3 Lintels

Lintels shall be to the dimensions and locations shown on the drawings, and installed true to line and level, and shall be supported by a 45mm thick doubling stud or jack stud fixed to a trimming stud, and secured against uplift in accordance with NZS 3604 8.6.1.8 as required.
The thickness of a lintel may be made from two or more members, where each member is the length of the lintel, in accordance with NZS 3604 2.4.4.7.

5.4.5.4 Sill & Head Trimmers

Unless specified or shown otherwise, sill and head trimmers to openings shall be the same width as the wall stud and to the thickness given in NZS 3604 Table 8.15, and installed at the required opening height true to line and level, and supported by a 45mm thick doubling stud or jack stud fixed to a trimming stud.

5.4.5.5 Dwangs

Dwangs shall be the same width and thickness as the wall stud, and installed at the centres noted on the drawings, and accurately cut and fixed in place true to line and level and flush with stud edges.
Dwangs fixed in accordance with NZS 3604 Table 8.19.

5.4.5.6 Ribbon Boards

Ribbon boards shall be as dimensioned and located on the drawings, and installed on edge and checked 25mm into studs at the required height, true to line and level, and fixed in place in accordance with NZS 3604 Table 8.19.

5.4.6 Roof Framing

5.4.6.1 Rafters

All rafters (including hip, valley and jack rafters) shall be to the dimensions, spacings, pitch, and layout shown on the drawings.
Rafters shall be aligned and paired at the required spacings to ridge boards, ridge beams, hip rafters and valley rafters, and as shown on the drawings, and installed parallel, true to line, pitch and plane, and fixed in accordance with NZS 3604 Table 10.1.
Any required jointing of rafters shall be made over supports shown on the drawings only.
Unless shown otherwise, rafter seating to top plates, beams, and lintels shall have a minimum bearing

of 32mm without reducing the rafter depth to less than 65mm, or 80%, at the birds mouth.
Extend rafter ends to form eaves as detailed on the drawings and in accordance with NZS 3604 10.2.1.14.
Fly rafters and outriggers installed to form gable verges as detailed on the drawings and in accordance with NZS 10.2.1.15.3

5.4.6.2 Purlins

Purlins shall be to the dimensions and spacings shown on the drawings and as required by the cladding material, and fixed to rafters and/or trusses in accordance with NZS 3604 Table 10.10 (purlins on their flat) and/or Table 10.11 (purlins on their edge).
Purlins on their flat shall be continuous over a minimum of two spans.
Provide all necessary blocking and lateral support to purlins laid on edge in accordance with NZS 3604 10.2.1.16.6, and as detailed.
Extend purlins to form gable verges as detailed and in accordance with NZS 3604 10.2.1.15.

5.4.6.3 Roof Trusses

Roof trusses shall be Specific Engineering Design (SED) in accordance with NZBC B1/VM1 and manufactured by an accredited fabricator, and shall comply with all aspects of NZS 3604 10.2.2. Roof trusses shall be fabricated to meet the specific design requirements of the roof including, but not limited to; roof layout, pitch, and details, in accordance with the drawings and specification.
Roof trusses shall be supported and fixed to the truss fabricator's specifications but shall be no less than that required by NZS 3604 Tables 10.14 and 10.15. Roof trusses shall be braced as shown on the drawings and in accordance with NZS 3604 10.3.

5.4.6.4 Roof Bracing

Roof bracing shall be as shown on the drawings and in accordance with NZS 3604 10.3 and 10.4 as necessary.

5.5 Workmanship & Materials

5.5.1 Workmanship

5.5.1.1 Supervision

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner. It is the main contractor's responsibility to ensure that the construction of all structural timber complies in all respects with the drawings and the specification.

All non-restricted building work shall be carried out by or under the direct supervision of competent tradespersons, suitably qualified for the work undertaken, and in accordance with the best and latest trade practice.

5.5.1.2 Sub-floor Ground Cover

Just prior to closing-in suspended sub-floor framing, clear all framing offcuts and other rubbish, and rake loose material even with the ground shaped in a manner will allow accumulated moisture to drain to the exterior. Lay 0. 25mm thick black polythene sheeting as a vapour barrier over the

prepared sub-floor ground surface. Cut polythene to neatly butt or lay up against foundations. Lap polythene joins minimum 100mm and seal with polythene tape. Hold polythene sheeting in place with pegs, masonry units or similar.

5.5.1.3 Timberwork

All timber shall be worked and cut to be true and square and free from wind and warp with all joints matching and mating to a proper contact fit over the full surface of the joint. All connections whether nailed screwed, glued, mortised or dovetailed shall be accurately made and properly executed to provide sound satisfactory connections for the class of work required.

Timber containing unacceptable defect or distortion shall not be cramped to provide mating at connections but shall be discarded and replaced by true defect-free timber before connections are made. Distribute any acceptable defects in timber so as not to impair the strength or the appearance of the finished work. Do not cut studs across the grain to straighten them.

The checking and cutting away of timbers shall be avoided where possible and shall be limited to such dimensions as will not prejudice the purpose for which the timber is used. Observe NZS 3604 restrictions on holing and checking of timber joists and beams. Concealed services pipes and wiring shall not project beyond the framing face and where possible shall be beyond the linings/claddings fixings reach.

Neatly punch exposed nailing to the diameter of the nail head below the surface. Completley remove bruises and tool marks, and replace all split timbers and hammer-marked finishing timbers.

Fit a 3-ply bituminous DPC or a single layer high impact polyethylene DPC at all timber to concrete junctions to provide complete separation. Ensure that the DPC material is compatible with the timber treatment.

Clean out framing voids before fixing sheathings or linings. Ensure framing voids are fully vermin proofed to the exterior. Build in as necessary all required flashings (supplied by others) to windows, doors, roof edges, etc.

5.5.1.4 Wall Underlay

Install a flexible heavyweight building paper or breathable/absorbent wall underlay behind all exterior wall claddings, fixed horizontally, with minimum 150mm horizontal laps and minimum 150mm vertical joint laps made over a stud, and kept taut without sagging or bulging.
Fix wall underlay at maximum 300mm centres, with 6mm - 8mm stainless steel staples or 20mm large-head galvanised clouts or galvanised proprietary fixings, fixed through nylon vertical strapping at every stud in exposed locations. Provide additional fasteners fixed through the underlay around framed openings. Cut window and door openings just prior to joinery installation; cut underlay at 45º angle away from each corner and return full framing depth and fasten to inside of frame.
Finish wall underlay at edges as detailed, and return full framing depth into window and door openings. Install all necessary flexible flashing tapes to openings, around pipes, ducts and other services penetrating the underlay, parapet and balustrade junctions, along head flashings and inter-storey flashings when installed, as required to seal the underlay, in accordance with wall underlay manufacturer's requirements and as shown on the drawings.

For drained cavity construction to framed walls without a rigid wall underlay and where the studs are at greater than 450mm centres, restrain the underlay with nylon strapping to prevent the underlay from bulging into the cavity space.
Any damaged underlay shall be made good by lapping in a new section.
Do not leave wall underlays exposed before covering with wall cladding for more than the manufacturer's recommended duration.

5.5.1.5 Roof Underlay

Install heavyweight building paper or breathable/absorbent roof underlay behind roof cladding as detailed, with minimum 150mm side and end laps, lapped such that any water will be shed to the outside of the underlay, and sufficiently tensioned in a manner that prevents sagging or ponding.
R1 class roof underlays shall be fully supported on nylon straps or non-corrosive netting/mesh; R2 class self-supporting underlays shall be laid to maximum 1200mm span between adjacent supports.
Run roof underlay horizontally or vertically up the roof slope on roof pitches above 10° pitch, and horizontally on roof pitches 10° or less.
Fix roof underlay at maximum 300mm centres to purlins, with 6mm - 8mm stainless steel staples or 20mm large-head galvanised clouts or proprietary underlay fixings.
For tiled roofs, lay the roof underlay over the anti-ponding board and no-corrosive support netting/mesh, and fix at maximum 300mm centres to the rafters/trusses before the tile battens are installed.
Finish roof underlay along roof edges and junctions, valley gutters, and at the ridge as shown on the drawings. Carefully cut underlay at roof openings at 45º angle away from each corner and lap-tape closed to framed up-stands, ducts and other services penetrating the underlay in accordance with the underlay manufacturer's requirements and as detailed. Roof underlay must be separated from chimneys and flues in accordance with the requirements of the NZBC C1-C6 Acceptable Solutions.
Any damaged underlay shall be made good by lapping in a new section.
Do not leave roof underlays exposed before covering with the roof cladding for more than the manufacturer's recommended duration.

5.5.1.6 Window Installation

Prepare window and external door framing openings for joinery installation by neatly cutting the building wrap at 45º into corners, returning turning the wrap through the frame depth and fixing to the inside face.
Over-flash the underlay along the sill with a flexible flashing tape, installed full frame depth and length of the opening, returned minimum 100mm up the jambs, and with minimum 50mm return over the outside edge.
Over-flash the underlay at head/lintel corners with a flexible flashing tape, extending minimum 100mm each way from the corner, full frame depth, and with minimum 50mm return over the outside face.

Install external joinery frames with metal flashings as detailed and/or as required to completely weatherproof all frame-to-cladding junctions.
Unless shown otherwise, head flashings shall be carried minimum 75mm up behind claddings, extended at 15º out over the joinery head or facing board and returned down to cover the joinery or facing board minimum 10mm and finished with a 5mm, 45º 'kick out' drip-edge.
Neatly dress down the head flashings at the ends of the facings - for drained cavity construction, also

form up-turned stop-ends in-line with the outside edge of cavity above.
Install metal (as specified) head flashings, fixed over the wall underlay, with the flashing upstand over-flashed minimum 50mm with a flexible flashing tape against the underlay, or with an additional piece of underlay extended over and lapped behind the underlay above, behind the inter-storey flashing or sill flashing above, or to the underside of the eaves.
Unless shown otherwise, sill flashings, where required, shall have a minimum 5º slope, minimum 8mm rear upstand with sealed sloping stop-ends, and be carried down minimum 35mm over the lower cladding and finished with a 5mm, 45º 'kick out' drip-edge.

Take delivery of window and door joinery. Check substrates for correct profile and alignment and that the joinery is fabricated to the correct wall construction set-out and depth. Set shims or pack as necessary to install joinery exactly true and square. Use appropriate separators between aluminium and other materials, and fix securely with due regard for any anticipated movements and for linings, trim, etc.

Install neat sealant beads as detailed or required.

After joinery installation, install closed cell backing rods as required and expanding foam seal the gap between the opening substrate and joinery liners/reveals (all round, from the inside).

On completion ensure that all sashes and doors neatly fit the openings with regular tolerances to all edges, and that all moving components and hardware are correctly adjusted and operating smoothly, without binding, to the required functionality.

5.5.1.7 Joinery Installation

Take delivery of all scheduled joinery items (doors, cabinets, shelves, etc.) and install in the positions shown, accurately aligned, true to level, plumb and square, and securely fastened as noted and in accordance with best trade practice and with due regard for adjacent linings, finishes and trim, and anticipated movements.

Cabinets scribed and/or recessed packers scribed to adjacent surfaces as detailed or directed. Protect all installed Joinery from damage including surface marking and contamination, dirt and dust, and moisture until completion. Do not use Joinery items for working supports or platforms or for storage of materials or tools and equipments.

On completion ensure that joinery item doors and drawers all neatly fit the openings with regular tolerances to all edges, and that all moving components and hardware are correctly adjusted and operating to the required functionality.

5.5.2 Timber

5.5.2.1 Timber Materials

All timber shall be graded in accordance with NZS 3631 - Structural Grade MSG8 or better for all framing timber - (to meet the requirements of Table 2.3 of NZS 3603 for mechanically graded timber), and Dressing Grade for all finishing timber. Timber that is deemed below standard, in the opinion of the Architect/Designer, shall be removed from the site.

All non-durable timber, including components in manufactured items, shall be appropriately treated against moisture and/or insect decay by treatment plants with recognised quality assurance systems that are administered by the Timber Preservation Council (NZTPC). Treatment of timber and wood-based building products shall be to the requirements of NZS 3602 as an absolute minimum, and all treated timber shall be identified and marked as required.
Ensure that similar timbers with different treatment levels are carefully managed during construction to avoid accidental use of an H1 treated item where H3 hazard class treatment is required by the NZS 3602.
Do not use LOSP (light organic solvent-based preservative) treated timber that has not adequately 'flashed-off'.
Ensure that all cut or drilled surfaces of H4 and H5 hazard class treated timbers are flood coat re-treated, with the product recommended by the original treatment plant, before installation.

All timber shall be seasoned or kiln dried, to the stable moisture content, be straight and true and free from wind, warp and distortion, and in lengths suitable for the members required and the location in the finished construction. All framing timber shall have a moisture content between 12% and 18 % before being installed. If the use of inadequately seasoned timber results in damage or opening joints in the finished building the timber shall be replaced. Fixing of internal linings shall be delayed after closing in until the timber framing has dried back below 20% moisture content and to allow for the maximum settling of substrates.

All kiln dried, dressed and/or finishing timbers shall be stacked under cover on delivery to the site, and all timber shall be full to the nominal sizes shown or specified, subject only to normal cutting and dressing tolerances.
All finishing timber shall have machine marks, stains and roughness removed and shall be sanded smooth.

Ensure that enclosed surfaces and ends of paint-finished exterior finishing timbers are fully primed before fixing. If this trade (Carpentry) carries out the priming it shall be to the specification and standard required of the Painter.

Unless specified otherwise, exposed framing timbers shall be unfinished to the exterior, and be fine bandsawn milled, treated with a minimum of discolouration, handled carefully at all times to avoid surface damage, and delivered free of crayon or pencil or other markings. Hazard class treatment markings shall be on the ends, NOT on the faces.

5.5.2.2 Timber Species

Unless noted or specified on the drawings, in the list below, or elsewhere in this specification all timber used shall be Radiata pine.
Other timbers shall be as follows:
- Douglas Fir (*NZ Oregon, Psuedotsuga menziesii*)
- Jarrah Clears (*Eucalyptus marginata*)
- Kwila Clears (*Merbau*)
- Balau (*Shorea spp*)
- Kwila (*Merbau*)
- Cedar Clears (*Western Red Cedar, Thuja plicata*)

- Rimu - (*NZ Red Pine*)
- Vitex Clears - (*Vitex cofassus*)
- Eucalypt Saligna Clears - *(Sydney Blue Gum*)
- Tasmanian Oak - (*Eucalyptus delegatensis / obliqua / regnans*)

Note: the use of alternate grades and varieties to those specified is subject to approval in each instance.

5.5.2.3 Timber Cavity Battens

To wall areas as noted install H3.1 treated ex.50mm x 25mm timber battens to form a drained vertical cavity complying with E2/AS1 in all respects. Ensure that flexible wall underlay and flexible flashing tape are completely and correctly installed before fixing battens in place. Fix the battens with 60mm hot-dip galvanised flat head nails at maximum 400mm centres, ensuring that the batten set-out completely fulfils the cladding's fixing requirements. Install 1:12 sloping horizontal cavity spacers where required to suit claddings, keeping the ends 50mm clear of the vertical battens.

5.5.2.4 Other Materials

Materials shall be delivered to site with the packaging and labelling intact, shall be of the same type, finish or colour to maintain continuity, shall be stored, and conditioned if required, in accordance with manufacturer's recommendations, and shall be protected from damage, contamination, and moisture - as appropriate.
Handle all materials in accordance with best practice and the manufacturer's requirements, and in a manner that prevents damage or deterioration to the material. Do not use damaged or defective materials or products, or products that are beyond their designated shelf life.

5.5.3 Laminated Veneer Lumber

Laminated Veneer Lumber (LVL) shall comply with AS/NZS 4357.0. Each piece of structural LVL shall be branded at least once with the manufacturer's logo and a registered brand or marking that clearly identifies the structural properties that apply to the product and its limitations on end use; all in conjunction with associated published literature.

Structural properties identified in the associated published literature shall be:
- details of marking specific to the product
- veneer details
- physical properties including
  - modulus of elasticity
  - bending stress
  - tension stress parallel to grain
  - compression stress perpendicular to grain
  - compression stress parallel to grain
  - shear stress
- joint group
- density
- dimensional tolerances
- adhesives used
- limitations on end use

The storage and handling of LVL shall comply with Appendix A of AS/NZS 4357.0. In particular:
- LVL should be kept dry during storage and transit
- LVL should be stacked on bearers well clear of the ground and arranged so that their supporting surfaces are in the one plane
- Bearers should be spaced sufficiently close so that LVL spanning between them does not deflect excessively under its own weight.
- Bearers or spacers within a stack should be located near direct vertical alignment
- Care should be taken in lifting and handling LVL in order to avoid mechanical damage
- Wrapping should avoid and prevent entrapment of moisture
- LVL should not be used in high humidity conditions or exposed to the weather.

5.5.4 Proprietary Sheet Bracing Systems

Proprietary sheet bracing systems to walls, ceilings and sub-floor foundations shall be installed in strict accordance with the manufacturer's technical literature and design guides. No materials specified in the manufacturer's technical literature and design guide can be substituted without the written approval from the Architect/Designer.

5.5.5 Proprietary Roof Trusses

Roof trusses shall be of proprietary design, complying with the requirements of NZS 3603, NZS 3604, and AS/NZS 1170, and manufactured by suitably qualified fabricators.

Make allowance for all notching and holing to timber members to accommodate roof bracing etc., in the design of member sections of the roof trusses. Allow for all additional rafters, purlins, fixings and bracing necessary to complete the roof framing system with all accessories and incidental items necessary for proper installation even where not specifically shown on the drawings.
Proprietary roof trusses shall be designed to carry all imposed gravity and lateral loads. Refer to the approved design drawings for truss set-out and specified design loads. Roof trusses are assumed to be generally at 900mm centres spanning clear between walls or roof beams as shown on the drawings. The Main Contractor is responsible for the design of proprietary roof trusses, including their layout and interaction with and dependence on adjoining elements.

Provide all necessary design information and shop drawings for all proprietary roof trusses to be incorporated in the works for review prior to fabrication.
Provide Producer Statements from a Charted Professional Engineer covering the design and construction of the roof trusses. Provide all information required by the Territorial Authority for the purpose of obtaining a Building Consent.

5.5.6 Fixings

5.5.6.1 Nails

Comply with the requirements of NZS 3604 Section 2.4.4 and the Nailing Schedules of NZS 3604 as applicable. Unless noted or specified on the drawings or elsewhere in this specification, all nails fixing exterior timbers shall be Grade 304 or 316 stainless steel. Nails that will be covered with plaster or any similar material shall be hot-dipped galvanised, unless noted or specified otherwise.

Finishing brads to all finishing timbers shall be set out neatly and punched to the diameter of the nail below the surface. Bore slightly undersize holes for nailing that could cause splitting of the timber. Power-driven staples are completely unacceptable in finishing timbers.

5.5.6.2 Screws

Screw fastenings shall be of suitable gauge, head type, thread design, and length to provide secure fastening into the substrate material, and be suitable for the assembly/construction of the fixed item/element and the substrate material.
Unless noted or specified otherwise, screws exposed to the exterior shall be Grade 304/316 stainless steel or hot-dipped galvanised, and hot-dipped galvanised or similar corrosion resistant for damp situations.
Self-drilling screws shall be in accordance with AS 3566 for fastener type and corrosion resistance class.
Unless noted or specified otherwise, screws fixing hardware or similar shall be of the same material and finish as the hardware. Except where raised head screws are shown or specified, screws shall be countersunk flush or recessed where stopped/filled.

5.5.6.3 Bolts

Where bolts are used they shall be complete with nuts and washers unless specified otherwise. All bolts, nuts and washers shall at least meet the durability requirements of NZS 3604 Table 4.1. Where a higher durability material is specified on the drawings, the higher durability material shall be used. The diameter of a hole for a bolt shall not be less than the bolt diameter nor exceed it by 1.5mm.

For the following bolt diameters use washer sizes as below unless noted otherwise on the drawings:
- up to M8: 25x 25 x 1.5mm;
- up to M12: 50 x 50 x 3mm;
- up to M20: 65 x 65 x 5mm;
- up to M20: 75 x 75 x 6mm.

Round washers may be used proving they are of a thickness and area not less than those specified above.

Subfloor framing - unless noted otherwise on the drawings, cast-in holding down bolts for subfloor framing fixed to concrete foundation walls shall be M12 Grade 304 stainless steel, embedded minimum 150mm into concrete, to the spacings required by NZS 3604, and located centrally on the timber.
Bottom plates - unless noted otherwise on the drawings, cast-in holding down bolts for bottom plates fixed to a concrete slab shall be M12 galvanised, embedded minimum 120mm into concrete, to the spacings required by NZS 3604, and located centrally on the timber.
Framing - timber/timber and timber/steel - Unless noted otherwise on the drawings, M16, hexagonal head mild steel and with 50 x 50 x 3mm washers.
Timber/concrete (dry situations) - Unless noted otherwise on the drawings, Ramset Trubolts, T12140 at maximum 900mm centres - for damp or exterior situations use stainless steel Trubolts.
Bolts shall be tightened until the washer just indents the timber surface. Exposed bolts shall be re-tightened just prior to Practical Completion to remove any slack consequent on timber shrinkage.
Allow to countersink bolt heads and nuts as necessary to clear linings.

5.5.6.4 Framing Hardware

Proprietary timber framing hardware and fixings, including multigrips, joist shoes, Z nails, gang nails and similar hardware, may be used where specifically approved, or where required on the drawings or by NZS 3604 schedules, in accordance with the manufacturer's requirements.
Proprietary timber framing structural brackets and ties, including post and bearer brackets, beam supports, angle brackets, tie cleats and similar hardware, shall be as noted on the drawings and installed in accordance with the manufacturer's requirements.
Refer to Metalwork or Structural Steel section of this specification for specific design engineered fabricated steel components that connect structural timber framing.

5.5.6.5 Powder Fastening Systems

Powder powered fasteners are not permitted for fastening structural timber framing unless specifically noted on the drawings. All applications are subject to specific approval.

5.5.6.6 Adhesives

Aliphatic PVA for dry timber applications - all other adhesives for timber jointing are subject to specific approval or as specified. Check surfaces are in appropriate condition to receive adhesive, and that adhesives are used strictly in accordance with the manufacturer's instructions. Clamp adhesive-jointed timber connections and check alignment of members before the adhesive has set.

5.5.7 Flashings

Flashing materials shall be in accordance with the requirements of NZBC E2/AS1 Sections 2.2 Materials, 4.0 Flashings, Table C.1.1.1B: Compatibility of materials in contact , and Table C.1.1.1C: Compatibility of materials subject to run-off, and as noted on the drawings.
All flashings around windows, doors and other openings and apertures, at internal and external corners, inter-storey junctions, soffit junctions, and at junctions with other building elements and cladding systems, etc., shall all be carefully constructed, fixed and finished to the details shown on the drawings.

5.5.8 Sealants

5.5.8.1 Sealants

For critical joints such as primary water/weatherproofing seals, precast panels primary seals, structural floor slab control joints, structural glazing, immersion or hydrostatic pressure seals, etc., either use the sealant noted on the drawings or obtain a reputable sealant manufacturer's recommendation for the precise situation, and submit the manufacturer's specifications covering all relevant criteria and characteristics of the proposed sealant, primers, joint surfaces preparation, etc. to the Architect/Designer for review and confirmation to proceed.
If so requested, additionally submit a sample of the proposed sealant made up into a demonstration joint, incorporating the same materials, preparation, finish tooling, etc. After confirmation to proceed with the proposed sealant install a sample joint to approval, length approximately 2% of the overall length of the joints required, with a minimum length of two metres; when accepted this joint becomes the quality control sample for all subsequent similar joints.

For less critical joints such as those in covered or protected situations, and bathroom and kitchen ceramics and sanitaryware etc., either use the sealant noted on the drawings or select the sealant

from a reputable manufacturer's range for the substrate materials involved, with due regard for the flexibility required, acid or neutral curing, mould resistance, paintability or clear or standard colours, slumping characteristics, temperature range expected, etc. - silicone, polymer or polyurethane sealants are anticipated.
For all simple gap-filling and draught sealing situations, either use the sealant noted on the drawings or select from a reputable manufacturer's range for a paintable acrylic sealant with good adhesion characteristics for the substrates involved - pay particularly care in the sealant selection where bare metal, polycarbonate, polystyrene or similar substrates or where bituminous-based membranes are adjacent or where exposure to solvents is possible.

All joint surfaces preparation and priming and all sealant application work shall be exactly in accordance with the sealant manufacturer's recommendations, and carried out by competent and experienced applicators familiar with the materials and techniques required.
Ensure that the sealant is being used within the manufacturer's stated design parameters, particularly with regard joint design and anticipated cyclic movement.
Check that the joint faces are sound, completely dry, and frost free, clean and free of dirt, rust, oil, grease, laitance, etc., and they are primed to suit the surface porosity - particularly for critical locations.
Insert a polyethylene tape slip layer at the back of the joint or a closed cell polyethylene PEF backer rod where required and to the sealant manufacturer's recommendations. Mask off joint edges where a clean straight finish line is required.
Check the toxicity of the selected sealant and handle it appropriately. Check that the temperature during sealant installation is within the manufacturer's guidelines.
Apply the sealant and tool the filled joint's surface smooth and even, utilising a lubricant as necessary and strictly within the manufacturer's guidelines.
Remove any masking tape immediately after tooling, clean up all adjacent surfaces using the recommended cleaning agents as required, and protect the finished joint until the sealant has properly cured.

5.5.9 Interior Finishing Trim

All interior finishing trim shall be cut to the exact dimensions and fine sanded smooth, and with lightly sanded arrisses, and all fixed with plated finishing pins. Machine staple fixing is NOT acceptable.
Note that even traces of planer marks are unacceptable on architraves. Margins between interior trim and other elements shall be exactly even, and all mitres shall be exact and tight.

No scotia (all square stopped).

No architraves.

5.6 Hermpac Weatherboard Cladding Systems

5.6.1 Scope

Scope
Supply and install the Hermpac Pacific Limited Weatherboard System, as specified herein, to the walls identified on the drawings, complete with all accessories and trim. For the purpose of this

specification, Hermpac Pacific Limited shall be referred to as Hermpac. All aspects of this work shall be complete in accordance with the Hermpac product specifications and technical literature (check www.hermpac.co.nz, email: technical@hermpac.co.nz, or call 09 421 9840 for the latest editions), and as shown on the drawings.

No substitutions or deletions are permitted for the Hermpac product.

5.6.2 Horizontal Weatherboard

Horizontal Rusticated Weatherboard
Supply and install the Hermpac Horizontal Rusticated Weatherboard Cavity System, as specified herein, to the walls identified on the drawings, complete with all accessories and trim. All aspects of this work shall be completed in accordance with the Hermpac product specifications and technical literature (check www.hermpac.co.nz, email: technical@hermpac.co.nz, or call 0800 329 423 for the latest editions), NZBC E2/AS1, other relevant product manufacturers' recommendations, and as shown on the drawings.
The Hermpac Rusticated Weatherboard Cavity System is CodeMark assured.
No substitutions or deletions are permitted for the Hermpac Horizontal Rusticated Weatherboard Cavity System

5.6.3 Timber Species & Profile

Western Red Cedar
Weatherboard Profile ~*as identified on the accompanying drawings*
Grade PC1 ~as identified on the accompanying drawings
Grain/Cut -Mixed-Grain ~*as identified on the accompanying drawings*
Face Finish ~*as identified on the accompanying drawings*
Coating ~*as identified on the accompanying drawings*

5.6.4 Cavity Batten & Base Closer

Timber Cavity Battens - Horizontal Weatherboards, 20mm Cavity
Timber Cavity Battens - to form a nominal 20mm deep drained cavity for Hermpac horizontal weatherboards. 40x20mm, minimum H3.2 treated Radiata pine cavity battens.
Fix timber cavity battens to stud with 40 x 2.5mm hot-dipped galvanised flat head nails or stainless steel finishing brads.
Installed vertically to the layout and details shown on the drawings and in accordance with Hermpac installation requirements

uPVC
uPVC Cavity Base Closer. Punched with 3-5mm holes or slots complying with NZBC E2/AS1 Paragraph 9.1.8.3. Fitted to the base of the drained cavity, above window and door heads, and inter-storey junctions. Installed in accordance with E2/AS1 to the locations and details shown on the drawings.

5.6.5 Co-operation

Co-operation
Co-operate with other trades to ensure that all preliminary and preparatory works, including membranes, flexible underlays, rigid air barriers, and trims and any other related works are

completed in accordance with the Hermpac Cavity System Installation Specification and Construction Drawings
Coordinate with trades the locations of pipes, outlets, cables, meter boards and other fittings installed by others, and to install Hermpac Weatherboard Cladding System as required.

5.6.6 Workmanship

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.
Installation work shall be carried out by suitably qualified and experienced tradespersons, familiar with the specified products and the required construction and installation techniques, in accordance with the requirements of the Hermpac technical literature and associated BRANZ Appraisal, NZBC E2/AS1, and as noted and detailed on the approved construction drawings.
Upon completion of the installation, the installing LBP shall complete and sign a Restricted Building Work (RBW) memorandum and the associated Hermpac Weatherboard Cladding System, Product Installation Check List. Issue a copy of the RBW document to the Building Consent Authority and to the Main Contractor.
All work shall be such as to leave a neat, efficient, robust and weathertight installation, to the required standard, free from damage and defects, including surface marking.
Make all necessary provisions to protect adjacent finished work and surfaces from damage during installation.
Refer www.hermpac.co.nz, email: technical@hermpac.co.nz, or call 0800 329 423 for any technical assistance required, and ensure that current Hermpac technical literature is referenced and followed when installing Hermpac weatherboards.

5.6.7 Delivery & Handling

Delivery & Handling
Store weatherboards and accessories undercover, flat and true, clear of the ground by at least 150mm and supported on dry and clean timber bearers at maximum 900mm centres in accordance with Hermpac recommendations. Keep stored weatherboards and accessories dry and protected from damage and contamination, and free from bending or excessive compression.
Do not use damaged or defective weatherboards or accessories.

Dock any oversized knots, unacceptable or unrequired grade characteristic, or damaged areas of weatherboard. Do not install weatherboards during periods of wet weather. Double seal all cut ends and fresh cut timber with selected exterior coating. Some grades of timber will require more docking than others. Please check NZ Grading Rules to ensure that all timber installed meets the NZBC requirements.
Handle weatherboards in accordance with the manufacturer's recommendations and in a manner that prevents damage and surface marking.
Installers shall be familiar with, and comply with, the manufacturer's safe handling requirements and precautions for use, and shall use appropriate safety gear when handling materials.
Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including the Best practice guidelines for working at height in NZ, and the OSH Guidelines For the Provision of Facilities and General Safety in the Construction Industry.

5.6.8 Preparation and Installation

General Requirements

Install the specified Hermpac Weatherboard Cladding System, complete with accessories, in accordance with the Hermpac installation requirements and technical literature and as shown on the approved construction drawings.

Confirm the layout and location of all control joints; the layout of cavity battens; and any specific cladding detailing requirements prior to installation.

Ensure that all associated preliminary and preparatory works are completed to the required standard and specification, and as shown on the drawings.

Ensure that the current and up-to-date Hermpac installation and technical literature is readily available on site for reference during installation.

Weatherboard soaker and/or flashing material compatibility shall be in accordance with NZBC E2/AS1 2.2, and as shown on the drawings.

Ensure all cut ends and fresh timber is double coated and sealed in accordance with Hermpac requirements before fixing.

Refer to Fixing for fixing type and placement etc.

All internal and external weatherboard corner junctions, inter-storey junctions, and weatherboard trim and accessories, shall be constructed and installed to the details shown on the drawings.

Always keep Hermpac weatherboard cladding lines consistent and true along walls and around corners.

All flashings around windows, doors and other openings, at corner junctions, inter-storey junctions, soffit junctions, and pipe penetrations, shall be carefully constructed, fixed and finished to the details shown on the drawings.

Hermpac Rusticated Weatherboard Cavity - Fixed over a Flexible Wall Underlay on Timber framing

Preparation

- Check all aspects of preparatory works, including, but not limited to:
- Check that the timber wall framing complies with NZS 3604, has studs at maximum 600mm centres and Nogs/Dwangs as per design specification and NZBC (refer NZS 3604:2011 Section 8.5.4), for horizontal cladding, is plumb and in true alignment, includes all blocking required for cavity battens and fixing at openings, joints, corners, soffits, etc., and has a maximum moisture content of 18% at the time of cladding installation.
- Check that the flexible wall underlay, as specified, has been installed in accordance with NZBC requirements and the manufacturer’s recommendations, and with all finishing tapes, flashings etc. at windows, doors, corners and penetrations all correctly incorporated to provide a continuous seal.
- Where the studs are at greater than 450mm centres, check that appropriate additional restraint is correctly installed to the underlay to keep bulk insulation from pushing the wrap into the cavity space.
- Check that all preparatory materials are lapped such that any water will run down to the exterior.

Installation

Hermpac Rusticated Weatherboards installed over a nominal 18mm cavity drain over a flexible wall underlay:

Over the flexible wall underlay, install and fix the specified cavity battens to the timber framing to the layout and details shown on the drawings.

Back flash all internal and external corners with Hermpac aluminium corner flashings.

Carefully set-out and fix the base weatherboard to the timber studs through the cavity battens, level along the base line, minimum 50mm or as detailed, below the bottom plate or floor structure.
Install full length weatherboards where possible. From the base board upwards, level and true the weatherboards to the cavity battens.
Where joints are unavoidable, scarf the weatherboards at 30º directly over a stud line, and fix weatherboard ends as specified and just clear of the scarf join.
Overlap, joint and fix cavity-installed Hermpac Rusticated Weatherboards in accordance with Hermpac installation requirements and as detailed on the drawings. NB: Ensure weatherboard end-grains are double coated.

5.6.9 Fixing

Fix Hermpac Vertical Shiplap Weatherboards
Fix Hermpac Weatherboards with Grade 316 Stainless Steel Annular Grooved Rose Head Nails in accordance with Hermpac fixing requirements and as shown on the drawings.
The nail shank must be minimum 3.15mm diameter for cavity-fixed weatherboards, or 2.8mm diameter for direct-fixed weatherboards.
When fixing with rose head nails (used most often for an oil/stain finish), the nail length must allow minimum 30mm penetration of the wall frame. When installed over Vertibat 40mm or 45mm thick cavity battens, nails shall achieve a minimum 30mm penetration into the Vertibat cavity battens.
All nail fixings shall be pre-drilled a maximum of 1mm diameter smaller than the nail gauge.
Ensure the weatherboards are set-out with an overlap of 25mm, with a 2mm expansion gap between boards at the overlap.
Single fix weatherboards at every fixing point, with nails driven in a slight upward slope, located 30-35mm from the edge of the weatherboard, and no closer than 32mm from the end of the board.
Nails shall be set flush onto the board surface - not into or below the surface.
The hidden side lap must be restrained using the Hermpac Clinch Nail at every fixing point, with the nail shank flush against the hidden edge - the nail must not be fixed through the lap, refer to Hermpac details for correct placement

5.6.10 Completion

Check that the specified Hermpac Weatherboard System has been correctly installed and fixed to the layout and details shown on the drawings; that all joints, associated trim and accessories finished correctly; and that all openings and penetrations have been properly flashed and sealed.
Check for damaged materials and defective work - carry out repairs as necessary to the required standard.
Ensure that the work of other trades does not negatively impact on or reduce the minimum clearances required by the NZ Building Code, between the cladding and ground, roof and/or deck junctures.
Leave all of this work complete and weathertight and to the required standard in accordance with Hermpac requirements and NZBC E2/AS1.
Leave the completed works and surrounding surfaces clean and free of debris and rubbish. Remove all rubbish and excess material from the site.
Complete and sign the Restricted Building Work (RBW) memorandum, and the Hermpac Weatherboard Cladding System Product Installation Check List. Issue a copy of the RBW document to the Building Consent Authority and to the Main Contractor.

5.7 GIB® Plasterboard Linings

5.7.1 Scope

Supply and install GIB® Plasterboard Linings specified herein, as sheet lining materials to the walls, ceilings and other elements identified on the drawings, complete with all accessories required for proper installation, finishing and performance. All aspects of this work shall be in complete accordance with the current GIB® Site Guide and relevant GIB® Systems literature (check www.gib.co.nz, or call 0800 100 442 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for GIB® Plasterboard Linings, GIB® Systems or GIB® System components and accessories.

This specification must be read in conjunction with relevant GIB® Systems specifications - GIB® EzyBrace® Systems, GIB® Fire Rated Systems, GIB® Noise Control Systems, GIB® Aqualine® Wet Area Systems, GIB® X-Block® Systems, GIB® Quietline®, GIB® Intertenancy Barrier System, and GIB® Rondo® Metal Batten Systems - and other specifications sections, as they are interrelated

5.7.2 Requirements

5.7.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

5.7.2.2 Warranty

GIB® Product & System Warranty:

GIB Systems Durability.
The following systems have, unless stated otherwise in GIB® technical literature, a serviceability life in excess of that stated and satisfy the requirements of NZBC Clause B2 Durability:
15 Years:
- GIB Aqualine® Wet Area Systems.

50 Years:
- GIB® Fire Rated Systems
- GIB EzyBrace® Systems
- GIB X-Block® Systems
- GIB Noise Control® Systems.

Provide the GIB® Product & System Warranty on the manufacturer's standard warranty form.
Commence the warranty from the date of practical completion of the contract works.

Include with the warranty: a copy of the completed GIB® Installation Sign-Off sheet, and the GIB® Plasterboard Lining Systems Care and Maintenance bulletin.

5.7.2.3 AWCI Membership

Installation of GIB® Plasterboard Linings and associated GIB® Systems shall be carried out by a registered member of the Association of Wall and Ceiling Industries of New Zealand Inc. (AWCI). If not already provided and if requested, submit evidence of AWCI membership and relevant experience.

5.7.2.4 Quality Assurance

Ensure that the installation and finishing of GIB® Plasterboard Linings and associated GIB® Systems comply in all respects with the approved design drawings and specifications, and Building Consent.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

5.7.2.5 Inspection & Acceptance of GIB® Plasterboard Linings

Carry out all necessary pre-installation, installation and finishing inspections of GIB® Plasterboard Linings for each area of work in accordance with the requirements of the GIB® Site Guide and associated industry Code of Practice (AWCI) recommendations.

Complete the GIB® Site Guide Pre-Installation Checklist prior to installing GIB® plasterboard linings, and relevant GIB® Performance Systems Installation Checklists.

Complete the GIB® Interior Plasterer/Stopper Installation Sign-Off Certificate upon completion and before handover for subsequent decoration.

5.7.2.6 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected GIB® Plasterboard Linings and GIB® Systems materials and work shall be repaired and/or replaced to the satisfaction of the Architect/Designer, without delay and at no additional cost to the Principal.

5.7.2.7 Producer Statement (other manufacturer's system)

Producer Statement PS1 - where required. Where GIB® Plasterboard Linings are installed as a component of another manufacturer's proprietary system, the system manufacturer shall furnish a completed Producer Statement PS1 (Design) as confirmation that the specified proprietary system as designed and documented complies with the relevant clauses of the New Zealand Building Code. The PS1 Producer Statement shall not serve as a product warranty or guarantee of compliance.

5.7.2.8 Substitution of GIB® Plasterboard Linings

GIB® plasterboard linings shall be as specified herein and as indicated on the approved drawings. The substitution of GIB® branded plasterboard linings and GIB® System components for alternative brands is not permitted under any circumstances.

The substitution of a specified GIB® plasterboard lining for an alternative GIB® plasterboard lining by the Contractor shall be in strict accordance with the requirements of the GIB® Site Guide: 2.3 - Board Substitution Options, and relevant GIB® Systems literature. Such substitutions shall only be permitted with the Architect's/Designer's written authorisation, and shall be at no additional cost to the

Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative GIB® Plasterboard Linings to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

5.7.3 Performance

5.7.3.1 Limitations of GIB® Plasterboard

GIB® plasterboard products must NOT be:
- used in external situations, or
- exposed to water or be installed in situations where extended exposure to humidity above 90% RH can reasonably be expected, or
- exposed to temperatures in excess of 52°C for prolonged periods.

5.7.3.2 Bracing Performance - Timber Framing

Bracing Performance - GIB EzyBrace® Systems - Timber Framing. To the timber framed elements noted as 'Bracing' on the drawings, additionally comply with all relevant aspects of the GIB EzyBrace® Systems (2016) publication and GIB Ezybrace® Bracing Software according to the specified bracing unit rating, BRANZ Appraisal No.928, and other relevant product manufacturers' recommendations. Refer to separate specification GIB EzyBrace® Systems.

5.7.3.3 Sound Insulation Performance

Sound Insulation Performance - GIB® Noise Control Systems. To the areas noted as 'Sound-rated' on the drawings, additionally comply with all relevant aspects of the GIB® Noise Control Systems (2017) publication according to the specified sound transmission class (STC) rating, BRANZ Appraisal No.394, and other relevant product manufacturers' recommendations. Refer to separate specification GIB® Noise Control Systems.

5.7.3.4 Wet Areas

Wet Area Plasterboard Linings - GIB Aqualine® Wet Area Systems. To the areas noted as 'Wet Area' on the drawings, additionally comply with all relevant aspects of the GIB Aqualine® Wet Area Systems publication, BRANZ Appraisal No.427 (2021), and other relevant product manufacturers' recommendations. Refer to separate specification GIB Aqualine® Wet Area Systems.

5.7.4 GIB® Plasterboard Linings

5.7.4.1 GIB® Standard Plasterboard, 10mm

GIB® Standard Plasterboard, 10mm. A 10mm thick standard plasterboard interior lining. Suitable for use in residential and commercial applications on walls. Manufactured to exceed the requirements of AS/NZS 2588. Refer to the GIB® Site Guide.

Installed Location: to all dry walls as per plans. Refer to plans / bracing plan.

5.7.4.2 GIB® Standard Plasterboard, 13mm

GIB® Standard Plasterboard, 13mm. A 13mm thick standard plasterboard interior lining. Suitable for use in residential and commercial applications on walls and ceilings. Manufactured to exceed the requirements of AS/NZS 2588. Refer to the GIB® Site Guide.

Installed Location: to all dry ceiling as per plans. Refer to plans / bracing plan.

5.7.4.3 GIB Aqualine®, 10mm

GIB Aqualine®, 10mm. A 10mm thick moisture resistant plasterboard interior lining, with a water resistant polymer impregnated core to help prevent moisture penetration. Suitable for use in residential and commercial applications on walls and ceilings in spaces at risk from water or moisture damage. Manufactured to exceed the requirements of AS/NZS 2588. Refer to the GIB® Site Guide.

Installed Location: to all wet walls as per plans. Refer to plans / bracing plan.

5.7.4.4 GIB Aqualine®, 13mm

GIB Aqualine®, 13mm. A 13mm thick moisture resistant plasterboard interior lining, with a water resistant polymer impregnated core to help prevent moisture penetration. Suitable for use in residential and commercial applications on walls and ceilings in spaces at risk from water or moisture damage. Manufactured to exceed the requirements of AS/NZS 2588. Refer to the GIB® Site Guide.

Installed Location: to all wet ceilings as per plans. Refer to plans / bracing plan.

5.7.5 Components & Accessories

5.7.5.1 Metal Ceiling Battens

Metal Ceiling Battens - GIB® Rondo® Metal Batten Systems. Installed in accordance with the manufacturer's requirements to the layout and details shown on the approved drawings. Refer to the GIB® Site Guide, and to separate specification GIB® Rondo® Metal Batten Systems.

5.7.5.2 Wet Area Sealant

Wet Area Sealant. A mould resistant, flexible, neutral curing silicone sealant with strong adhesion, suitable for wet area applications and where there is high humidity, including bathrooms, toilets, showers, wash-down areas, kitchens, laundries.

Applied in accordance with the sealant manufacturer's instructions, as required by the GIB® Site Guide and GIB® System literature. Sealant joints shall be in accordance with the sealant manufacturer's joint design width-to-depth ratio.

Manufacturer & Brand:

5.7.5.3 Gap Filler

GIB® Gapfiller. A general purpose, gun applied, one-part water based, paintable acrylic gap filler. Provides excellent adhesion for gaps and cracks and other low movement joints. Used in strict in accordance with the manufacturer's requirements. Refer to the GIB® Site Guide.

5.7.6 Level of Finish

5.7.6.1 Level of Finish

To the areas noted as a specific Level of Finish (3-5) on the drawings, additionally comply with all relevant aspects of the GIB® Site Guide and AS/NZS 2589, complete with all system accessories, and other relevant product manufacturers' recommendations.

NOTE: Unless stated otherwise, Level 4 is the default Level of Finish.

5.7.6.2 Acceptance of Levels of Finish

Carry out all necessary inspections and assessments of completed plasterboard jointing and finishing prior to hand-over for subsequent decoration.

Do not apply surface sealers and decorative treatments until written agreement between the Contractor and Painter/Decorator is given confirming the specified Finish Levels have been achieved and the plasterboard linings are ready for subsequent sealing and decoration.

5.7.7 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.
Co-operate with the Decorator to ensure that the specified Finish Levels for plasterboard jointing and finishing is achieved before decorating commences.

Coordinate with other trades to install GIB® Plasterboard Linings as required, and to ensure that:
- appropriate tolerances and clearances allow for adjacent internal linings, fixtures, fittings, services, etc; and
- the linings correctly allow for proper door and window installation; and
- penetrations for building services are correctly handled to maintain sheet integrity and system performance.

5.7.8 Workmanship

Where required by the NZ Building Act 2004, it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

Installation and finishing work of GIB® Plasterboard Linings shall be carried out by qualified and experienced tradespersons, familiar with the specified materials and installation and finishing techniques, in accordance with the GIB® Site Guide and the relevant GIB® product technical literature, and to fully comply with all warranty requirements. Submit evidence of experience on request, e.g. National Certificate of Interior Systems, or Certified Business Member of AWCINZ.

GIB® Plasterboard Linings shall be jointed and finished to the specified Finish Levels in accordance with AS/NZS 2589 and GIB® Site Guide. Make all necessary arrangements for the quality assessment of plasterboard jointing and finishing Finish Levels prior to commencing decorating.

All cutting, fixing, jointing, finishing and sealing techniques shall be exactly as recommended by the manufacturer. All work shall be such as to leave a neat, efficient and robust installation, to the required standard and free from damage and defects.

Protect surrounding surfaces and areas from jointing compound splashes and sanding dust.

5.7.9 Delivery & Handling

Store GIB® Plasterboard Linings indoors, in neat, flat stacks off the floor, in dry conditions and without any sagging or distortion, in accordance with the GIB® Site Guide. Keep plasterboard linings,

compounds and accessories dry, out of direct sunlight, and protected from damage, moisture and contamination at all times.

Do not use damaged or defective materials and products, or products that are beyond the designated shelf life.

Should a problem be encountered with any GIB® product during installation or delivery, immediately contact the GIB® Helpline on 0800 100 442. Do not continue to use the product that is not performing to specification or expectation. Keep samples of the product in question and where possible, document batch numbers and/or manufacturing dates.

Handle all products and materials in accordance with the manufacturer's requirements and relevant Product Data Sheets and GIB® Site Guide, and in a manner that prevents damage. Carry plasterboard sheets on edge, and avoid damage to sheet edges, ends, and surfaces.

Installers shall be familiar with and comply with the requirements of the GIB® Site Guide precautions for use, and use appropriate safety gear when handling materials.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice.

5.7.10 Preparation

5.7.10.1 General

All framing and substrates shall be complete and ready for GIB® Plasterboard Lining installation.

Timber framing shall comply with NZS 3604, or with NZS 3603 and AS/NZS 1170 for specific design, and have a maximum moisture content 18% at the time of plasterboard lining installation.

Light structural steel framing shall comply with the requirements of AS/NZS 4600 or the NASH Standard for Residential and Low-rise Steel Framing, Part 1: Design Criteria. All light structural steel framing members shall satisfy the requirements of AS/NZS 1170. Comply with the steel framing fabricator's specifications and requirements for plasterboard installation.

Steel stud partitioning shall comply with AS 1397 and as specified and shown on the drawings. Comply with the manufacturer's specifications and requirements for plasterboard installation.

Concrete substrates shall comply with the CCANZ CP 01:2011 or with NZS 3109. New concrete must have aged for a minimum of 28 days. Ensure that concrete surfaces are within the tolerances specified. For of direct bonded plasterboard linings, concrete substrates must below 75% relative humidity prior to installation.

Concrete masonry substrates shall comply with NZS 4229, or with NZS 4230 and AS/NZS 1170 for specific design. For of direct bonded plasterboard linings, concrete masonry substrates must below 75% relative humidity prior to installation.

Carry out all necessary moisture readings. Do not commence installation until the moisture readings are below the required level.

Carry out all necessary substrate inspections and preparatory work in accordance with the manufacturer's recommendations and the GIB® Site Guide prior to installation. Complete and sign the GIB® Site Guide Pre-Installation Checklist.

Check that the building envelope has been finished at all penetrations including doors, windows, services, etc., and the building is weathertight.

Check junctions to all other building elements and ensure that all necessary works have been completed, including cavity insulation.

Check that all fixtures, fittings and built-in items are correctly installed, and that all framing and substrate edges are completed as detailed.

Confirm the location and details of movement control joints, as indicated on the drawings, prior to installation.

Ensure all pre-wiring and service piping is installed and complete.

Check that any required cavity insulation has been installed correctly and its bulk thickness does not exceed the framing thickness.

Remove all debris and rubbish from framing voids prior to installing linings.

The commencement of work on each section/area shall be deemed to indicate full acceptance by the installer that all preparatory works by other trades is complete.

5.7.10.2 Framing Check

Framing - check all aspects of preparatory works, including but not limited to:
- Check that the framing is straight and true to line, and is plumb/level and correctly aligned.
- Check that the framing is within the required deviation tolerances defined in AS/NZS 2589 according to the specified Finish Level.
- Check that vertical and horizontal framing members are at the spacings shown on the drawings, and that any required battens or furring channels are installed to the required layout.
- Check that the framing has no projections due to structural and bracing bracketry, etc. Ensure that framing brackets, plates, braces, hold-downs, etc., are correctly installed.

5.7.10.3 Work above Ceilings

Check that all building work, mechanical, plumbing, electrical, fire protection and other services installed above the ceiling are completed and independently supported by the building structure - not by the ceiling system.

5.7.11 Installation

5.7.11.1 General

Install GIB® Plasterboard Linings and accessories in accordance with the requirements of the GIB® Site Guide and product technical literature and associated fixing schedules, to the locations and details

shown on the drawings. For GIB® Performance Systems, refer to the relevant GIB® system specification.

Prior to installation, confirm:
- The locations and construction details of all movement control joints;
- The locations and installation details of all building services items within framed structures;
- The specified GIB® plasterboard installation and fixing requirements;
- The specified Finish Level(s) for the plasterboard linings.
- Subsequent surface treatments and finishes applied to GIB® plasterboard.

5.7.11.2 Standard Ceiling Fixing - Metal Ceiling Battens

GIB® Plasterboard Ceiling Linings - Standard Ceiling Fixing with Metal Ceiling Battens. Metal ceiling battens shall be from the GIB® Rondo® Metal Batten Systems - refer to separate specification GIB® Rondo® Metal Batten Systems.

Unless independently supported, uniformly distributed loads (fixtures and fittings and/or overlaid insulation) supported by GIB® plasterboard ceiling linings shall not exceed 3.0 kg/m².

Metal ceiling batten spacings shall be shall be as given in the GIB® Site Guide according to the specified plasterboard thickness - 600mm for 13mm or greater thickness, 450mm for 10mm thickness. Ceiling battens shall all run in the same direction within the ceiling area. In no case shall ceiling battens be continuous over movement control joints in the structure.

Install GIB® Plasterboard sheets right angles to ceiling battens, with sheet end-joints staggered minimum 600mm and located off battens and back-blocked. Fully support sheets during positioning and fixing - for ceiling installations, the use of a mechanical lifting machine is recommended.

Plasterboard sheets shall be fixed to ceiling battens in conjunction with GIBFix® adhesive applied at maximum at 200mm centres. Do not apply adhesive at sheet edges or within 200mm of fasteners. Firmly press the plasterboard where adhesive has been applied to ensure full contact.

Fix sheets to timber ceiling battens with GIB® Grabber® Self Tapping Screws in accordance with GIB® Site Guide fastener schedule according to the plasterboard thickness. Position fasteners no closer than 12mm from a tapered edge or 18mm from a cut sheet edge.

Install all necessary paper-faced metal beads, casing beads, shadow and reveal beads and other edge trims to plasterboard corners and edges as necessary and as detailed on the drawings.

Form movement control joints to the locations and details shown on the approved drawings. Where not indicated on the drawings, movement joints shall be positioned at maximum 12m intervals in both directions on any single ceiling, and where there is a change in ceiling lining material, and shall coincide with the junctions between adjoining spaces.

Accommodate recessed light fittings, heating and ventilating diffusers and grilles and other utility fixtures and fittings that penetrate the ceiling lining.

5.7.11.3 Ceiling Diaphragms

Ceiling Diaphragms - refer to separate specification GIB® Ezybrace Systems, and to the GIB EzyBrace® Systems publication.

5.7.11.4 Wall Linings - Horizontally Fixed - Timber Frame

GIB® Plasterboard Wall Linings Horizontally-Fixed to Timber Framing. Install GIB® plasterboard sheets horizontally, at right angles to studs, with any end-joints staggered, and with the bottom edge of the lower sheet gapped 5–10mm off finished floor level.

All joints between sheets shall be touch fitted. Eliminate or minimise the butting of sheet end-joints by using full-length or long-length sheets. Give careful consideration to the placement of sheet joints. Where possible, place joints in situations where they are less likely to be affected by critical lighting.

It is recommended that sheet end joints in horizontally fixed plasterboard be unsupported, off-stud and back blocked - stud centres must not exceed 600mm. For plasterboard linings with Level 3 Finish and Level 4 Finish, sheet end joints can be located on-stud.

Sheet end joints at openings, such as window and door openings, shall not coincide with the vertical edges of the opening - sheets shall be fitted so that the vertical end joint falls minimum 200mm either side of the edge of the opening.

Plasterboard sheets shall be fixed to timber framing in conjunction with GIBFix® adhesive applied at maximum at 300mm centres to intermediate studs. Do not apply adhesive at sheet edges or within 200mm of fasteners. Firmly press the plasterboard where adhesive has been applied to ensure full contact.

Fix sheets to timber framing with GIB® Grabber® High Thread Screws or GIB® Nails in accordance with GIB® Site Guide fastener schedule. Place fasteners at 300mm centres to top and bottom plates and to perimeter studs, and to each stud where the horizontal joint crosses the stud, with screws no closer than 12mm from sheet edges. It is recommended that fasteners at wall corners are placed 50mm in from the corner in each direction (horizontal/vertical).

Install all necessary paper-faced and metal beads, casing beads, shadow and reveal beads and other edge trims to plasterboard corners and edges as necessary and as detailed on the drawings.

Form movement control joints to the locations and details shown on the approved drawings. Where not indicated on the drawings, movement joints shall be positioned at maximum 12m intervals in both directions (horizontally/vertically), and shall coincide with movement joints in the primary structure, and where there is a change in wall lining material.

Accommodate piped and cabled services and other building services fixtures and fittings that penetrate the wall lining.

5.7.11.5 Wall Linings - Vertically Fixed - Timber Frame

GIB® Plasterboard Wall Linings Vertically-Fixed to Timber Framing. Install GIB® plasterboard sheets vertically, parallel with studs, with any end-joints staggered, and with the bottom edge of the lower sheet gapped 5–10mm off finished floor level.

All joints between sheets shall be touch fitted. Eliminate or minimise the butting of sheet end-joints by using full-length or long-length sheets. Give careful consideration to the placement of sheet joints. Where possible, place joints in situations where they are less likely to be affected by critical lighting.

Form sheet edge joints on studs. Short vertical edge joints (400mm or less) such as above windows and door can be made off stud and back blocked.

Sheet joints at openings, such as window and door openings, shall not coincide with the vertical edges of the opening - sheets shall be fitted so that the vertical end joint falls minimum 200mm inside the edge of the opening.

Plasterboard sheets shall be fixed to timber framing in conjunction with GIBFix® adhesive applied at maximum at 300mm centres to intermediate studs. Do not apply adhesive at sheet edges or within 200mm of fasteners. Firmly press the plasterboard where adhesive has been applied to ensure full contact.

Fix sheets to timber framing with GIB® Grabber® High Thread Screws or GIB® Nails in accordance with GIB® Site Guide fastener schedule. Place fasteners at 300mm centres around the perimeter of each sheet, no closer than 12mm from sheet edges. It is recommended that fasteners at wall corners are placed 50mm in from the corner in each direction (horizontal/vertical).

Install all necessary paper-faced and metal beads, casing beads, shadow and reveal beads and other edge trims to plasterboard corners and edges as necessary and as detailed on the drawings.

Form movement control joints to the locations and details shown on the approved drawings. Where not indicated on the drawings, movement joints shall be positioned at maximum 12m intervals in both directions (horizontally/vertically), and shall coincide with movement joints in the primary structure, and where there is a change in wall lining material.

Accommodate piped and cabled services and other building services fixtures and fittings that penetrate the wall lining.

5.7.11.6 Wall Linings - Direct Bonded to Concrete/Masonry (above ground level)

GIB® Plasterboard Wall Linings Direct Bonded to Concrete and Masonry Substrates (above ground level). Install GIB® plasterboard sheets horizontally, with any end-joints staggered, and with the bottom edge of the lower sheet gapped 5–10mm off finished floor level.

All joints between sheets shall be touch fitted. Eliminate or minimise the butting of sheet end-joints by using full-length or long-length sheets. Give careful consideration to the placement of sheet joints. Where possible, place joints in situations where they are less likely to be affected by critical lighting.

Sheet end joints at openings, such as window and door openings, shall not coincide with the vertical edges of the opening - sheets shall be fitted so that the vertical end joint falls minimum 200mm either side of the edge of the opening.

Plasterboard sheets shall be direct bonded to concrete and masonry walls with GIB-Cove® Bond applied in daubs approximately 50mm diameter x 12mm thick, at 300-400mm centres vertically and 500-600mm centres horizontally, and no closer than 25mm from the sheet edges. Position the sheet and press into place. Ensure each sheet achieves proper contact with GIB-Cove® Bond, and is in true alignment over the surface of the sheet before setting.

Install all necessary paper-faced and metal beads, casing beads, shadow and reveal beads and other edge trims to plasterboard corners and edges as necessary and as detailed on the drawings.

Form movement control joints to the locations and details shown on the approved drawings. Where not indicated on the drawings, movement joints shall coincide with movement joints in the primary structure, and where there is a change in wall lining material.

Accommodate piped and cabled services and other building services fixtures and fittings that penetrate the wall lining.

5.7.11.7 Jointing & Finishing

Joint and finish GIB® Plasterboard Linings with GIB® joint and finishing compounds appropriate for the plasterboard type and durability, and the finish level required. Refer to Joint & Finishing Compounds clause.

Carry out jointing and finishing according to the specified Finish Level in accordance with the GIB® Site Guide and GIB® Compounds brochure. Reinforce sheet joints and internal corners with joint tape or paper-faced trim embedded into the Taping (first) Coat.

Sheet joints, internal and external corners, and fastener heads shall be evenly finished with GIB® compounds. When dry, lightly sand to a smooth finish with 220 grit sandpaper or drywall sanding screen to remove tool marks, ridges and other imperfections prior to subsequent sealing and decorating.

5.7.12 Completion

Check that GIB® Plasterboard Linings have been installed in accordance with the GIB® Site Guide and GIB® Systems literature, and are finished to the specified finish levels.

Check for any damage and defective work - repair or replace as necessary to the required standard.

Ensure that inspection and assessment of the plasterboard Finish Level has been carried out, and that written agreement stating the completed jointing and finishing is acceptable for subsequent surface sealing and decoration has been provided.

Ensure that the GIB® Installation Sign-Off Certificate has been completed and signed by the Interior Plasterer/Stopper.

Leave all of this work complete and to the required standard in accordance with the manufacturer's warranty requirements, as shown on the drawings and the conditions of the Building Consent.

Clean up thoroughly and leave the finished work and surrounding surfaces clean and free of contamination from compound splashes and dust. Remove all associated rubbish and excess material from the site.

Issue to the Owner a copy of the GIB® Plasterboard Lining Systems Care and Maintenance bulletin, and a copy of the GIB® Product and System Warranty.

Preparation and painting (by others) of GIB® Plasterboard Linings shall be carried out in accordance with AS/NZS 2311 and with the paint manufacturer's recommendations. Refer to separate specification section Painting & Decorating.

Preparation, including application of under-tile waterproofing membranes, and tiling (by others) of GIB® Plasterboard Linings shall be carried out in accordance with AS 3589.1 and the BRANZ Good Practice Guide: Tiling. Refer to separate specification section Tiling.

6 CLADDING

6.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

6.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

3604:2011(NZS)	Timber-framed buildings
4210:2001(NZS)	Masonry construction: Materials and workmanship
4236:2002(SNZHB)	Masonry veneer wall cladding

6.3 Schistwork

6.3.1 Scope

Supply the specified Schistwork and install as shown on the drawings.

6.3.2 Materials

Schist stone shall include variable colours ranging through ochres, umbers and greys. The schist shall be broken (and edge guillotined) into the finished stones before delivery to the site.

6.3.3 Workmanship

Where required by the NZ Building Act 2004 it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All work shall be by or under the direct supervision of Registered Masons certified by the NZ Mason's Registration Committee or, through reference to several completed projects, the Main Contractor must show that the proposed Subcontractor is fully competent to produce the required results. All aspects of the schistwork shall be to generally recognised best (local) trade practice.

Co-operate with the Contractor to ensure that all support foundations, nibs, and framed substrates are completely appropriate for the schistwork required, and that blockwork walls and fireplace insitu concrete walls have been fully waterproofed. Co-ordinate with all trades to build all necessary fixings, sleeves, or electrical or plumbing devices etc. into the schistwork and check that positions are correct before finish grouting. Coordinate with all trades to form all required holes, openings etc. in their exact positions.

Carefully select schist stones for sizes and faces and position to produce a well bonded (approximating stretcher bond) mass with the required face finish. Finish jambs and ends to clean straight lines.

Use mortar dry enough to avoid slurry trickles on the finished schist faces but moist enough to provide a good bond with the schist. No retempering of partially set or dried mortar. Keep the wall faces clean as work proceeds and regularly inspect for mortar droppings etc. Turn back scaffold planks at night and during rain. On completion thoroughly clean all surfaces affected by this work.

7 EXTERNAL WINDOW & DOOR JOINERY

7.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

7.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1734:1997(AS/NZS)	Aluminium and aluminium alloys - Flat sheets, coiled sheet and plate
1866:1997(AS/NZS)	Aluminium and aluminium alloys - Extruded rod, bar, solid and hollow shapes
2208:1996(AS/NZS)	Safety glazing materials in buildings
4211:2008(NZS)	Specification for performance of windows
4223.1:2008(NZS)	Code of practice for glazing in buildings - Glass selection and glazing
4223.2:2016(NZS)	Glazing in buildings - Part 2: Insulating glass units
4223.3:2016(NZS)	Glazing in buildings - Part 3: Human impact safety requirements
4223.4:2008(NZS)	Glazing in buildings - Part 4: Wind, dead, snow, and live actions
4667:2000(AS/NZS)	Quality requirements for cut-to-size and processed glass
4668:2000 (AS/NZS)	Glossary of terms used in the glass and glazing industry
AS/NZS 4666:2012	Insulating glass units

7.3 Aluminium Windows & Doors

7.3.1 Alternatives

The materials and elements specified indicate the required standards for these works. Alternatives which are equal to or superior to these materials and elements may be tendered for approval.

Thermal performance (NZBC H1/AS1) must be as required to meet the Designer's Thermal Evaluation.

7.3.2 Installation Type

7.3.2.1 Timber Frame Installation - Cavity Construction

All windows (and aluminium frame external doors) installation work shall be exactly in accordance with NZBC E2/AS1, the Windows Association's Windows Installation System (WANZ:WIS), and details on the drawings or supplied by the windows manufacturer.
Check framing alignment, and that window openings are square and the correct size for fitting tolerances.
Prepare framing openings by neatly cutting the building wrap at 45º into the corners, turning wrap through the frame depth and fixing to the inside face, flashing the bottom corners with moulded

plastic and over-flashing the full sill and 200mm up the jambs with the specified flexible flashing tape, stapled to hold the stretched external corners. At head corners install flashing tape 200mm each way from the corners.

Install the WANZ extruded aluminium support bar with built in drainage and ventilation to NZBC E2, to provide continuous support to the window unit. Install the head cavity closer, positioned to provide a 15mm drip edge to the cladding.

Set shims or pack as necessary and install the frames exactly true and square, blocked-up off the support bar as required. Use appropriate separators between aluminium and other materials, and fix securely with due regard for any anticipated movements and for linings, trim etc.

Install the head flashing, extending 35mm up behind the cladding (and in turn over-flashed with an additional piece of wrap cover extended up under the wrap or flashing or eaves above), sloping at 15º down to the exterior, and turning down to cover the top of the aluminium frame by at least 10mm, before finishing with a 5mm 45º 'kick out'. Upstand the head flashing ends as detailed. Install jamb flashings/ sealant or scribers as detailed.
After frames installation install closed cell backing rods as required and expanding foam air-seal the gap between framing and liners.

7.3.3 Interior Finish

GIB Groove.

7.3.4 Glass Platform

Double Glazed.

7.3.5 Workmanship

These windows will be manufacturerd in workshops containing all mechanical equipment appropriate for the work, and by experienced and competent tradesmen who are familiar with the techniques and materials specified.

The manufacturer will co-ordinate with other trades to establish the exact sizes for all frames before fabrication. Frames and sashes will be fabricated true, square, rigid, and ‘out of wind’, with all joints strongly mechanically fixed, and with mitres tight and fully sealed. Potential thermal, wind and seismic movements will be accommodated within the construction. All cavities will drain to the exterior, and all drilling swarf etc. will be removed during fabrication.

Stays, hinges, running gear and glazing will be installed as scheduled (the Designer will be notified if any scheduled hardware of fixing position appears to be inappropriate for this project).

Hardware will be fixed true to line and position, and adjusted and oiled as required for correct operation.

Glass will be cut true and square, sized to provide correct edge clearances, blocked into place as required, and all units will be delivered either pressure fit, pocket glaze, or beaded/wedged, unless site glazing is required. Glazing gaskets will be compatible with all adjacent materials, and cut 1% over-length to absolutely avoid stretching during installation. Frames will be braced etc. as necessary for transportation to the site.

Flashings as detailed will be supplied. Flashing materials will be compatible with the windows.

7.3.6 Delivery and Installation

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and the construction principles that are embodied in the Acceptable Solutions.

Arrange for delivery of windows to the site only when a suitable storage situation is available for them, handle the windows in accordance with the manufacturers requirements, avoid any frame distortion, avoid rubbing damage, avoid contact with concrete, plaster, mud etc. and keep them dry. Retain protective coverings for as long as possible, and remove them at completion.

Experienced and competent tradesmen who are familiar with the techniques and materials specified shall carry out all installation work. Fix in accordance with the manufacturer's instructions. Take utmost care to avoid damage to anodized or powder coated surfaces - correction of any such disfigurement requires written authority - replace any badly damaged items.

Use fixings compatible with the materials involved, as recommended by the windows manufacturer and to comply with the DWP requirements, basically aluminium or Type 316 stainless steel where exposed externally; galvanized to AS/NZS 4680, 610g/m2, may be used where not exposed.

Thoroughly check all preparatory work to openings prior to installation, including underlay, corner seal tapes, adjacent cladding, pre-installed flashings, waterproofing systems etc. as appropriate. Use inert barriers or coatings to prevent contact between dissimilar metals or between aluminium and concrete.

Install flashings as detailed and supplied by the windows manufacturer, installed tightly and neatly with absolute minimum tolerances, with head weathering jamb, jamb weathering sill, and sill open (draining) to exterior. Except where the window is recessed all head flashings shall extend 30mm minimum beyond the frame.

Air-seal all frame perimeters to adjacent structure to a depth of 15 - 20mm with expanding foam or appropriate sealant including a PEF rod at head, sill and jambs to retard the spread of sealant.

Weather-seal frame jambs etc. to adjacent surfaces (or to each other) as detailed or as required by the windows manufacturer, to achieve a fully watertight installation. In preparation for sealant the joints shall be clean, dry, and primed if necessary. Insert closed cell polyethylene backer rods or a polyethylene tape slip layer if required. Mask adjacent surfaces if appropriate, install the sealant fully in accordance with the sealant manufacturer's recommendations, and finish to even smooth surfaces.

Remove trade debris progressively, appropriately clean any affected adjacent surfaces, thoroughly clean the windows, check that all hardware is in full working order, and provide safety indication of the glass for the balance of adjacent works.

8 GLAZING

8.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

8.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1170.0:2002(AS/NZS)	Structural design actions - Part 0: General principles
2208:1996(AS/NZS)	Safety glazing materials in buildings
3604:2011(NZS)	Timber-framed buildings
4211:2008(NZS)	Specification for performance of windows
4223.1:2008(NZS)	Code of practice for glazing in buildings - Glass selection and glazing
4223.2:2016(NZS)	Glazing in buildings - Part 2: Insulating glass units
4223.3:2016(NZS)	Glazing in buildings - Part 3: Human impact safety requirements
4223.4:2008(NZS)	Glazing in buildings - Part 4: Wind, dead, snow, and live actions
4232.2:1988(NZS)	Performance criteria for fire resisting enclosures - Part 2: Fire resisting glazing systems
4667:2000(AS/NZS)	Quality requirements for cut-to-size and processed glass
4668:2000 (AS/NZS)	Glossary of terms used in the glass and glazing industry
AS/NZS 4666:2012	Insulating glass units

8.3 Non-Structural Glazing

8.3.1 Scope

Supply and install the selected glass products to the windows, doors, curtain wall systems, roofs and canopies, balustrades and barriers, partitions and screens, and other non-structural glazing elements, as noted and shown on the drawings. All aspects of this work shall be in accordance with the glass manufacturer's installation requirements and recommendations, other relevant product manufacturers' recommendations, and as shown on the drawings.

8.3.2 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades for all necessary holes and cut-outs, etc., for glass-mounted hardware, fittings and fixtures, and to install all glass and glazed elements as required.

8.3.3 Workmanship

All installation work shall be carried out by experienced and competent tradesmen familiar with the products specified and installation techniques, to the manufacturer's requirements and recommendations, and the requirements of the relevant Glazing Standards, and to the layout and details shown on the drawings.
Handle and store glass in accordance with the manufacturer's recommendations.
Provide temporary safety markings to all glass panes as the installation work progresses.
Finish all external glazing wind and watertight.
Do not use damaged, marked or faulty materials.

8.3.4 Glass Type

8.3.4.1 Clear Float Glass

Clear Float Glass. Clear annealed float glass, complying with AS/NZS 4667 and in accordance with NZS 4223.1. Installed to the locations identified on the drawings and schedules.

Manufacturer, brand name & type:

8.3.4.2 Obscure & Patterned Glass

Obscure and Patterned Glass. Surface patterned glass and/or obscure glass, complying with AS/NZS 4667 and in accordance with NZS 4223.1. Installed to the locations identified on the drawings and schedules.

Manufacturer, brand name & type:

8.3.4.3 Toughened Safety Glass

Toughened Safety Glass. Toughened Grade 'A' Safety Glass, complying with AS/NZS 2208 and AS/NZS 4667 and in accordance NZS 4223.1. Installed to the locations identified on the drawings and schedules. All cutting and drilling and other processing requirements must be done prior to toughening.

Manufacturer, brand name & type:

8.3.5 Insulating Glass Units

8.3.5.1 Standard Double Glazing

Standard Double Glazing. Air-filled and sealed insulating glass units (IGUs) complying with NZS 4223.2, with clear float glass complying with NZS 4223.1. Double glazed IGUs shall be manufactured and installed in accordance with AS/NZS 4666. Factory-fitted to the windows and doors identified as 'double glazed' on the drawings and schedules.

8.3.6 Components & Accessories

8.3.6.1 Aluminium Framed Glazing

Provide all necessary glazing components and accessories including glazing tape, setting and distance blocks, sealants, gaskets, etc., to complete aluminium framed glazing as required.

8.3.7 Installation

8.3.7.1 Aluminium, Double Glazed (IGU's)

Install Insulated Glass Units into aluminium frames in accordance with the glazing manufacturer's recommendations and NZS 4223.1, and as detailed.

8.3.8 Completion

Check that all glass has been installed correctly to the required standard and as shown on the drawings. Check for damage and surface marking and replace as necessary. Clean off and remove all temporary safety markings, as programmed and when instructed, and leave glass trade clean.
Remove all rubbish and waste material from site.
Issue to the Owner a copy of the Glass Manufacturer's maintenance requirements and all necessary Manufacturer Warranties.

9 INSULATION

9.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

9.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

4218:2009(NZS)	Thermal insulation - Housing and small buildings
4220:1982(NZS)	Code of practice for energy conservation in non-residential buildings
4243.1:2007(NZS)	Energy efficiency - Large buildings - Building thermal envelope
4246:2016(NZS)	Energy efficiency - Installing bulk thermal insulation in residential buildings
4859.1:2018(AS|NZS)	Thermal insulation materials for buildings - Part 1: General criteria and technical provisions

9.3 Pink Batts Insulation

9.3.1 Scope

Supply and install Pink® Batts® Insulation, as specified herein, to the locations identified on the drawings, complete with all accessories required for proper installation and performance. No substitutions are permitted for Pink® Batts® Insulation. All aspects of this work shall be in complete accordance with Pink® Batts® technical information and installation requirements and as shown on the drawings:
https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

The following is a list and/or general description of the extent of the Pink® Batts® Insulation works, which are more specifically defined in the contract documents, required for the completion of the contract works:

9.3.2 Requirements

9.3.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

9.3.2.2 Warranty - applies to BRANZ Appraised Pink® Batts® Ceiling & Wall products

Pink® Batts® Lifetime Product Warranty:

- 50 Years Warranty for BRANZ Appraised Pink® Batts® ceiling and wall products installed according to the warranty conditions.
- Provide the Pink® Batts® Lifetime Product Warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of permanent installation.

9.3.2.3 Substitutions

Pink® Batts® Insulation shall be as specified herein and as indicated on the approved drawings. The substitution of Pink® Batts® branded products for alternative brands is not permitted under any circumstances.

The substitution of a specified Pink® Batts® product for an alternative Pink® Batts® branded product by the Installer (PinkFit® or other) shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Pink® Batts® branded products to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Installer.

9.3.3 Wall Thermal Insulation

9.3.3.1 Pink® Batts® Ultra® R2.8 Wall

Pink® Batts® Ultra® R2.8 Wall - product code 7127128. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. R-value R-2.8. 90mm thick x 560mm wide x 1140mm long segments.

BRANZ Appraised for use as a thermal insulating material for framed or part-framed walls, ceilings and roofs of domestic and commercial buildings according to the conditions and limitations of BRANZ Appraisal No.238. Refer to product data - https://www.pinkbatts.co.nz/assets/Products/April-2022-changes-/Wall-Product-Sheet_April22_1075-RevF.pdf

Pink® Batts® Ultra® R2.8 Wall is licenced with Environmental Choice New Zealand: Thermal Building Insulants Licence No.2504017.

Installed as wall cavity thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location: As per plans / H1 report.

9.3.3.2 Pink® Batts® Ultra® R3.2 140mm Wall

Pink® Batts® Ultra® R3.2 140mm Wall - product code 7127132. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. R-value R-3.2. 140mm thick x 560mm wide x 1140mm long segments.

BRANZ Appraised for use as a thermal insulating material for framed or part-framed walls, ceilings and roofs of domestic and commercial buildings according to the conditions and limitations of BRANZ

Appraisal No.238. Refer to product data - https://www.pinkbatts.co.nz/assets/Products/April-2022-changes-/Wall-Product-Sheet_April22_1075-RevF.pdf

Pink® Batts® Ultra® R3.2 140mm Wall is licenced with Environmental Choice New Zealand: Thermal Building Insulants Licence No.2504017.

Installed as wall cavity thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location: As per plans / H1 report.

9.3.4 Ceiling Thermal Insulation

9.3.4.1 Pink® Batts® Classic R3.2 Ceiling

Pink® Batts® Classic R3.2 Ceiling - product code 7110132.

Glasswool insulation manufactured from over 80% recycled New Zealand glass.

Product is BRANZ Appraised, and supported by an EPD and Eco Choice certification.

170mm thick x 432mm wide x 1220mm long segments.

Pink® Batts® ceiling insulation is a lightweight flexible glasswool insulation products designed to:

- thermally insulate ceilings in new homes, be retrofitted into existing homes without insulation, or over existing insulation for better performance;

- fit easily into standard ceiling constructions, or be easily cut to fit non-standard constructions;

- meet the requirements of the New Zealand Building Code for different designs and environments.

Pink® Batts® Classic R3.2 Ceiling is BRANZ Appraised - refer to BRANZ Appraisal No.238. Refer to data - https://www.pinkbatts.co.nz/assets/Uploads/Downloads/Roof-and-RTA-Data-Sheet-February-2023.pdf

Installed as ceiling thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location: As per plans / H1 report.

9.3.4.2 Pink® Batts® Superbatts® R6.0 Ceiling

Pink® Batts® Superbatts® R6.0 Ceiling - product code 7113160.

Glasswool insulation manufactured from over 80% recycled New Zealand glass.

Product is BRANZ Appraised, and supported by an EPD and Eco Choice certification.

245mm thick x 460mm wide x 1220mm long segments.

Installed as ceiling thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location: As per plans / H1 report.

9.3.5 Building Insulation Blanket (BIB)

9.3.5.1 Pink® Batts® BIB R2.8 Blanket

Pink® Batts® BIB R2.8 Blanket - product code 720082. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. R-value R-2.8. 130mm thick x 1.2m wide x 8m long rolls.

Pink® Batts® Building Insulation Blanket (BIB) is specifically designed for commercial roof and commercial wall applications. When used in residential applications, installation must be completed in line with NZS 4246.

BRANZ Appraised for use as a thermal insulating material for framed or part-framed walls, ceilings and roofs of domestic and commercial buildings according to the conditions and limitations of BRANZ Appraisal No.238. Refer to product data - https://www.pinkbatts.co.nz/assets/BIB/PB_BIB-ProductSheet_MARCH22_1080-RevD.pdf

Installed as thermal insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location: As per plans / H1 report.

9.3.6 Acoustic Insulation

9.3.6.1 Floor - Pink® Batts® Silencer® Midfloor

Pink® Batts® Silencer® Midfloor - product code 7310051. A non-combustible, resin bonded fibrous glasswool insulation manufactured from recycled and virgin glass and cured urea extended phenolic resin. IIC Rating 43 (*construction: 200 x 50mm floor joist @450mm crs, 20mm particle board flooring, 10mm GIB standard plasterboard ceiling lining fixed to ceiling battens @ 400mm crs)*. R-value R-3.6 (estimate only). 150mm thick x 432mm wide x 1140mm long segments.

Pink® Batts® Silencer® Midfloor insulation is specifically designed to reduce noise transmission between floors.

Refer to product data - https://www.pinkbatts.co.nz/assets/Acoustic-Silencer-Product-Sheet-FEB20-RevD.pdf

Installed as inter-storey floor acoustic insulation to the locations shown on the drawings in accordance with the manufacturer's requirements.

Installed Location:

9.3.7 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with trades to install Pink® Batts® Insulation as required.

9.3.8 Workmanship

All installation work shall be carried out by registered PinkFit® installers; the preferred Pink® Batts® installers, or by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to:
https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

9.3.9 Delivery & Handling

Store the Pink® Batts® Insulation materials undercover, in a weatherproof environment, off the floor, on a flat, even surface in accordance with the manufacturer's requirements. Keep materials dry and protected from damage, moisture and contamination at all times.

For best practice, refer to Pink Batts Product and Installation Guides.
Further assistance contact 0800 746 522

Store the Pink® Batts® Insulation materials undercover, in a weatherproof environment, off the floor, on a flat, even surface in accordance with the manufacturer's requirements. Keep materials dry and protected from damage, moisture and contamination at all times.

Conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including the Workplace and facilities requirements

9.3.10 Installation

9.3.10.1 General

Install Pink® Batts® Insulation in accordance with NZS 4246.
All installation work shall be carried out by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to:
https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

9.3.10.2 Pink® Batts® Wall

Install Pink® Batts® Wall Insulation in accordance with NZS 4246.

All installation work shall be carried out by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to:

https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

9.3.10.3 Pink® Batts® Silencer® Midfloor

Install Pink® Batts® Silencer® Midfloor in accordance with NZS 4246.

All installation work shall be carried out by experienced and competent installers, familiar with the specified products and installation techniques, in accordance with the manufacturer's requirements, and to fully comply with all warranty requirements. For more information on best practice Pink® Batts® installation refer to:

https://www.pinkbatts.co.nz/resources/downloads/product-data-sheets

9.3.11 Completion

Check that all specified Pink® Batts® Insulation products have been installed correctly in accordance with the manufacturer's requirements.

Check for damage and defects - replace damaged and defective insulation as necessary to the required standard.

Ensure the installed insulation will be adequately protected for durability and performance in accordance with the manufacturer's warranty requirements.

Leave all of this work complete, and in the condition required for proper performance, including for the installation of subsequent linings, in accordance with the manufacturer's warranty requirements.

Leave adjacent surfaces and finished work clean and free of damage. Remove all associated rubbish and waste material from site.

Issue to the Owner a copy of the Pink® Batts® Lifetime Product Warranty for all Pink® Batts® Insulation products installed.

10 ROOFING

10.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

10.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1397:1993(AS/NZS)	Steel sheet and strip - hot-dipped, zinc-coated or aluminium/zinc-coated
1562.1:1992(AS)	Design and installation of sheet roof and wall cladding. Part 1: Metal
2295:2006(NZS)	Pliable, permeable building underlays
3604:2011(NZS)	Timber-framed buildings
NZMRM Code of Practice	NZ Metal Roof and Wall Cladding Code of Practice - Version 3.0

10.3 Roofing Systems - Profiled Steel

10.3.1 Scope

Supply the selected trapezoidal profile 0.55BMTxG300 galvanized steel roofing and install it to the areas shown on the Roof Plan. All handling and fixing techniques, and all jointing and sealing materials and techniques, shall be exactly as recommended by the roofing manufacturer.

10.3.2 Preparation

Co-operate to ensure that roof framing has appropriate spacings and fixings, is in accordance with NZS 3604, and coordinate to ensure that all timber members required for ridges, hips, valleys, barges, penetrations, junctions with vertical faces, etc. are correctly in place. Lap sheets away from the prevailing wind. Set-out the roofing sheets exactly square to the building axis and maintain this throughout the works.

10.3.3 Flashing

Ridges, hips, and barge flashings etc. shall all be matching galvanized steel, and as detailed. Soft edge flashings very neatly dressed down where required, plumbing penetrations custom flexible rubber flashed (fully sealed), and instruct the Plumber that no copper (or brass) pipes are to discharge on to the roof.

10.3.4 Completion

Protect the galvanizing from damage at all times; replace the whole sheet where a significant depth of the coating has been damaged. Completely clean off all drill and power saw swarf and pop-rivet shanks as the work proceeds (at least daily, and keep them and other rubbish out of the spoutings).

11 TILING

11.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

11.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

2358:1990(AS)	Adhesives - For fixing ceramic tiles
3103:1991(NZS)	Specification for sands for mortars and plasters
3122:2009(NZS)	Specification for Portland and blended cements (General and special purpose)
3661.2:1994(AS/NZS)	Slip resistance of pedestrian surfaces - Part 2: Guide to the reduction of slip hazards
3740:2010(AS)	Waterproofing of domestic wet areas
4586:2004(AS/NZS)	Slip resistance classification of new pedestrian surface materials
4858:2004(AS/NZS)	Wet area membranes
BRANZ Good Practice Guide	Tiling
NZBC B2/AS1	Durability
NZBC D1/AS1	Access Routes
NZBC E3/AS1	Internal Moisture

11.3 Tiling

11.3.1 Scope

Supply, install and finish all Tiling works, complete with all necessary components and accessories required for proper installation and performance, as specified herein and to the locations, layouts and details shown on the approved drawings. All aspects of this work shall be carried out to comply with the New Zealand Building Code and relevant standards, and in accordance with the approved project design documentation, and with any relevant product manufacturers' technical literature.

The following is a list and a general description of the extent of Tiling work, which are more specifically defined in the contract documents, required for the completion of the contract works:

11.3.2 Requirements

11.3.2.1 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of Tiling work are carried out to the highest standard.

11.3.2.2 Inspection & Acceptance of Tiling Work

Carry out all necessary pre-installation, installation and finishing inspections of Tiling for each area of work in accordance with the requirements of industry best practice recommendations and code of practice guidelines.

Complete all necessary Pre-Installation/Application Checklists prior to installing proprietary under-tile waterproofing systems and heating systems and floor levelling systems, and relevant Installation/Application Checklists.

Complete all necessary Installation/Application Sign-Off Certificates and before undertaking subsequent work or handing over.

11.3.2.3 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected Tiling materials and work shall be repaired and/or replaced to the satisfaction of the Architect/Designer, without delay and at no additional cost to the Principal.

11.3.2.4 Provision for Spare Tiles

Provision for Spare Tiles - refer to Reserve Material clause.

11.3.3 Performance

11.3.3.1 Slip-Resistance Performance of Access Routes

Slip-Resistance Performance of Access Routes. The slip-resistance performance of tiled access routes, ramps and stairs shall comply with the requirements of NZBC D1/VM1 and NZBC D1/AS1.

11.3.3.2 Interior Wet Area Performance

Interior Wet Area Performance. The performance of tiled interior wet areas shall comply with the requirements of NZBC E3/AS1.

11.3.4 Co-operation

Co-operate with other trades to ensure that all preliminary and preparatory works are completed to specification and as shown on the drawings.

Coordinate with other trades to install tiling as required, and to ensure that:
- appropriate tolerances and clearances allow for adjacent finishes, fixtures and fittings, etc; and
- penetrations for piped and cabled services are correctly located to maintain tile integrity and tiling performance.

11.3.5 Workmanship

Where required by the NZ Building Act 2004, it is the building contractor's responsibility to ensure that all restricted building work is carried out by a Licensed Building Practitioner.

All Tiling work shall be carried out to best trade practice by qualified and experienced tradespersons, familiar with the specified materials and installation and finishing techniques, in accordance with AS

3958.1 and relevant product manufacturers' technical literature, to the layout and details shown on the approved drawings, and to fully comply with all warranty requirements.

Submit evidence of experience on request, e.g. National Certificate in Floor and Wall Tiling, or certified member of Master Plasterers and Tilers Association.

All substrate preparation, tile laying and tiling accessories application and finishing techniques shall be exactly as recommended by the specified product manufacturer. All work shall be such as to leave a neat, efficient and robust installation.

Interior wet-area tiling shall be waterproof and installed over a waterproof membrane as shown on the drawings.
Exterior floor tiling shall be waterproof and weathertight, and where necessary installed over a waterproof membrane as shown on the drawings.

As recommended by the tile manufacturer, use only an approved adhesive that is compatible with the specified tile, its substrate and its application/use.

Where necessary, delay tiling to allow maximum curing and settling and initial creep of the substrates, particularly to load bearing structural elements.

Do not cover or bridge movement control joints with tiles and tile underlay.

Tiling shall not be undertaken when the ambient and surface temperatures are outside the specified product manufacturer's permissible temperature range.

Where necessary, mask off and protect from contamination adjacent surfaces, joinery, fixtures and finished work before commencing.

Exterior tiling shall not be undertaken during inclement weather. As necessary and in accordance with the manufacturer's requirements, protect exterior tiling from rain, hot dry winds and direct sunlight to aid proper drying and curing.

Leave all tiled surfaces clean, sound, and free from blemishes of any kind.

11.3.6 Delivery & Handling

Upon delivery to site, inspect the tile packs and reject those items that are found to be damaged, defective or contaminated. Contact the supplier for replacement of rejected items at time of delivery to site.

Do not use damaged, defective or contaminated materials, or products that are beyond their designated shelf life.

Store all tiling materials undercover, in a weatherproof environment, off the floor, on a flat, even and level surface in accordance with the manufacturer's requirements. Keep products and materials dry, out of direct sunlight and protected from damage, moisture and contamination at all times.

Handle tiling materials in accordance with the manufacturer's requirements and in a manner that prevents damage to and contamination of the materials and works.

Installers shall be familiar with and comply with all associated product Safety Data Sheet precautions for use, and use appropriate safety gear when handling materials.

Installers shall conform with all relevant WorkSafe NZ Guidelines and Codes of Practice - including General risk and workplace management - part 1.

11.3.7 Preparation

11.3.7.1 General

All substrates to be tiled shall be structurally sound, even and smooth, clean, dry, and free from dirt, dust, grease, oil, wax, paint residue, loose plaster and laitance, curing compounds and other materials and contaminants likely to affect the bonding and performance of the specified tile adhesive and grout.

Carry out all necessary moisture readings of substrates. Do not commence installation until the moisture readings for the whole area are below the required level.

Carry out all necessary substrate inspections and preparatory work in accordance with the relevant product manufacturer's recommendations prior to application.

Check that the substrate is free of voids and depressions, and is in correct alignment - true to line, level and/or plumb, and to the falls indicated on the drawings.

Check that all fixtures, fittings and embedded items are correctly installed, and that all substrate edges are completed as detailed.

Confirm the location of any movement control or crack control joints prior to commencement of the works, and ensure that they are appropriately trimmed. Do not cover or bridge movement control joints with tiles, adhesive and grout.

Allow self-levelling underlayments and mortar screeds to properly cure in accordance with the manufacturer's recommendations before commencing tiling.

Allow new concrete substrates to cure for at least four weeks prior to tiling.

Ensure that the back of each tile is clean and free from dust or other contaminants prior to laying.

The commencement of work on each section/area shall be deemed to indicate full acceptance by the Tiler that all preparatory works by other trades are appropriate to achieve the required finished results.

11.3.7.2 New Particle Board Floor

New Particle Board Floor - check all aspects of preparatory works, including but not limited to:
- Check that the sheets have been installed, jointed and fixed in accordance with the manufacturer's

requirements and indicated on the drawings, and that all sheet edges are fully supported.
- Check that the sheet joints are flush and even, and that all fixings are countersunk and filled with a compatible filler.
- Using a proprietary levelling compound, repair flush with smooth, feathered edges any damaged areas in the floor surface.
- Mechanically sand to remove all surface irregularities and contaminants likely to affect adhesion.
- Leave the surface completely clean and free of dust and contaminants, then fully prime the substrate with an appropriate primer in accordance with the particle board manufacturer's recommendations.

11.3.7.3 Plasterboard Wall Lining

Plasterboard Lining - check all aspects of preparatory works, including but not limited to:
- Check that the plasterboard sheets have been installed in accordance with the manufacturer's requirements, are supported on all edges on framing, are securely fastened, and that all joints and junctions have been stopped flush with reinforcing tape embedded in the jointing compound.
- Check junctions with all other substrates and elements, ensuring that all necessary works have been completed as detailed.
- Check that all apertures, openings, edges and expansion and movement control joints are completed as detailed.

11.3.8 Installation

11.3.8.1 Floor Tiles

Floor Tiles. Install floor tiles by direct-stick method to clean, dry and properly prepared substrates in accordance with AS 3958.1 and the adhesive manufacturer's instructions. Accurately set-out and lay tiles to the layout and details shown on the drawings. Confirm the floor tile layout and pattern requirements prior to installation.

As required by the adhesive manufacturer, seal or prime porous substrates or substrates where dusting or powdering exists. The use and application of adhesive shall be exactly to the adhesive manufacturer's instructions.

All tile cutting, boring and shaping shall be carried out using appropriate tools and equipment and methods suitable for the tile type and in accordance with the tile manufacturer's recommendations. Only install cut tiles that have smooth, uniform cut edges - do not use tiles with jagged or flaked edges.

Mechanically mix powdered adhesive at the recommended ratio with clean potable water to a smooth, lump-free paste in accordance with the manufacturer's requirements. Do not mix more than can be used within the specified open time.

Apply tile adhesive evenly using a suitably notched trowel to properly prepared substrates in accordance with the manufacturer's instruction.
- Do not apply more adhesive than can be covered within the specified open time.
- Do not over spread the adhesive, and avoid surface skinning - particularly when used in

unfavourable conditions such as direct sunlight, wind and/or high temperatures.
- Ensue to follow the adhesive manufacturer's recommended setting and curing periods.

Lay floor tiles into adhesive to achieve maximum contact and bonding before skinning occurs. Re-trowel any adhesive that has skinned - do not apply water to skinned adhesive. Where necessary, back-butter tiles with adhesive to ensure maximum contact and bonding - do not spot-fix floor tiles.

Floor tiles shall be laid so that the finished surface and edges are true and even, level and/or to the falls shown on the drawings, and finished flush with adjoining finished work as appropriate or as detailed.

Tile joints shall be to the required layout, uniform, accurately aligned, straight and true to line, and set even and parallel to the specified joint width.

Where indicated on the drawings, return floor tiles along walls, upstands, toe spaces, etc., to the height and details shown on the drawings.

Remove excess adhesive from tile joints as each tile is laid to ensure full depth grouting can be achieved, and leave the tile surface completely clean.

11.3.8.2 Wall Tiles

Wall Tiles: Install wall tiles by direct-stick method to clean, dry and properly prepared substrates in accordance with AS 3958.1 and the adhesive manufacturer's instructions. Accurately set-out and lay tiles to the layout and details shown on the drawings. Confirm the wall tile layout and pattern requirements prior to installation.

As required by the adhesive manufacturer, seal or prime porous substrates or substrates where dusting or powdering exists. The use and application of adhesive shall be exactly to the adhesive manufacturer's instructions.

All tile cutting, boring and shaping shall be carried out using appropriate tools and equipment and methods suitable for the tile type and in accordance with the tile manufacturer's recommendations. Only install cut tiles that have smooth, uniform cut edges - do not use tiles with jagged or flaked edges.

Mechanically mix powdered adhesive at the recommended ratio with clean potable water to a smooth, lump-free paste in accordance with the manufacturer's requirements. Do not mix more than can be used within the specified open time.

Apply tile adhesive evenly using a suitably notched trowel to properly prepared substrates in accordance with the manufacturer's instruction.
- Do not apply more adhesive than can be covered within the specified open time.
- Do not over spread the adhesive, and avoid surface skinning - particularly when used in unfavourable conditions such as direct sunlight, wind and/or high temperatures.
- Ensue to follow the adhesive manufacturer's recommended setting and curing periods.

Press wall tiles into adhesive to achieve maximum contact and bonding before skinning occurs. Re-trowel any adhesive that has skinned - do not apply water to skinned adhesive. Where necessary, back-butter tiles with adhesive to ensure maximum contact and bonding - do not spot-fix wall tiles.

Wall tiles shall be installed so that the finished surface and edges are true and even, level, and finished flush with adjoining work as appropriate or as detailed.

Tile joints shall be to the required layout, uniform, accurately aligned, straight and true to line, level and plumb, and set even and parallel to the specified joint width. Use proprietary tile spacers, sized for the specified joint width, to ensure accurate jointing.

Form internal and external wall corner junctions true and plumb and with tile joints continued around corners level and true.

Remove excess adhesive from tile joints as each tile is laid to ensure full depth grouting can be achieved, and leave the tile surface completely clean.

11.3.8.3 Edge Trim

Edge Trim. As required and indicated on the drawings, install all necessary tiling edge trim - including edge cappings, corner mouldings, transition strips, etc., - all neatly finished, accurately aligned and true, to the required layout and as detailed on the drawings.

11.3.8.4 Stairs & Steps

Stairs & Steps. Accurately lay tiles to steps and stair treads, risers and landings as detailed on the drawings. Finish tiles neatly along tread/riser junctions and against trim. Ensure that the tile joints on treads and risers are aligned, straight and true along each stair flight. As indicated on the drawings, install nosing tiles or proprietary stair-nosings to treads.

11.3.8.5 Movement Control Joints

Movement Control Joints. Form movement control joints in tiling to the locations and details shown on the drawings and in accordance with AS 3958.1.

Movement control joints in tiling shall coincide with control joints in the substrate and structure, and at junctions between dissimilar substrates and other surface finish materials in the same plane.

Ensure to carry movement control joints through tiling from the substrate. Do not bridge movement control joints with underlayment, membranes, adhesive or tiles.

Seal movement control joints after grouting with the specified flexible sealant in accordance with the sealant manufacturer's instructions and as detailed.

Proprietary movement control joints shall be installed in strict accordance with the manufacturer's instructions and to the layout and details shown on the drawings. Finish tiling against proprietary movement control joints as detailed.

11.3.8.6 Grouting

Grouting. Grouting shall be in accordance with the grout manufacturer's requirements and recommendations. Coloured grout shall be to the colour specified.

Prior to grouting, ensure that the tile adhesive has completely set, and that the tile joints are clean, dry and free from excess adhesive and any foreign material. Rake out any excess adhesive from joints to ensure a maximum, uniform grout joint is achieved. Tile spacers must be removed prior to grouting.

Mechanically mix powdered tile grout with clean water at the required ratio to a smooth, lump-free paste in accordance with the manufacturer's requirements. Do not mix more than can be used within the manufacturer's specified open time. Ensue to follow the manufacturer's recommended drying and curing periods.

Apply tile grout evenly with a rubber squeegee or grouting float, ensuring that the tile joints are completely filled and smoothed to a dense, uniform surface. Do not spread more grout than can be cleaned within the specified open time. Remove excess grout immediately. In hot or windy conditions, dampen the joints to prevent the grout from drying out too quickly.

Clean the tiles with a damp sponge when the grout joints have firmed, making sure not to wash-out the joints. Finish grout joints to a smooth, uniform effect and leave grout free of pin holes and blemishes.

Allow grout joints to dry before cleaning with a clean, dry, soft cloth, to completely remove any grout haze and residue from the surface of the tiles.

11.3.8.7 Protection

Protection. Take all necessary measures to protect exterior tiling from the extremes of weather and climate during the fixing and grouting operation and for as long as possible thereafter.

Keep the working area cordoned off during the whole tiling installation. Protect completed tiling from excessive loads, damage and contamination until hand-over or as directed.

Restrict foot traffic from completed floor tiling in accordance with the tile manufacturer's time frames for 'set-to-light-foot-traffic' and 'ready-for-service-use'.

Where necessary, cover completed floor tiling with a heavy-duty temporary floor protection such as Ovaboard, Ram Board, Buffalo Board; laid in accordance with the manufacturer's requirements.

Protect exterior tiling, immediately after laying and grouting, from rain and moisture for at least 24 hours, and from frost and strong sunlight after laying in accordance with the tile adhesive and grout technical specifications.

11.3.9 Completion

Check that all Tiling work has been correctly installed to the required layout, and that all tile joints, edge-trimming and other detailing is correctly finished, grouted and sealed.

Check all Tiling installations for damage, marks and defects - repair or replace as necessary. Carry out any repairs to the required standard.

Thoroughly clean tiled surfaces in accordance with the manufacturer's recommended procedures and techniques. Lightly buff where appropriate.

Leave this work complete and to the required standard, and in accordance with the associated warranty requirements.

Clean up thoroughly, and leave adjacent surfaces and finished work clean and free of damage and contamination. Remove all associated rubbish from site.

Protect the completed installation from damage, trafficable dirt and grime, and stains as necessary until hand-over as scheduled or directed.

Issue to the Owner a copy of all relevant product manufacturers' maintenance requirements, and a copy of relevant manufacturer Product Warranties and the installer/applicator Installation Warranty for the installed products and completed works.

12 PLUMBING

12.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

12.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1221:1997(AS/NZS)	Fire hose reels
1254:2010(AS/NZS)	PVC-U pipes and fittings for stormwater and surface water applications
1260:2017(AS|NZS)	PVC-U pipes and fittings for drain, waste and vent applications
1477:2017(AS|NZS)	PVC pipes and fittings for pressure applications
1546.1:2008(AS/NZS)	On-site domestic wastewater treatment units - Septic tanks
1596:2014(AS/NZS)	The storage and handling of LP Gas
2032:2006(AS/NZS)	Installation of PVC pipe systems
2033:2008(AS/NZS)	Installation of polyethylene pipe systems
2492:2007(AS/NZS)	Cross-linked polyethylene (PE-X) pipes for pressure applications
2537.1:2011(AS/NZS)	Mechanical jointing fittings for use with crosslinked polyethylene (PE-X) for pressure applications - Part 1: Plastics piping systems for hot and cold water installations - Crosslinked polyethylene (PE-X) - General
2642.2:2008(AS/NZS)	Polybutylene pipe systems - Polybutylene (PB) pipe for hot and cold water applications
2712:2007(AS/NZS)	Solar and heat pump water heaters - Design and construction
3500.1:2015(AS|NZS)	Plumbing and drainage - Part 1: Water services
3500.1:2018(AS|NZS)	Plumbing and drainage Part 1: Water services
3500.1:2021(AS/NZS)	Plumbing and drainage, Part 1: Water services
3500.2:2015(AS|NZS)	Plumbing and drainage - Part 2: Sanitary plumbing and drainage
3500.2:2021 (AS|NZS)	Plumbing and drainage Part 2: Sanitary plumbing and drainage
3500.2:2021(AS|NZS)	Plumbing and drainage, Part 2: Sanitary plumbing and drainage
3500.3:2018(AS|NZS)	Plumbing and drainage Part 3: Stormwater drainage
3500.3:2021(AS|NZS)	Plumbing and drainage, Part 3: Stormwater drainage
3500.4:2015(AS|NZS)	Plumbing and drainage - Part 4: Heated water services
3500.4:2018(AS|NZS)	Plumbing and drainage Part 4: Heated water services
3500.4:2021(AS|NZS)	Plumbing and drainage, Part 4: Heated water services
3501:1976(NZS)	Specification for copper tubes for water, gas, and sanitation

4020:2018(AS|NZS)	Testing of products for use in contact with drinking water
4121:2001(NZS)	Design for access and mobility: Buildings and associated facilities
4517:2010(NZS)	Fire sprinkler systems for houses
4602:1988(NZS)	Low pressure copper thermal storage electric water heaters
4603:1985(NZS)	Installation of low pressure thermal storage electric water heaters with copper cylinders (open-vented systems)
4606.1:1989(NZS)	Storage water heaters - General requirements
4607:1989(NZS)	Installation of thermal storage electric water heaters: valve-vented systems
4613:1986(NZS)	Domestic solar water heaters
4614:1986(NZS)	Installation of domestic solar water heating systems
4617:1989(NZS)	Tempering (3-port mixing) valves
4692.1:2005(AS/NZS)	Electric water heaters - Energy consumption, performance and general requirements
5601.1:2013(AS|NZS)	Gas installations - Part 1: General installations
7602:1977(NZS)	Specification for polyethylene pipe (Type 5) for cold water services
7643:1979(NZS)	Code of practice for the installation of unplasticized PVC pipe systems
7646:1978(NZS)	Specification for polyethylene pipes and fittings for gas reticulation
AS/NZS 3500.5:2012	Plumbing and drainage - Part 5: Housing installations
NZBC B2/AS1	Durability
NZBC G11	Gas as an Energy Source
NZBC G12	Water Supplies
NZBC G13/AS1	Sanitary Plumbing

12.3 General

Carry out all works necessary to leave the water, waste, vent and soil systems serving the sanitary fittings and the plumbing hardware shown on the drawings or specified below in correct working order complete with all ancillary systems (safetrays, floor drains, overflows, relief valves, etc.) required, and with all normal incidentals customarily installed by this trade.

Comply with the Building Code, Territorial Authority By-laws and statutory authority Regulations as appropriate. Obtain all necessary permits and consents, serve all necessary notices, arrange for all tests and pay all fees and customary charges in connection with the required works.

12.4 Workmanship

12.4.1 Co-operation

Co-operate with all other trades. Attend upon Concretor, Drainlayer and Carpenter to set out the exact positions of pipe runs before adjacent work is put in hand, and to ensure that all pipes, sleeves, fixings, flashings etc. are correctly incorporated into the structure as construction proceeds.

12.4.2 Workmanship

All plumbing work shall be carried out by, or under the direct control of, properly qualified tradesmen, and shall be to recognised high standards.

Observe best local trade practice to avoid problems which arise from freezing winter conditions.

The cutting away and checking of timbers shall be limited to such dimensions as will not prejudice the purpose for which the timber is used; observe NZS 3604 restrictions on the holing and checking of joists and beams. Chasing and checking of other materials only to approval. Install seismic restraints to storage tanks and HWCs.

Weatherseal wherever pipes, screws, bolts or other fastenings penetrate an external surface, and particularly roofing; seal with gaskets, flashings (and overflashings if necessary) or mastic as appropriate - any damage that results from failure of such seals will be made good at the Plumber's expense.

Adequately protect all surfaces. Any damage to fittings or surfaces made good by the appropriate trade at the Plumber's expense.

12.4.3 Pipework

Joints between pipes of different materials shall always be to the approval of the TA Plumbing Inspector.

Pipework set-out neatly with a minimum number of bends, and more or less parallel to and at right angles to structural elements - avoid diagonal piping.

All internal pipework shall be concealed except where otherwise is either shown or approved. Exposed pipework shall be accurately and neatly run. Arrange all pipework (and particularly traps) in a manner which will allow maximum future accessibility for repairs or maintenance. Arrange for access panels to any primary maintenance positions, and install conveniently located isolating valves for each group of fittings. Wingbacks securely and squarely fixed. Crox unions usually acceptable only at the final connection to fittings. Install white plastic flanges where pipes penetrate linings in visible locations.

Where pipes are covered with nail fixed linings and trim ensure that their positions are marked on the linings to minimise the risk of subsequent nailings penetrating the pipe. Any such damage shall be rectified immediately, with all consequential damage made good.

Set pipework out in straight runs to even gradients. Fix all pipes to the structure sufficiently to fully support and to prevent sagging or vibration. Clips and saddles shall be the same material as the pipe. Exterior pipes on stand-off brackets. Fixings to the exterior or damp locations shall all be hot dip galvanized unless otherwise noted. Sleeves for pipes or drains penetrating concrete or masonry shall be uPVC, 20mm minimum larger internal diameter than the external diameter of the pipe, finished flush with concrete or masonry, and packed and mastic sealed.

Close open ends of the systems during construction to prevent the entry of foreign matter.

12.4.4 Temperature Movement

All work shall respect in full all probable thermal movements - layouts, fixings and jointings shall be arranged to allow thermal movement without risk of prejudice to watertight conditions, or risk of damage from straining of the pipes which will generate failures.
In particular, observe best local trade practice to avoid problems arising from freezing conditions.

12.4.5 Excavation

Allow to carry out all excavation that is required to suit the services installed by this trade. Check for other services before excavation. Trenches true to line and level, base of trenches clear of loose material, and shore trenches as required to suit the ground conditions. Backfilling shall be carried out by this trade, and be to the requirements specified in Siteworks.

12.4.6 Fire Wall/Ceiling Penetrations

Ensure that where drainage pipe work penetrate through fire rated floor or wall areas that these penetrations are stopped with intumescent foaming sealant for joints up to 10mm, and with intumescent stopping putty where the gap exceeds 10mm. Where required fit approved intumescent type fire collars to pipes located such that the fire rating of the wall or ceiling is maintained.

12.4.7 Testing

All plumbing services shall be completed in stages which will allow for proper testing under normal working pressures prior to the application of insulation, concealment or other enclosure. Testing of piped water services shall be by hydrostatic testing in accordance with AS/NZS 3500.1 and shall not show any leakage when subjected to a hydrostatic pressure of 1500kPa for a period of not less than 30 minutes. All leaks remedied and retested. On completion the whole of the plumbing services to be subjected to full operational tests in the presence of the plumbing inspector, with any defects revealed in these tests properly remedied.

12.4.8 Warranties

Warranty cards and manufacturer's guarantees for all items supplied and installed by this trade shall be correctly filled in and handed over at Practical Completion.

12.5 Systems

12.5.1 Wastes & Vents

Fit bird proof domes to all vents.

12.5.2 Cold Water System

12.5.2.1 Supply From New Connection to Reticulated Supply

All cold water supply pipework shall be medium/high-density polyethylene (MDPE/HDPE), arranged and fixed so that all joints are in a fully ‘relaxed' condition, without any stress or tension.
Make complete arrangements for the installation of a new connection to the reticulated supply in the street and the main feed and toby in the position shown. Lay on a 20mm main from the toby along the route shown on the Site Plan to the connection position noted on the Floor Plan (pipe depth, protection, backfilling, signal strip etc. to comply with all Supply Authority requirements). At the

connection position take a branch feed off for the hosecocks (and reticulate to the positions shown and install angle hosecocks) and toilet cisterns and then take the main feed through an accessibly positioned cleanable in-line sediment and dirt filter.
Primary distribution from the water filter shall be in 20mm piping, reducing to 15mm for the final feed to individual items. Install conveniently located isolating valves to turn off each group of fittings, and install a small isolating valve alongside each toilet cistern not integrally fitted with one. (Note that these isolating valves and the hosecocks are not covered by the Plumbing Hardware Prime Cost Sum).

12.5.3 Hot Water System

12.5.3.1 Electric Storage, High Pressure Hot Water Cylinder

Supply the electric storage high pressure hot water cylinder noted on the drawings and install it where shown. Where appropriate install the cylinder on a safetray, with its drain discharging in a visible location.
Install temperature and pressure relief valves, cold water expansion valves, flow control valves, line strainers, pressure limit valves, and non-return/isolating valves as required to leave the hot water system in full design operational order. Install a tempering valve for each cylinder to control the hot water temperature at any sanitary fixture used for personal hygiene at not more than 50°C.
Check that the water pressure is suitable for the cylinders operation, and install PRV's if excessive.
Pressure relief discharges shall be copper and to the exterior in approved positions.
Flush all pipework before making the final connections. Lag the main distribution pipes full length with wall pipe insulation.
Showers shall have priority feeds, without 'tees', and the pipework layout shall ensure that the showers temperature and pressure remain as even as possible.
Irrespective of whether a mixing device is installed, the storage water heater control thermostat shall be set at a temperature of not less than 60°C to prevent the growth of Legionella bacteria.

1 3 D R A I N A G E

13.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

13.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1254:2010(AS/NZS)	PVC-U pipes and fittings for stormwater and surface water applications
1260:2017(AS|NZS)	PVC-U pipes and fittings for drain, waste and vent applications
1546.1:2008(AS/NZS)	On-site domestic wastewater treatment units - Septic tanks
1547:2012(AS/NZS)	On-site domestic wastewater management
2032:2006(AS/NZS)	Installation of PVC pipe systems
3500.2:2018(AS|NZS)	Plumbing and drainage Part 2: Sanitary plumbing and drainage
3500.3:2018(AS|NZS)	Plumbing and drainage Part 3: Stormwater drainage
7643:1979(NZS)	Code of practice for the installation of unplasticized PVC pipe systems

13.3 General

Carry out all required works to leave the sewer and stormwater systems shown on the drawings in correct working order complete with all normal incidentals.

Comply with Local Authority By-laws and Health Department Regulations as appropriate. Obtain all necessary permits and consents, serve all necessary notices, arrange all tests and pay all fees and customary charges in connection with the works.

13.4 Workmanship

13.4.1 General

Carry out all required works to leave the sewer and stormwater systems shown on the drawings in correct working order complete with all normal incidentals. Comply with Local Authority By-laws and Health Department Regulations as appropriate. Obtain all necessary permits and consents, serve all necessary notices, arrange all tests and pay all fees and customary charges in connection with the works.

13.4.2 Co-operation

Cooperate with all trades and attend upon the Concretor and Plumber to set out exact pipe runs before any adjacent work is put in hand and ensure that all sleeves etc. are correctly incorporated as work proceeds.

13.4.3 Materials

All pipes and other materials shall comply with the appropriate Standards, and shall be protected from damage of any kind until installation is complete. All incidentals appropriate for the applications involved. Concrete shall be 17.5MPa and as specified under Concretor, Mortar shall be as specified in Blocklayer.

13.4.4 Workmanship

All drainlaying shall be carried out by, or under direct control of, properly qualified tradesmen, and shall be to recognised high standards. Ensure cast-in items are installed when required so that no delay is caused by this trade. Adequately protect all adjacent surfaces - clean down to remove dirt etc., and any damage shall be made good by the appropriate trade at the Drainlayer's expense.

On completion of drainlaying clean up full area affected by this trade to the condition it was in before drainlaying commenced.

Site is to be returned as close as possible to its present condition on completion of the contract.

13.4.5 Excavation

As required for sewer and stormwater. Check for other service lines before excavation - the Drainlayer is responsible for making good any damage. Trenches true to line and with even gradients between gullies, soil stack terminations or downpipes, etc.

Keep the bottom of trenches clear of loose material. All pipes shall be laid in appropriate bedding material, compacted as required. Shore trenches if required to suit ground conditions. Backfilling shall be by this trade, to the standards required in Siteworks.

13.5 Drainlaying Elements

13.5.1 Drainlaying

Commence drainlaying at the low end of even fall sections of drains and proceed in a continuous sequence to the fittings connections.

Sumps, gullies, etc. solidly bedded. Lay 110mm uPVC drains to connect gullies, sumps, stacks, and downpipes through to the street edge connections.

Every junction and bend shall be an inspection position. Temporarily seal the open ends of incomplete drains to prevent entry of foreign matter. Make appropriate provision for any anticipated differential settlement. Place signal strip above all drains.

Ensure that stormwater drains are very accurately positioned so that downpipes can drop directly into them, without offsets.

13.5.2 Testing

The sewer and stormwater systems shall both be fully tested to the approval of the Territorial Authority Inspector before being covered in. If any defects show rectify and then fully retest.

13.5.3 As Built Drawings

During drainlaying plot the location of all bends and changes in direction and all cleaning access positions. Locate each item by two diagonal measures from structure corners, etc. and record on a blank plan copy (supplied by Architect/Designer when requested).

Note that Practical Completion of the contract will not be certified until this as-built drawing has been produced (made available to the Contractor in time for the Code Compliance Certificate application.

14 ELECTRICAL

14.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

14.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

2053.1:2001(AS/NZS)	Conduits and fittings for electrical installations - General requirements
2201.1:2007(AS/NZS)	Intruder alarm systems - Client's premises - Design, installation, commissioning and maintenance
2293.2:2019(AS|NZS)	Emergency lighting and exit signs for buildings - Part 2: Routine service and maintenance
3000:2018(AS|NZS)	Electrical installations - Known as the Australian/New Zealand Wiring Rules
3100:2009(AS/NZS)	Approval and test specification - General requirements for electrical equipment
3112:2011(AS/NZS)	Approval and test specification - Plugs and socket-outlets
5000.1:2005(AS/NZS)	Electric cables - Polymeric insulated - For working voltages up to and including 0.6/1 (1.2) kV
60335.2.30:2015(AS|NZS)	Household and similar electrical appliances - Safety - Part 2.30: Particular requirements for room heaters
60335.2.30:2015(AS|NZS)INCIEC	Household and similar electrical appliances - Safety - Part 2.30: Particular requirements for room heaters
60335.2.35:2013(AS/NZS)	Household and similar electrical appliances - Safety - Part 2.35: Particular requirements for instantaneous water heaters
60598.2.2:2016(AS|NZS)	Luminaires - Part 2.2: Particular requirements - Recessed luminaires
6104:1981(NZS)	Specification for emergency electricity supply in buildings

14.3 Workmanship

14.3.1 General

Supply and install all materials, including all necessary minor and incidental items, for proper completion of all of the electrical services specified or shown on the drawings. The contract will not be deemed to be complete until the Electrician has provided an Electrical Certificate of Compliance (made available to the Contractor in time for the Code Compliance Certificate application).

Obtain all necessary permits and consents, serve all notices and pay all fees in and customary charges connection with the works.

The position of switches, light and power outlets and other fittings, although shown specifically in some instances, are in general only shown diagrammatically. The exact location of each of these items will be as directed on site by the Architect/Designer; the Electrician shall give reasonable notice of when this information is required. Items positioned in contravention of this shall be repositioned if directed, including rewiring if necessary, all at the Electrician's expense.

Unless drawn (on 1:20 wall elevations) or specified otherwise the mounting height to the centreline of the following items above the floor shall be:

-1000mm for lighting switches;
-2000mm for wall mounted lights;
-2100mm for the bayonet of pendant lights;
-300mm for power points, except at benches.

(Notify the Architect/Designer if either the actual fitting or mounting position seem to make the mounting height noted above inappropriate).

Warranty cards and manufacturers guarantees for items supplied and installed by this trade shall be filled in correctly and handed over at Practical Completion. Arrange all circuits to obtain an optimum balance of the system, and check and reconnect where necessary to achieve this on completion. Leave the works clean and tidy and in full operational order.

14.3.2 Co-operation

Co-operate with all other trades and attend upon the Concretor and Carpenter to set out all required penetrations and to ensure that all wiring and fittings are correctly incorporated as work proceeds. The Carpenter will provide and fix all necessary dwangs and timber supports in locations determined by the Electrician.

14.3.3 Workmanship

All electrical work shall be carried out by, or under the direct control of, registered tradesmen, and shall be to recognized high standards. All work shall be such as to leave a neat, efficient and robust installation. Neatly label switchboards to identify each circuit.

The cutting away and checking of timbers shall be limited to such dimensions as will not prejudice the purpose for which the timber is used; observe NZS 3604: 2011 restrictions on the holing and checking of joists and beams. Chasing and checking of other materials shall be only to approval.

Adequately protect all surfaces. Any damage to fittings or surfaces made good by the appropriate trade at the Electrician's expense.

14.3.4 Wiring

Joints within cable runs will not normally be accepted. TPS cable shall be adequately supported, and clipped at regular intervals. At terminations all strands of conductors shall be fully secured in a terminal block or clamped under a screw head washer; do not cut away any strands. Wiring which terminates in enclosed fittings and/or where subject to heat liable to cause deterioration, shall be

high temperature type, with the tails made off with heat resisting sleeves, to protect the permanent wiring.

Wire lights in 1.5mm 3 core - 7.5 amps loading max per circuit (allow for 100w to all light fittings unless identified otherwise).
Wire power outlets in 2.5mm 3 core - 7 maximum GPO singles or doubles per circuit. Assess power outlets for specific equipment and allow accordingly.

Conceal all wiring except as noted on drawings or below. All wiring cast into concrete shall be run in conduit pipes. All cables shall be stranded (single core is unacceptable).

Wire more or less parallel to and at right angles to the structural elements - avoid any diagonal wiring. Layout of the principal distribution wiring shall be to approval. Position all wires to minimise the risk of damage from subsequent nailing of linings etc.

Generally, do not run TPS horizontally within timber walls except in the area up to 300mm above floor. Wire in the ceiling framing and drop vertically to outlets and switches.

Do not run TPS horizontally within partitions except in the area up to 300mm above floor. Wire in the ceiling void and drop vertically to outlets and switches. Principal wiring in the ceiling void shall be supported on adequate catenaries.

Wire exterior lighting in screened cable.

Where cables pass through fire rated walls or floors use a fire barrier or fire rated sealing compound to seal the space after installation of the cables.

14.4 Systems

14.4.1 Earth

Provide a driven main earth suitable for the full installation, close to the meterboard, complying fully with all appropriate regulations and to the complete approval of a certified inspector. Bond all exposed metals, including light fittings and piped services and provide earth conductors for the entire system. Sheathing to any neutral screened cables may be used for earthing.

14.4.2 Mains

Install a neutral screened 16mm main cable underground (depth, cover/protection, backfilling, signal strip etc. to comply with all relevant regulations) from the grid connection position noted on the Site Plan along the route indicated to the meterboard, positioned where shown on the Floor Plan, and make appropriate arrangements for the grid connection. Install pilot as required. The meterboard shall be metalclad with a meter reading window, recessed maximum depth into the wall and at 2m to the top of the board, with the meters and water heater controllers by the supply company nominated by the Principal. Install all switches and fuses that are necessary. From the meterboard run (route to approval) a neutral screened 16mm main plus controllers etc. to the switchboard.

14.5 Materials & Control

14.5.1 Materials

All materials delivered with packaging and labeling intact. All required incidentals (insulating tape, seals, fixings, etc.) shall be completely appropriate for the application involved. The use of items damaged in any way is subject to approval in each instance.

14.5.2 Switchboard

The switchboard shall be an appropriate size standard PDL DBF series board installed fully recessed where shown and at 2m to the top of the board. Install appropriate sized MCB's for all circuits, including a minimum of two power and one lighting RCDs as required to cover all outlets.